


Bull Run Dam 2 Tower Improvements

Contract Manager/General
Contractor (CM/GC)
Guaranteed Maximum
Price (GMP)

December 14, 2011




The Bull Run Management Unit



Habitat Conservation Plan (HCP)


- Adopted by PWB April 2009.
- Outlined tasks to mitigate impacts of the dams.
- HCP prescribes water temperatures for the Bull Run River.
- Modifying intake towers is necessary to achieve prescribed river temperatures.
- Only HCP in the nation allowed off-site mitigation measures in lieu of providing fish passage.




Dam 2 Current Conditions

- Completed in 1962.
- 145' Tall Earthen Fill Dam.
- Two intake towers , 150' upstream of the dam.
- North Tower is higher capacity.
- South Tower largely used as backup.
- Each tower intake is located the bottom of the reservoir.

Dam 2 Towers - 1959




Dam 2 Towers - 2011



Project Team

- Owner, Portland Water Bureau (PWB)
- Procurement Services
- Design Consultant, Black and Veatch (B&V)
- CM/GC Contractor, Advanced American Construction (AAC)



South Tower Project Elements

- Install access and safety improvements South Towers.
- Fish Flow piping at the Headworks facility.

CM/GC Contract Strategy

- Shall not exceed GMP.
- Time and Material - Only pay what is actually invoiced.
- Savings clause. All funds less than GMP will be divided by PWB and AAC.
- Savings allocation; 75% PWB – 25% AAC

Main Cost Drivers

- Site is in the Bull Run Watershed and remote.
- Project is one of a kind.
- 15 story, steel structure with unique gates and controls.
- Wetwell installation requires diving to 100 foot depth. This depth of dive is challenging and expensive.
- Work on going while the other tower is providing water to town, can not drain the reservoir.
- Water quality requirements for both people and fish.

Project Cost Estimate History

Two Tower Option

➤ October 2008 – HCP Estimate

• \$10 Million + \$4.5 Million = \$14.5 Million

(Original (10% Design) estimate + Fish Flow Piping)

One Tower Option*

➤ August 2011 – 90% Design

➤ \$27 Million + \$4.5 Million = \$31.5 Million

(90% Design estimate + Fish Flow Piping)

*Includes access improvement to South Tower and Fish Flow Piping.

Comparison of Selective Withdrawal System on Local Dams

	Shasta Dam –	Cougar Dam	Round Butte Dam
Owner	US Bureau of Reclamation	Portland District, USACE	Portland General Electric
Cost	\$80M	\$55M	\$110M
Construction Period	2 Years	3 Years	3 Years
Year Completed	1997	2005	2010
Type	Selective withdrawal structure attached over intake gates of the powerhouse.	Selective withdrawal structure attached over existing intake structure.	Selective withdrawal structure over existing intake structure with floating fish capture and re-direction facility.
Configuration	Shutter Structure – (5) Units totaling 250' long, 50' wide, and 300' high. Lower Level Intake Structure – (3) Units totaling 125' long, 50' wide, and 170' high.	Concrete wet well 50' wide, 50' long, and 300' high attached to upstream face of existing intake structure.	Selective Withdrawal Bottom Structure at 68' long, 57' wide, 67' high. 40' diameter Steel Conduit. Selective Withdrawal Top Structure at 150' long, 90' wide, and 50' high. 287' access bridge.
Construction Type	Work performed at full reservoir with diver	Work performed in an empty reservoir. Seasonal	Work performed at full reservoir with diver

Budget Constraints

- Program Budget for FY 11-12, 12-13, 13-14;
\$33.1 Million
- Actions taken to keep the project within budget.
 - Modify Headworks piping to provide Fish Flow.
 - Eliminate wetwell installation from the South Tower.

Project Phasing

- Broke project into parts due to uncertainty with UV Variance.
- **Part 1:** North Tower, South Tower work (\$27 Million).
- **Part 2:** Fish Flow Piping at Headworks (\$4.5 Million).

Potential Costs

Maximum cost (GMP) - \$31.5M
Towers (Part 1) + Fish Flow Piping (Part 2)
\$27M + \$4.5M

Most probable cost - \$29.5M
\$25M + \$4.5M

Lowest probable cost - \$27.5M
\$23M + \$4.5M

Anticipated Notice to Proceed 1/15/12
Anticipated Construction Completion 12/31/13

Environmental Controls

- Erosion Control installed around the impacted site (silt fence, wattles, hay, gravel pads)
- All equipment entering the watershed will be cleaned prior to entering the watershed. Cleaning station will be located just outside of the watershed.
- Specifications comply with the Water Bureau's **Aquatic Invasive and Nuisance Species Standard Operating Procedure**.
- Silt Curtain will surround the North Tower Work. No sediment will leave the work zone. We have groundwater as a back-up.
 - Excavation will take 4–6 weeks.
 - Armor Flex will take 2-3 weeks.


Temporary Work Dock Installation Lake Pend Oreille, Idaho



550,000 LB Gate Lift (Section 1 of 4) John Day Dam Gate Replacement Project



Typical Dive Barge & Crane Barge Setup Gig Harbor Project



Dive Crew – Gig Harbor Project



Dive Crew – Gig Harbor Project



Dive Crew – Gig Harbor Project (Decompression Chamber in Connex)




Diver - Lake Oswego Interceptor Sewer Project



Diver - Lake Oswego Interceptor Sewer Project



Diver - Lake Oswego Interceptor Sewer Project



Thank you
Questions?