# City of Portland, Bureau of Development Services Field Issuance Remodel (FIR) Program Application Permit

SITE ADDRESS: 3245 NE 40 th Ave JOB/REFERENCE #:				
PROPOSED SCOPE OF WORK ( Please be as detailed as possible. Attach extra sheet as needed):  Garage Retrofit				
PROJECT VALUATION: \$ 49,995 new added square footage				
Please read the following and check the boxes that apply:				
1. The proposed work includes ( Please include Site Plan And Affected Elevations): Please check which applies:				
☐ footprint changes.				
□ a new detached accessory structure				
<ul> <li>physical changes to the street facing façade</li> </ul>				
□ in-ground swimming pool				
2. Any Proposed Addition requires a consideration for storm water disposal				
The existing rain drains terminate (Please check which applies):				
☐ On site ☐ To street ☐ To hubs				
3. The types of Projects noted below cannot be Permitted through FIR (contact a FIR Inspector for Specific questions or Special Conditions): creation of accessory dwelling units, fire repairs, conversion of single-family residences to duplexes, houseboats, manufactured dwellings, shared garages.				
NAME OF COMPANY: HAMIER HAND				
ADDRESS: 1020 SE HARRISON ST				
NAME OF APPLICANT (on site Project Manager) :				
OFFICE PHONE: FAX:				
MOBILE PHONE: 503 - 803 - 860/ Site Plan Attached				

Statement of Fact: I certify that the facts and information set forth in this application are true and complete to the best of my knowledge. I understand that any falsification, misrepresentation or omission of fact (whether intentional or not) in this application or any other required document, as well as any misleading statement or omission, may be cause for revocation of permit and/of certificate of occupancy, regardless of how or when discovered.

I acknowledge that work related to this Building Permit Application may be subject to regulations governing the handling, removal and/or disposal of asbestos and/or lead-based paint. (initials)

FAX THIS FORM TO (503) 823-7425



# City of Portland, Oregon - Bureau of Development Services



1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds

High Efficiency Interior Lighting Systems Form
Permit No.: 14-185341RS Jurisdiction:
Site Address: 32-15 N.E. 40th ave.
Subdivision/Lot: and/or
Map and Tax Lot:
By my signature below, I certify that a minimum of fifty (50) percent of the permanently installed lighting fixtures in the above mentioned building have been installed with compact or linear fluorescent, or a lighting source that has a minimum efficacy of 40 lumens per input watt. (Oregon Residential Specialty Code N1107.2 <sup>[1]</sup> )
Signature: Date: 9-25-2014  Owner/General Contractor/Authorized Agent
Print Name: Soul Toyner
<sup>11</sup> ORSC Section N1107.2. High-efficiency interior lighting systems. A minimum of fifty (50) percent of the permanently installed lighting fixtures shall be installed with compact or linear fluorescent, or a lighting source that has a minimum efficacy of 40 lumens per input watt. Screw-in compact fluorescent lamps comply with this requirement.  The building official shall be notified in writing at the final inspection that a minimum of fifty percent of the permanently installed lighting fixtures are compact or linear fluorescent, or a minimum efficacy of 40 lumens per input watt.
insp_moistcontent_efflight 10/22/08
tear at perforation
City of Portland, Oregon - Bureau of Development Services
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Moisture Sensitive Wood Framing Moisture Content Form
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Moisture Sensitive Wood Framing Moisture Content Form  I. Brad Joyna , am the general contractor or the owner/builder at the following address:
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Moisture Sensitive Wood Framing Moisture Content Form  I, Brad Seyman, am the general contractor or the owner/builder at the following address:  Street Address 3245 No 40th ave
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Moisture Sensitive Wood Framing Moisture Content Form  I, Brad Seyman, am the general contractor or the owner/builder at the following address:  Street Address 3245 No 40th ave  City Portland State Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Zip Code 9
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Moisture Sensitive Wood Framing Moisture Content Form  I, Brad Seyman, am the general contractor or the owner/builder at the following address:  Street Address 3245 No 40th ave
1900 SW Fourth Avenue • Portland, Oregon 97201 • 503-823-7300 • www.portlandonline.com/bds  Moisture Sensitive Wood Framing Moisture Content Form  I, Brad Seyna , am the general contractor or the owner/builder at the following address:  Street Address 3245 No. 40th ave  City Psalud State Oregon Zip Code 9  Permit No.: 14-185341 Rs Jurisdiction:

#### GENERAL NOTES

2

\*

These plans were designed to conform to the latest edition of the State of Oregon 2011 Residential Specialty Code, Structural & Mechanical Requirements and the 2009 Edition of the International Building Code, adhering to the most stringent code requirements in each case of the time the plans were drawn (exclusive of seismic and high wind regulations). Due to continuous changes in both local and national building codes, accommodating all building restrictions is impossible. Therefore, these plans are subject to local requirements and interpretations. It becomes the responsibility of the user to make certain these plans comply to local code requirements. In the event of a conflict between specifications contained in this set of plans and applicable codes or regulations in your area, the more stringent provision shall apply and be followed during construction. Variations required by local building officials shall not be binding on the designer. The designer is not responsible for the availability of any suggested manufactured products specified on these plans or materials lists.

# BUILDER QUALIFICATION & CONSTRUCTION STANDARDS

These plans are intended for use only by persons knowledgeable in and familiar with generally accepted methods, techniques and industry standar for construction, and who are familiar with all applicable codes and other regulations that govern the construction of this type of structure. All constructions is to be performed in accordance with these regulations and

#### DIMENSIONS

Written dimensions shall take precedence over scale dimensions. (DO NOT SCALE DRAWINGS).

#### ERRORS AND OMISSIONS

Every effort has been made to insure that these plans are accurate and drawn to reflect all current national standards for safe and proper building

#### FOUNDATIONS

- To insure proper support for the footings and foundation walls, footings must always be poured with a flat bottom surface. Footings may be stepped where necessary to allow the footing to remain below frostline on a sloping grade, but the structure may not be built on a site where the finished grade line exceeds thirty degrees down from level. Sloping sites require special engineering for extended foundation walls and stepped footings.
- Drains shall be provided around all usable spaces located below ground.

  Drain tiles, perforated pipe, or other methods approved by local codes should be installed at or below the area to be protected, and must discharge by gravity or mechanical means to a drainage system

#### CONCRETE

- 1. Concrete forms, shoring and pouring methods shall conform to all current practices endorsed by the American Concrete Institution.
- 2. Backfill shall not be placed against basement retaining walls until:
- a. Concrete or masonry grout has reached its 28-day strength,
- and
  b. Structural floor framing (including sub-floor) required to stabilize walls is complete, fully nailed and anchored,
- c. Walls have been properly shored.

# WOOD FRAMING

All solid sawn lumber shall be Douglas Fir-Larch Species. Solid sawn lumber at visually exposed locations shall be of a "clear grade #1 select". All lumber shall have a moisture content of no more than 19%. Lumber shall be graded in accordance with the Western Wood Products. Association and/or the Canadian Wood Council.

#### FRAMING NOTES

- A. Top plates shall be doubled on all walls except where noted

- otherwise and the doubted of an want except whele folder otherwise and the doubted of the state of the state
- I. The ends of all joists shall bear on not less than 1½° on wood or metal and not less than 3° on masonry. The ends of all beams or girders shall bear on not less than 3".

  J. Lap all joists 3" minimum (24" maximum) at all interior bearing
- supports.

  K. Mud sills and ledger boards at concrete walls shall have anchor bolts of the sire and spacing shown on the drawings. Each board shall be secured with at least two bolts and each board shall have a bolt within 12" of each end.

  L. Provide double framing at all roof and floor diaphragm penetrations, unless noted otherwise on plans.

- Provide double framing at all roof and floor diaphragm penetrations, unless noted otherwise on plans.
   M. Contractor shall provide adequate bracing or otherwise support all portions of the structure until all members have been permanently joined together.
   N. All roof trusses shall be designed by a registered engineer for the truss manufacturer. Submit sealed truss engineering drawings to the local Building Department indicating bracing, etc., that may be required.
- be required.

  O. Provice to plumbing walls as required.

  P. All mechanical holes through any structural member shall be at the center line of the member in compliance with the latest edition of the Wood Structural Data specifications.

#### MISCELLANEOUS

- A. Caulk around all penetrations through exterior
- A. Caust around an principations intogrication convelope.

  B. A vapor-permeable air infiltration barrier is to be installed between the wall sheathing and siding.

  C. All manufactured articles, materials, and equipment shall be applied, installed, connected, erected, used, cleaned, etc., in accordance with the manufacturer's representatives in writing.

  D. Structure is designed to carry the load of composition roof shingles or shakes. Should substantially heavier materials be contemplated, then the structure will need to be redesigned accordingly.

  E. Safety glazing shall be used within all doors and within 12" of a door and/or 18" of the floor or a walkway. For specific requirements refer to Section R308.

  F. The contractor is responsible for providing adequate bracing or to
- Section R308.

  F. The contractor is responsible for providing adequate bracing or to otherwise support all portions of the structure until all members have been permanently fastened together.

#### STRUCTURAL & MISCELLANEOUS

Structural shapes, bars, and plates shall be steel meeting American Society for Testing & Materials (ASTM) standard A36. Pipe columns, where shown on plans, shall be standard weight meeting ASTM A35; type S, Grade B. Design and fabrication shall conform to the latest edition of the American Institute of Steel Construction (AISC) specifications. Exposed welds shall be ground smooth and flush. Reinforcement shall be bent cold and shall not be welded. All items, except those to be encased with cast-in-place concrete, shall be shop painted with rust primer. Erection shall conform to AISC specifications.

#### FLASHING

Install flashing and counter-flashing of 26-guage galvanized metal or aluminum where ever dissimilar building materials join or intersect at the roof of the structure. This includes all intersections of the roof with vertical walls, chimneys, and dormers, and as otherwise shown on the drawings. Flashing must also be installed above windows and doors, and at all horizontal joints in sheet siding.

### GUTTERS

All gutters shall be made of aluminum or as otherwise shown on drawings. Gutters should be secured a minimum of every 4'-0" with approved fasteners.

# SYMBOLS

DETAIL / THRU SECTION

EXTERIOR ELEVATION




ELEVATION HEIGHT

#### ABBREVIATIONS

INT interior

AFF ARCH	above finish floor architect (ural)	JST	joist
ARCH	architect (urai)	LAM	laminate (d)
BSMNT	basement	LL	Live Load
BRG	hearing	LVL	Laminated Veneer Lumber
BD	hoard	LVL	Lammated Veneer Lamier
BLDG	building	MFR	manufacturer
BM	beam	MAX	maximum
DIM	beam	MECH	mechanical
CAB	cabinets	MIN	minimum
CLG	ceiling	MIIIA	minimitan
CTR	center, centered	NO	number
CC	center, centered	140	number
CLR	clear (ance)	O.C.	on center
C.O.	covered opening	OPT	optional
CONC	concrete	OLI	optional
CONSTR	construction	PEN	plywood end nail
CONT	continuous	psi	pounds per square inch
CONT	contaidous	psf	pounds per square froit
d	penny (nail size)	psi	pounds per square root
DL	Dead Load	OTY	quantity
DIAM	diameter	QII	quantity
DRWG	drawing	REOD	required
DKWG	drawing	R.O.	rough opening
EW	each way	R.O.	rough opening
ELEC	electric (all)	S.C.	solid core
ELEV	elevation	SO	square
EXT	exterior	STD	standard
Litt	CALCITOS	STOR	storage
FIN	finished	STOR	aiorage
FLR	floor	T&G	tongue and groove
FD	floor drain	TYP	typical
FTG	footing	• • • •	Opicar
FDN	foundation	UNO	unless noted otherwise
1211	Tournation	01.0	unica noted outerwise
GA	gauge	VERT	vertical
GWB	gypsum wall board		
0.112	g) pount man cours	WC	water closet
HDR	header	W	(steel section i.e. W12x5)
HORIZ	horizontal	W/	with
	hose hib	WWM	with welded wire mesh
HB	nose bib		
		WD	wood

# NE KLICKITAT STREET



SITE PLAN CS / SCALE: 1" = 10'-0"



City of Portland Bureau of Development Services Date 7 Approved by Planning and Zoning Review

City of Portland

REVIEWED FOR CODE COMPLIANCE

JUL 2 4 2014

Permit Number

## DRAWING INDEX CS Cover Sheet, General Notes & Symbols & Site Plan A1.0 Existing / Demo Garage Plans, Notes & Section A1.1 Proposed Garage Plans, Notes & Details A2.0 Proposed Garage Exterior Elevations A3.0 Proposed Section & Details

draftingby: brokenboxdesigns, amy griffith, CSBA
503.754.1587 Rev. Remove Side Lear To Roof 07-23-2014

U 0 Ö S 0

O

0

X,1

7212 pn 6 Retrofit 40th

Ave Garage 3245 NE 2 3245 POR

9 U 多 S 0 heet


ot eral a P er en 70 0 ite S 14-180

06.05.2014

# GENERAL DEMOLITION NOTES:

- 1. Verify all existing condition and needed demolition with structural information prior to starting work.
- 2. Shore as necessary.
- 3. All rough openings of doors and windows need to be verified with actual product information before demolition and construction.
- 4. Before discarding any removed materials, verify possible reuse.

KEY EXISTING WALLS TO BE REMOVED



2 EXISTING SECTION A1.0 SCALE:  $\frac{1}{2}$ " = 1'-0"



1 EXISTING / DEMO FLOOR PLAN A1.0 SCALE: ½" = 1'-0"

(E) Garage 216 Sq. Ft.

C.H. = 7'-8"

(E) Concrete Driveway

(E) 8'-0"x7'-5" Garage Door



Verify Condition Of (E) Exterior Stud Wall Remove and Replace As Needed

City of Portland
REVIEWED FOR CODE
COMPLIANCE

(E) Patio

JUL 2 4 2014

97212 Garage Retrofit 3245 NE 40th Ave PORTLAND, OR

brokenboxdesigns, Ik amy griffith, CSBA 503.754 1587 amy\*brokenboxpdx.com

esídence

Perlaki-Morgan

Demo

8

Plans

Garage


Existing


06.05.2014


ection

S

14-180








STEM WALL DETAIL

A3.0 SCALE: 1" = 1'-0"



esídence

draftingby:

brokenboxdesigns,
amy griffith, CSBA
503.754 1587

Rev. Remove Side Lean To Roof 07-23-2014

Perlaki-Morgan Garage Retrofit 3245 NE 40th Ave PORTLAND, OR 97212

Proposed Garage Section

A3.0

06.05.2014