## **EXHIBIT E**

# CITY OF PORTLAND, OREGON BUREAU OF TRANSPORTATION

# PRELIMINARY ENGINEER'S ESTIMATE

# NW Front Avenue Road Diet (NW 9th to north of NW 19th Avenue)

#### This estimate includes the following:

Partially reconstructed traffic signals at 9th, 15th, and 17th due to road diet (one new mast arm pole + new signal heads on Front + new loops on Front + incidentals per intersection)

4.5" grind and inlay (24,465 sy per GeoDesign)

Traffic control

Replacement of 8 existing ped ramps to current ADA standards

18" deep pavement repair (2,290 sy per GeoDesign)

Permanent striping

This estimate excludes the following:

New curbs/sidewalks

Public Works frontage improvements for ^Project

Street lighting along the corridor

Signing upgrades along the corridor

Reconstruction of any existing driveways

Replacement of 11 existing ADA-compliant ped ramps

Adjustments to existing manholes, inlets, etc.

Right-of-way or easements

PRELIMINARY ENGINEER'S ESTIMATE FOR THE IMPROVEMENT OF NW Front Avenue from NW 9th Avenue to NW 20th Avenue

VALUES IN BLUE ARE PERCENT OF CONTRACT.

## ###### BID ITEMS ######

		TOTAL						
NO.	ITEMS OF WORK AND MATERIALS	QUANTITY	UNIT	UNIT PRICE	TOTAL AMOUNT			
1	MOBILIZATION	1.00	LS	\$96,388.22	\$96,388.22			
2	TEMPORARY PROTECTION & DIRECTION OF TRAFFIC	1.00	LS	\$48,194.11	\$48,194.11			
3	TEMPORARY SIGNS	200.00	SQFT	\$23.41	\$4,682.00			
4	TEMPORARY BARRICADES, TYPE II	10.00	EACH	\$62.04	\$620.40			
5	TEMPORARY BARRICADES, TYPE III	20.00	EACH	\$199.00	\$3,980.00			
10	TEMPORARY PLASTIC DRUMS	200.00	EACH	\$70.24	\$14,048.00			
12	TEMPORARY FLEXIBLE PAVEMENT MARKERS	4,800.00	EACH	\$1.99	\$9,552.00			
13	TEMPORARY STRIPING	160,000.00	FOOT	\$0.23	\$36,800.00			
15	STRIPING & STRIPE REMOVAL MOBILIZATION	8.00	EACH	\$403.86	\$3,230.88			
18	PORTABLE CHANGEABLE MESSAGE SIGNS	2.00	EACH	\$14,398.38	\$28,796.76			
19	FLAGGERS	480.00	HOUR	\$44.48	\$21,350.40			
22	EROSION CONTROL	1.00	LS	\$18,072.79	\$18,072.79			
28	INLET PROTECTION	10.00	EACH	\$105.35	\$1,053.50			
29	POLLUTION CONTROL PLAN	1.00	LS	\$6,024.26	\$6,024.26			
42	REMOVAL OF STRUCTURES & OBSTRUCTIONS	1.00	LS	\$36,145.58	\$36,145.58			
136	COLD PLANE PAVEMENT REMOVAL, 4.5 INCH DEEP	75,417.50	SQYD	\$3.00	\$226,252.50			
	LEVEL 3, 1/2 INCH DENSE, MHMAC MIXTURE	6,117.00	TON	\$85.81	\$524,899.77			
144	18 INCH ASPHALT CONCRETE PAVEMENT REPAIR	0.00	SQYD	\$66.75	\$0.00			
165	CONCRETE SIDEWALK RAMPS	8.00	EACH	\$2,000.00	\$16,000.00			
	DETECTABLE WARNING SURFACE	96.00	SQFT	\$46.82	\$4,494.72			
191	THERMOPLASTIC, NON-PROFILE, 120 MILS, EXTRUDED	64,000.00	FOOT	\$1.11	\$71,040.00			
192	PAVEMENT LEGEND, TYPE B: ARROWS	16.00	EACH	\$243.48	\$3,895.68			
194	PAVEMENT LEGEND, TYPE B: BICYCLE LANE SYMBOLS	20.00	EACH	\$250.51	\$5,010.20			
196	PAVEMENT BAR, TYPE B	600.00	SQFT	\$6.91	\$4,146.00			
225	TRAFFIC SIGNAL MODIFICATION	1.00	LS*	\$225,000.00	\$225,000.00			
	* Unit Price Shown is on Pound, Each, or Foot Basis as Applicable							
TOT	TOTAL BID ITEMS							
	******* ANTICIDATED ITEMS *******							

#### ###### ANTICIPATED ITEMS ######

		TOTAL			
NO.	ITEMS OF WORK AND MATERIALS	QUANTITY	UNIT	UNIT PRICE	TOTAL AMOUNT
	MISC. UTILITY POLE INSPECTION	1.00	LS	\$5,000.00	\$5,000.00
14	BOLI FEE PAYMENT	1.00	LS	\$1,409.68	\$1,409.68
15	CONTRACT CONTINGENCY (REQUIREMENT TO ACCEPT BIDS UP TO 10% OVER ESTIMATE)	1.00	LS	\$140,967.78	\$140,967.78
TOT	AL ANTICIPATED ITEMS				\$147,377.45

# EXHIBIT E

NO.	ITEMS OF WORK AND MATERIALS	TOTAL QUANTITY	UNIT	UNIT PRICE	TOTAL AMOUNT
SCHEDULE SU	MMARY				
BID ITEMS					\$1,409,677.77
CONSTRUCTIO	ON CONTINGENCY		5%	of Bid Items*	\$70,484.00
SUBTOTAL					\$1,480,161.77
ANTICIPATED I	TEMS				\$147,377.45
TOTAL CONSTI	RUCTION				\$1,627,539.22
PROJECT MAN	AGEMENT				\$28,708.63
<b>DESIGN ENGIN</b>	IEERING				\$143,542.96
CONSTRUCTIO	ON MANAGEMENT				\$86,126.02
SUBTOTAL					\$258,377.61
PROJECT ENG	INEERING & MANAGEMENT OVERHEAD		73.78%	of PM, Eng, and CM	\$190,631.00
TOTAL PROJEC	CT ENGINEERING & MANAGEMENT				\$449,008.61
TOTAL PROJEC	CT RIGHT-OF-WAY				\$0.00
INFLATION RAT	TE ON CONTRACT				\$163,196.36
	TE ON PERSONNEL				\$46,733.26
ESTIMATE CON	NTINGENCY FOR UNDEFINED OR CHANGE IN SCOPE				\$264,369.48
TOTAL PROJEC	CT CONTINGENCY				\$474,299.10
TOTAL PROJ	JECT ESTIMATE				\$2,550,846.93