

D.

CO. 00. 160942 DFS. 01.

JAN 21 2005
MICROFILMED

6

00-60942-DFS-01-CO Micro

RECEIVED

JOIST GIRDER

DEC 20 2000

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

DOCUMENT SERVICES

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	1 BTF SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
5	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCOR	BASE LENGTH	EXT BOTTOM CHORD	BRG DEPTH	SLOPE RATE	HIGH END	PITCH	TYPE
							LEFT	RIGHT	LEFT	RIGHT	OR	EDL OR EDR
G1	1	48G5N13.0	51-8 5/8	7/8	1 3/4	51-6	5 7/8	6 3/4	6	6		
G2	3	48G5N17.5	51-8 5/8	7/8	1 3/4	51-6	5 7/8	6 3/4	6	6		
G3	1	48G5N25.0	51-8 5/8	7/8	1 3/4	51-6	5 7/8	6 3/4	6	6		

MARK	SCL	LOCATION	SCR	LOCATION	HCL	LOCATION	HCR	LOCATION	FIXED MOMENT	LATERAL MOMENT	BC L _y DISTANCE	ADD. TC AXIAL FORCE	NET UPLIFT	I REQ'D.
G1	8	5 3/8	8	6 1/4			1A	1-0 1-3 7/4				87.0	348	
G2	8	5 3/8	8	6 1/4			1A	1-0 1-3 7/4				39.0	480	
G3	8	5 3/8	8	6 1/4			1A	1-0 1-3 7/4				55.0	634	

ADDITIONAL CONCENTRATED LOADS—LOCATED FROM BASE LENGTH LEFT END

MARK	"A"	"B"	"C"	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD	SPLICE
G1	9-10	11-8	10-0	0.9K	19-10	13.0K	49-10						
G2	9-10	11-8	10-0	1.2K	19-10	17.5K	49-10						
G3	9-10	11-8	10-0	1.1K	9-10	2.5K	19-10	25.0K	49-10				

MARK	REMARKS	- REMARKS	- REMARKS	- REMARKS	- REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
G1	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"					REJECTED		REVISIONS	
G2	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"							REVISIONS	
G3	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"							REVISIONS	

NO EXCEPTION TAKEN MAKE CORRECTIONS NOTED
GENERAL NOTES: REVISE AND RESUBMIT REJECTED

$\Delta LL \leq L/360$

REVIEWED FOR GENERAL CONFORMITY WITH CONTRACT DOCUMENTS SUBCONTRACTOR IS RESPONSIBLE FOR ALL QUANTITIES, DIMENSIONS, JOINERY AND COMPLETE COMPLIANCE WITH CONTRACT DOCUMENTS.

ANDERSEN CONSTRUCTION CO., INC.

BY *Rick Johnson* DATE *12/19/00*

CHECKING IS ONLY FOR GENERAL CONFORMANCE WITH THE DESIGN CONCEPT OF THE PROJECT AND GENERAL COMPLIANCE WITH THE INFORMATION GIVEN IN THE CONTRACT DOCUMENTS. ANY ACTION SHOWN IS SUBJECT TO THE RECOMMENDATIONS OF THE PLANS AND SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR DIMENSIONS WHICH SHALL BE CONFIRMED AND CORRECTED AT THE JOB SITE.

FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION COORDINATION OF HIS WORK WITH THAT OF ALL OTHER TRADES AND THE SATISFACTORY PERFORMANCE OF HIS WORK.

KRAMER, GEHLEN & ASSOC., INC.
CONSULTING STRUCTURAL ENGINEERS

DATE *12/19/00* BY *RJ*

DRAWN BY *ADP*

CHECKED BY *62-5*

MKA

SHOP ORDERED BY

SHOP ORDER CHECKED BY

SUBMITTAL #

JOIST GIRDER

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	2 BT SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
9	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH OR EDL	TYPE OR EDR
							LEFT	RIGHT	LEFT	RIGHT				
G4	1	48G6N13.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				
G5	6	48G6N17.5	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				
G6	2	48G6N25.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				

MARK	BEARING SEAT SLOTS				TOP CHORD HOLES				FIXED MOMENT		LATERAL MOMENT		BC L _{yy} DISTANCE	ADD. TC AXIAL FORCE	NET UPLIFT	I REQ'D.
	SCL	LOCATION	SCR	LOCATION	HCL	LOCATION	HCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT				
G4	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4						87.0	310	△
G5	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4						39.0	480	
G6	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4						55.0	684	

ADDITIONAL CONCENTRATED LOADS—LOCATED FROM BASE LENGTH LEFT END													
MARK	"A"	"B"	"C"	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD	SPLICE
G4	8-0	4-2	10-0										
G5	8-0	4-2	10-0										
G6	8-0	4-2	10-0										

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
G4	KNIFE PLATE BE, HOLD BACK 11"									
G5	KNIFE PLATE BE, HOLD BACK 11"									
G6	KNIFE PLATE BE, HOLD BACK 11"									

GENERAL NOTES										
△ LL ≤ L/360										

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY _____ SHOP ORDER CHECKED BY _____

JOIST GIRDER

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	3 BT SHT 1 OF 1	SC0-1359
PIECE COUNT	PAIN	REFER TO DWG
5	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCDL	TCDR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH OR EDL	TYPE OR EDL
							LEFT	RIGHT	LEFT	RIGHT				
G7	1	48GSN13.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				
G8	3	48GSN17.5	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				
G9	1	48GSN25.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				

BEARING SEAT SLOTS				TOP CHORD HOLES				FIXED MOMENT		LATERAL MOMENT		BG Lyy DISTANCE	ADD. TO AXIAL FORCE	NET UPLIFT	1 REQ'D
MARK	SCL	LOCATION	SCR	LOCATION	HCL	LOCATION	HCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT			
G7	8	6 1/4	8	6 1/4	1A	1-3 1/4	1A	1-3 1/4					87.0	300	
G8	8	6 1/4	8	6 1/4	1A	1-3 1/4	1A	1-3 1/4					39.0	480	
G9	8	6 1/4	8	6 1/4	1A	1-3 1/4	1A	1-3 1/4					55.0	624	

ADDITIONAL CONCENTRATED LOADS-LOCATED FROM BASE LENGTH LEFT END											
MARK	"A"	"B"	"C"	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION
G7	5-6	6-8	10-0								
G8	5-6	6-8	10-0								
G9	5-6	6-8	10-0								

MARK	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS
G7	KNIFE PLATE BE, HOLD BACK 11"														
G8	KNIFE PLATE BE, HOLD BACK 11"														
G9	KNIFE PLATE BE, HOLD BACK 11"														

GENERAL NOTES

$\Delta LL \leq L/360$

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY SHOP ORDER CHECKED BY

JOIST GIRDER

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	4 BT SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
5	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH		TYPE
							LEFT	RIGHT	LEFT	RIGHT			OR	EDL	DR
G10	1	48GSN13.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6					
G11	3	48GSN17.5	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6					
G12	1	48GSN25.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6					

BEARING SEAT SLOTS				TOP CHORD HOLES				FIXED MOMENT		LATERAL MOMENT		BC L _{yy} DISTANCE	ADD. TO AXIAL FORCE	NET UPLIFT	1 REQ'D.
MARK	SCL	LOCATION	SCR	LOCATION	HCL	LOCATION	HCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT			
G10	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4					87.0	276	
G11	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4					39.0	480	
G12	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4					55.0	684	

ADDITIONAL CONCENTRATED LOADS-LOCATED FROM BASE LENGTH LEFT END												ADLCAD	SPICE
MARK	"A"	"B"	"C"	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION		
G10	13-0	9-2	10-0	13.0K	3-0	1.2K	13-0						
G11	13-0	9-2	10-0	17.5K	3-0	2.0K	13-0						
G12	13-0	9-2	10-0	25.0K	3-0	2.9K	13-0						

MARK	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS
G10	KNIFE PLATE LE, HOLD BACK 11" TIE ROD RE														
G11	KNIFE PLATE BE, HOLD BACK 11"														
G12	KNIFE PLATE BE, HOLD BACK 11"														

GENERAL NOTES

Δ LL ≤ L/360

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY SHOP ORDER CHECKED BY

JOIST GIRDER

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	5 BTF SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
5	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCXR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH OR EDL	TYPE OR EDL
							LEFT	RIGHT	LEFT	RIGHT				
G13	3	48G5N17.5	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				
G14	1	48G5N25.0	52-5 1/2	1 3/4	1 3/4	52-2	6 3/4	6 3/4	6	6				
G15	1	48G8N17.5	59-8		1 3/4	59-6 1/4	5	6 3/4	6	6				

MARK	BEARING SEAT SLOTS				TOP CHORD HOLES				FIXED MOMENT		LATERAL MOMENT		BC L _y DISTANCE	ADD. TC AXIAL FORCE	NET UPLIFT	I REQ'D.
	SCL	LOCATION	SCR	LOCATION	HCL	LOCATION	HCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT				
G13	8	5 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4						39.0	480	
G14	8	6 1/4	8	6 1/4	1A	1-0 1-3 1/4	1A	1-0 1-3 1/4						55.0	684	
G15			8	6 1/4			1A	1-0 1-3 1/4						39.0	480	

ADDITIONAL CONCENTRATED LOADS-LOCATED FROM BASE LENGTH LEFT END													
MARK	"A"	"B"	"C"	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD	SPLICE
G13	10-6	11-8	10-0	17.5K	0-6 1/4	1.2K	10-6	17.5K	50-6				
G14	10-6	11-8	10-0	25.0K	0-6 1/4	1.8K	10-6	25.0K	50-6				
G15	14-0 1/4	5-6	10-0	8.8K	4-0 1/4								

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
G13	KNIFE PLATE BE, HOLD BACK 11"									
G14	KNIFE PLATE BE, HOLD BACK 11"									
G15	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"									

GENERAL NOTES													
$\Delta LL \leq L/360$													

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY _____ SHOP ORDER CHECKED BY _____

JOIST GIRDER

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	6 BTF SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
3	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCOL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH OR EOL OR EDR	TYPE
							LEFT	RIGHT	LEFT	RIGHT				
G16	1	48G6N17.5	55-9 3/4		1 3/4	55-8	5	6 3/4	6	6				
G17	1	48G6N17.5	51-11 3/8		1 3/4	51-9 5/8	5	6 3/4	6	6				
G18	1	48G5N25.0 Δ	48-1 1/8		1 3/4	47-11 3/8	5	6 3/4	6	6				

BEARING SEAT SLOTS				TOP CHORD HOLES				FIXED MOMENT		LATERAL MOMENT		BC L _y DISTANCE	ADD. TO AXIAL FORCE	NET UPLIFT	I REQ'D.
MARK	SCL	LOCATION	SCR	LOCATION	HCL	LOCATION	HCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT			
G16			8	6 1/4			1A	1-0 1-3 1/4					39.0	480	
G17			8	6 1/4			1A	1-0 1-3 1/4					39.0	480	
G18			8	6 1/4			1A	1-0 1-3 1/4					55.0	684 Δ	

ADDITIONAL CONCENTRATED LOADS-LOCATED FROM BASE LENGTH LEFT END													
MARK	"A"	"B"	"C"	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD	SPLICE
G16	10-2	5-6	10-0										
G17	6 3 5/8	5-6	10-0										
G18	12-5 3/8	5-6	10-0	8.8K	2-5 3/8								

MARK	REMARKS	-	REMARKS	--	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS	-	REMARKS
G16	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"														
G17	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"														
G18	NO AXIAL FORCE LE KNIFE PLATE RE, HOLD BACK 11"														

GENERAL NOTES															
$\Delta L \leq L/360$															

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY _____ SHOP ORDER CHECKED BY _____

LONG SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE RED	LIST NUMBER 7 BTF SHT 1 OF 1	FILE NUMBER S00-1359
PIECE COUNT 6	PAINT GREY	REFER TO DWG 1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH	TYPE
							LEFT	RIGHT	LEFT	RIGHT				
T1	5	44LH15	72-5 1/4		1/4	72-5			3 3/4	3 3/4	1.125	RE		
T2	1	44LH15	72-4 3/4		1/4	72-4 1/2			3 3/4	3 3/4	1.125	RE		

MARK	SCL	BEARING SEAT SLOTS		FIXED MOMENT		LATERAL MOMENT		BG L _y DISTANCE	ADD. TO AXIAL FORCE	NET UPLIFT	I REQ'D
		LOCATION	SCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT			
T1	7	1 3/4	7	1 3/4					11.0	120	
T2	7	1 3/4	7	1 3/4					11.0	120	

ADDITIONAL CONCENTRATED LOADS—LOCATED FROM BASE LENGTH LEFT END													
MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	SPLICE
T1													
T2													

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
T1	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 6"										
T2	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 6"										

GENERAL NOTES											
1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2.											
$\Delta L \leq L/360$											

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY _____ SHOP ORDER CHECKED BY _____

SHORT SPAN JOIST

BILL OF MATERIALS

JCB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	8 BTF SHT 1 OF 1	S00-1359
PIECE COUNT	PAYMENT	REFER TO DWG
19	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END
							LEFT	RIGHT	LEFT	RIGHT		
J1	5	30K10	40-0 3/4	1/4	2 1/4	39-10 1/4			3 3/4	3 3/4	.875	LE
J2	1	30K10	39-11 3/4	1/4	2 1/4	39-9 1/4			3 3/4	3 3/4	.875	LE
J3	13	30K10	39-11 1/2	1/4	1/4	39-11			3 3/4	3 3/4		

BEARING SEAT SLOTS					ADD. TC AXIAL FORCE	BC Lyy DISTANCE	NET UPLIFT
MARK	SCL	LOCATION	SCR	LOCATION			
J1	9	1 3/4	9	1 3/4	11.0		120
J2	9	1 3/4	9	1 3/4	11.0		120
J3	9	1 3/4	9	1 3/4	11.0		120

ADDITIONAL CONCENTRATED LOADS—LOCATED FROM BASE LENGTH LEFT END													
MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD
J1													
J2													
J3													

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
J1	TIE PLATE BE, HOLD BACK NAILER 6"										
J2	TIE PLATE BE, HOLD BACK NAILER 6"										
J3	TIE PLATE BE, HOLD BACK NAILER 6"										

GENERAL NOTES

$$\Delta L \leq L/360$$

1 3/4" LSL NAILER INSTALLED BY MFG. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2.

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY SHOP ORDER CHECKED BY

SHORT SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
RED	9 BTF SHT 1 OF 1	S00-1359
PIECE COUNT	PART	REFER TO DWG
5	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCXR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END
							LEFT	RIGHT	LEFT	RIGHT		
J4	2	3CK10	39-10 1/2	1/4	1/4	39-10			3 3/4	3 3/4		
J5	1	3CK10	39-11	1/4	1/4	39-10 1/2			3 3/4	3 3/4		
J6	2	3CK10	39-9 1/4		1/4	39-9			3 3/4	3 3/4		

BEARING SEAT SLOTS					ADD. TC AXIAL FORCE	BC Lvy DISTANCE	NET UPLIFT
MARK	SCL	LOCATION	SCR	LOCATION			
J4	9	1 3/4	9	1 3/4	11.0		120
J5	9	1 3/4	9	1 3/4	11.0		120
J6	9	1 3/4	9	1 3/4	11.0		120

ADDITIONAL CONCENTRATED LOADS--LOCATED FROM BASE LENGTH LEFT END

MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD
J4													
J5													
J6													

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
J4	TIE PLATE BE, HOLD BACK NAILER 6"										
J5	TIE PLATE BE, HOLD BACK NAILER 6"										
J6	TIE PLATE BE, HOLD BACK NAILER 6"										

GENERAL NOTES

$\Delta L \leq L/360$

1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2.

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY SHOP ORDER CHECKED BY

LONG SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE BLUE	LIST NUMBER 10 BTF SHT 1 OF 1	FILE NUMBER S00-1359
PIECE COUNT 27	PAIN GREY	REFER TO DWG 1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCXL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH OR EDL	TYPE OR EDR
							LEFT	RIGHT	LEFT	RIGHT				
T3	25	44LH15	72-5 1/4		1/4	72-5			3 3/4	3 3/4	1.125	RE		
T4	1	44LH542/291	72-5 1/4		1/4	72-5			3 3/4	3 3/4	1.125	RE		
T5	1	44LH562/311	72-5 1/4		1/4	72-5			3 3/4	3 3/4	1.125	RE		

MARK	BEARING SEAT SLOTS				FIXED MOMENT		LATERAL MOMENT		BC Lyy DISTANCE	ADD. TO AXIAL FORCE	NET UPLIFT	I REQ'D.
	SCL	LOCATION	SCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT				
T3										11.0	120	
T4										11.0	120	
T5										11.0	120	

ADDITIONAL CONCENTRATED LOADS—LOCATED FROM BASE LENGTH LEFT END

MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD	SPUCE
T3														
T4														
T5														

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
T3	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 6"										
T4	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 6"										
T5	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 6"										

GENERAL NOTES

1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2.

$$\Delta LL \leq L/360$$

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY _____ SHOP ORDER CHECKED BY _____

LONG SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
BLUE	11 BTF SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
2	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCOL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END	PITCH		TYPE
							LEFT	RIGHT	LEFT	RIGHT			OR EDL	OR EDR	
T6	1	44LH15	72-5 1/4		1/4	72-5			3 1/4	3 3/4	1.125	RE			
T7	1	44LH542/291	72-5 1/4		1/4	72-5			3 1/4	3 3/4	1.125	RE			

MARK	SCL	BEARING SEAT SLOTS		FIXED MOMENT		LATERAL MOMENT		BG Lyy DISTANCE	ADD. TO AXIAL FORCE	NET UPLIFT	I REQ'D.
		LOCATION	SCR	LOCATION	LEFT	RIGHT	LEFT	RIGHT			
T6									11.0	120	
T7									11.0	120	

ADDITIONAL CONCENTRATED LOADS—LOCATED FROM BASE LENGTH LEFT END														
MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD	SPLICE
T6	0.58K	21-0	0.58K	29-0	0.58K	37-0	0.58K	45-0						
T7	0.15K	21-0	0.15K	29-0	0.15K	37-0	0.15K	45-0						

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
T6	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 5"										
T7	NO AXIAL FORCE LE TIE PLATE RE, HOLD BACK NAILER 5"										

GENERAL NOTES

1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2.

$\Delta LL \leq L/360$

DRAWN BY ADP CHECKED BY MKA S-DP ORDERED BY _____ SHOP ORDER CHECKED BY _____

SHORT SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
BLUE	12 BTJ SHT 1 OF 1	S00-1359
PIECE COUNT	PAINT	REFER TO DWG
30	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCOL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END
							LEFT	RIGHT	LEFT	RIGHT		
J7	27	30K10	40-0 3/4	1/4	2 1/4	39-10 1/4			3 3/4	3 3/4		
J8	2	30K468/345	40-0 3/4	1/4	2 1/4	39-10 1/4			3 3/4	3 3/4		
J9	1	30K488/365	40-0 3/4	1/4	2 1/4	39-10 1/4			3 3/4	3 3/4		

BEARING SEAT SLOTS					ADD. TC AXIAL FORCE	BC Lyy DISTANCE	NET UPLIFT
MARK	SCL	LOCATION	SCR	LOCATION			
J7					11.0		120
J8					11.0		120
J9					11.0		120

ADDITIONAL CONCENTRATED LOADS--LOCATED FROM BASE LENGTH LEFT END													ADLCAD
MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	
J7													
J8													
J9													

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
J7	TIE PLATE BE, HOLD BACK NAILER 6"										
J8	TIE PLATE BE, HOLD BACK NAILER 6"										
J9	TIE PLATE BE, HOLD BACK NAILER 6"										

GENERAL NOTES

$\Delta LL \leq L/360$

1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY _____ SHOP ORDER CHECKED BY _____

SHORT SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
BLUE	13 BTF SHT 1 OF 1	SCO-1359
PIECE COUNT	PAIN	REFER TO DWG
79	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCOL	TCOR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END
							LEFT	RIGHT	LEFT	RIGHT		
J10	70	30K10	39-11 1/2	1/4	1/4	39-11			3 3/4	3 3/4		
J11	6	30K488/345	39-11 1/2	1/4	1/4	39-11			3 3/4	3 3/4		
J12	3	30K488/365	39-11 1/2	1/4	1/4	39-11			3 3/4	3 3/4		

BEARING SEAT SLOTS					ADD. TO AXIAL FORCE	BG Lvy DISTANCE	NET UPLIFT
MARK	SCL	LOCATION	SCR	LOCATION			
J10					11.0		120
J11					11.0		120
J12					11.0		120

ADDITIONAL CONCENTRATED LOADS-LOCATED FROM BASE LENGTH LEFT END

MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLOAD
J10													
J11													
J12													

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
J10	TIE PLATE BE, HOLD BACK NAILER 6"												
J11	TIE PLATE BE, HOLD BACK NAILER 6"												
J12	TIE PLATE BE, HOLD BACK NAILER 6"												

GENERAL NOTES

$$\Delta LL \leq L/360$$

1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2.

DRAWN BY

ADP

CHECKED BY

MKA

SHOP ORDERED BY

SHOP ORDER CHECKED BY

SHORT SPAN JOIST

BILL OF MATERIALS

JOB: COLUMBIA DISTRIBUTION

LOC: PORTLAND, OREGON

COLOR CODE	LIST NUMBER	FILE NUMBER
BLUE	14 BTJ SHT 1 OF 1	SC0-1359
PIECE COUNT	PAYT	REFER TO DWG
12	GREY	1 OF 2

MARK	QTY	DESIGNATION	OVERALL LENGTH	TCDL	TCDR	BASE LENGTH	EXT BOTTOM CHORD		BRG DEPTH		SLOPE RATE	HIGH END
							LEFT	RIGHT	LEFT	RIGHT		
J13	12	30X10	39-9 1/4		1/4	39-9			3 3/4	3 3/4		

BEARING SEAT SLOTS					ADD. TO AXIAL FORCE	BC L/y DISTANCE	NET UPLIFT
MARK	SQL	LOCATION	SCR	LOCATION			
J13					11.0		120

ADDITIONAL CONCENTRATED LOADS-LOCATED FROM BASE LENGTH LEFT END

MARK	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	LOAD	LOCATION	ADLCAD
J13													

MARK	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS	REMARKS
J13	TIE PLATE BE, HOLD BACK NAILER 6"												

GENERAL NOTES

$$\Delta LL \leq L/360$$

1 3/4" LSL NAILER INSTALLED BY MFR. USE #14 X 1 3/4" GRADE 5 SCREWS @ 24" O.C. SEE DETAIL 1/2

DRAWN BY ADP CHECKED BY MKA SHOP ORDERED BY SHOP ORDER CHECKED BY



SOLUTIONS + SERVICE

00-160942-DFS-01-CO

STRUCTURAL CALCULATIONS

THE STEEL JOISTS DESIGNATED BELOW WERE DESIGNED IN ACCORDANCE WITH
STANDARD SPECIFICATIONS ESTABLISHED BY THE STEEL JOIST INSTITUTE.

- G1, G2, G3, G4, G5, G6, G7, G8, G9, G10, G11, G12, -
- G13, G14, G15, G16, G17, G18, C1, C2, C3, C4, C5, C6, -
- C7, J1, J2, J3, J4, J5, J6, J7, J8, J9, J10, J11, -
- J12, J13, - END -

NO EXCEPTION TAKEN ☒ MAKE CORRECTIONS NOTED ☐
REJECTED ☐ REVISE AND RESUBMIT ☐
SUBMIT SPECIFIED ITEM ☐

CHECKING IS ONLY FOR GENERAL CONFORMANCE WITH THE DESIGN
CONCEPT OF THE PROJECT AND GENERAL COMPLIANCE WITH THE
INFORMATION GIVEN IN THE CONTRACT DOCUMENTS. ANY ACTION
SHOWN IS SUBJECT TO THE REQUIREMENTS OF THE PLANS AND
SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR: DIMENSIONS
WHICH SHALL BE CONFIRMED AND CORRELATED AT THE JOB SITE
FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION
COORDINATION OF HIS WORK WITH THAT OF ALL OTHER TRADES AND
THE SATISFACTORY PERFORMANCE OF HIS WORK.

KRAMER, GEHLEN & ASSOC., INC.
CONSULTING STRUCTURAL ENGINEERS

DATE 12/18/00 BY RJ

CUSTOMER:
JOB NO.:

WOOD LAM
A04061

NO EXCEPTION TAKEN ☐ MAKE CORRECTIONS NOTED ☐
REVISE AND RESUBMIT ☐ REJECTED ☐
REVIEWED BY ANDERSEN DATE 12/18/00
DOCUMENTS SUBCONTRACTOR IS RESPONSIBLE FOR
ALL QUANTITIES, DIMENSIONS JOINERY AND COMPLETE
COMPLIANCE WITH CONTRACT DOCUMENTS.

ANDERSEN CONSTRUCTION CO., INC.

BY Andersen DATE 12/18/00

ACCO JOB # 625


SUBMITTAL # _____

RECEIVED

DEC 20 2000

DOCUMENT SERVICES

13 Dec 2000




**Portland
APPROVED**

08 2001

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G1 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- **LOADING CONDITIONS** -----
(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G5N13.0 LIVE LOAD ...: 0.00 lb/ft

----- **CONCENTRATED LOADS** -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. Cmp [deg]
1	1	Near	13.00	9.10	3.48	9'-10"	9'-10"	5	1	90 0
2	1	Near	13.00	9.10	3.48	19'-10"	10'-0"	5	1	90 0
3	1	Near	13.00	9.10	3.48	29'-10"	10'-0"	5	1	90 0
4	1	Near	13.00	9.10	3.48	39'-10"	10'-0"	5	1	90 0
5	1	Far	0.90	0.90	0.00	19'-10"	19'-10"	5	1	90 0
6	1	Far	13.00	13.00	0.00	49'-10"	30'-0"	5	1	90 0

----- **END MOMENTS [ft-kip] & AXIAL LOADS [kips]** -----

MOMENTS

AXIAL LOADS

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-87.00	87.00	0.00	0.00
(case 2)...	0.00	0.00	87.00	-87.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.71 in (L/ 360)
 Calculated deflection under service live load = 1.11 in (L/ 551)
 Joist inertia = 5099.19 in⁴
 Required camber = 1.08 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)
 (Fy = 50 Ksi U/N)

(Eff. depth = 45.87 in)

Left Reaction = 27.90/ -5.38 kips Right Reaction = 38.06/ -5.01 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	74.97	-80.02	LL 4 X .375	z 72	0.683	4'-11"		
1.2	74.97	-80.02	do	z 75	0.699	4'-11"		
1.3	85.56	-99.01	do	z 76	0.876	5'-0"		
1.4	85.56	-99.01	do	z 76	0.876	do		
1.5	89.45	-110.71	do	z 76	0.979	do		
1.6	89.45	-110.71	do	z 76	0.979	do		
1.7	86.54	-101.61	do	z 76	0.899	do		
1.8	86.54	-101.61	do	z 76	0.899	5'-0"		
1.9	75.72	-84.13 x	do	xx 97	0.958	10'-0"		
1.10	75.72	-94.76	LL 4 X .375	z 23	0.592	1'-8"		
Bottom Chord								
2.1	0.00	0.00	LL 3.5 X .313	z 83	0.564	4'-11"		
2.2	70.52	-13.64	do	z 172	0.747	9'-11"		
2.3	109.44	-20.93 x	do	xx111	0.871	10'-0"		
2.4	111.96	-21.42 x	do	yy140	0.892	10'-0"		
2.5	80.46	-15.11	do	z 188	0.858	10'-10"		
2.6	0.00	0.00	LL 3.5 X .313	z 99	0.549	5'-10"		
End Diagonal								
3.1	44.49	-11.12 x	LL 2 X .216	xx119	0.907	6'-2 1/2"	.216 - 7"	
3.2	68.04	-17.01	LL 3 X .25	z 138	0.789	6'-11 1/4"	.250 - 9 1/4"	T45
Diagonal Towards End								
4.1	24.50	-6.13 x	LLV 1.75 x .143	xx139	0.851	6'-4 7/8"	.143 - 5 3/4"	
4.2	15.67	-3.92 x	LL 2 X .216	xx123	0.319	do	.216 - 2 1/2"	
4.3	0.31	-15.67 x	LL 2 X .216	xx123	0.973	do	.216 - 2 1/2"	
4.4	19.84	-4.96 x	LLV 1.75 x .143	xx139	0.689	6'-4 7/8"	.143 - 4 5/8"	
Diagonal Towards Center								
5.1	8.79	-45.42 x	LL 3 X .224	xx 80	0.973	6'-4"	.224 - 6 7/8"	
5.2	4.60	-24.49 x	LL 2.5 X .188	xx 97	0.904	6'-4 7/8"	.188 - 4 3/8"	
5.3	3.98	-19.82 x	LL 2.5 X .188	xx 97	0.732	6'-4 7/8"	.188 - 3 5/8"	
5.4	9.16	-45.70 x	LL 3 X .25	xx 90	0.955	7'-0 7/8"	.250 - 6 1/8"	
Secondary Web Member								
7.1	0.00	-1.68	U 1 x 1 x 0.118	z 155	0.019	4'-0"	.118 - 1 1/2"	
7.2	0.00	-2.08 d	U 1 3/8 x 0.118	z 106	0.479	do	do	
7.3	0.00	-2.33 d	do	z 106	0.535	do	do	
7.4	0.00	-2.14 d	U 1 3/8 x 0.118	z 106	0.491	4'-0"	.118 - 1 1/2"	
7.5	0.00	-19.23	LL 3 X .224	z 114	0.650	5'-9 1/4"	.224 - 2 7/8"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 40'-10 7/8" ==> 0 Row(s) Minimum

Laterals supports
 Concentrated loads

@ Bottom Chord: 36'-10 1/8" ==> 2 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 19'-10"

KB 29'-10"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,
-U = 1 U profile,

BL = 2 angles welded in box,
UU = 2 U profiles one inside the other,

BR = Round bar
-CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2165 (317.84) / 2288 (336.44)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G2 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD 0.00 lb/ft 48G5N17.5 LIVE LOAD ... 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 0-6 1/2	Incl. Cmp [deg]
1	1	Near	17.50	12.25	4.80	9'-10"	9'-10"	5	1	90 0
2	1	Near	17.50	12.25	4.80	19'-10"	10'-0"	5	1	90 0
3	1	Near	17.50	12.25	4.80	29'-10"	10'-0"	5	1	90 0
4	1	Near	17.50	12.25	4.80	39'-10"	10'-0"	5	1	90 0
5	1	Far	1.20	1.20	0.00	19'-10"	19'-10"	5	1	90 0
6	1	Far	17.50	17.50	0.00	49'-10"	30'-0"	5	1	90 0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.71 in (L/ 360)
 Calculated deflection under service live load = 1.19 in (L/ 516)
 Joist inertia = 6428.75 in⁴
 Required camber = 1.08 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.70 in)

Left Reaction = 37.54/ -7.43 kips Right Reaction = 51.22/ -6.92 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	40.00	-46.81	LL 4 X .438	z 73	0.346	4'-11"		
1.2	40.00	-46.81	do	z 75	0.612	4'-11"		
1.3	54.67	-121.53	do	z 76	0.931	5'-0"		
1.4	54.67	-121.53	do	z 76	0.931	do		
1.5	60.06	-149.53 x	do	yy 58	0.980	do		
1.6	60.06	-149.53 x	do	yy 58	0.980	do		
1.7	56.02	-129.97	do	z 76	0.995	do		
1.8	56.02	-129.97	do	z 76	0.995	5'-0"		
1.9	41.03	-57.05 x	do	xx 98	0.654	10'-0"		
1.10	41.03	-76.20	LL 4 X .438	z 23	0.411	1'-8"		
Bottom Chord								
2.1	0.00	0.00	LL 4 X .375	z 72	0.476	4'-11"		
2.2	95.25	-18.89	do	z 151	0.738	9'-11"		
2.3	147.81	-29.00	do	z 152	0.862	10'-0"		
2.4	151.23	-29.68	do	z 152	0.882	10'-0"		
2.5	108.68	-20.93	do	z 165	0.756	10'-10"		
2.6	0.00	0.00	LL 4 X .375	z 86	0.543	5'-10"		
End Diagonal								
3.1	60.00	-15.00	LL 2.5 X .230	z 148	1.007	6'-2 1/2"	.230 - 8 7/8"	T45
3.2	91.81	-22.95	LL 3 X .313	z 139	0.860	6'-11 1/4"	.313 - 9 7/8"	T45
Diagonal Towards End								
4.1	33.04	-8.26 x	LL 2 X .142	xx121	1.005	6'-4 7/8"	.142 - 7 7/8"	
4.2	21.13	-5.28 x	LL 2.5 X .188	xx 97	0.389	do	.188 - 3 3/4"	
4.3	0.43	-21.13 x	LL 2.5 X .188	xx 97	0.779	do	.188 - 3 3/4"	
4.4	26.75	-6.69 x	LL 2 X .142	xx121	0.814	6'-4 7/8"	.142 - 6 3/8"	
Diagonal Towards Center								
5.1	12.16	-61.27 x	LL 3 X .281	xx 81	1.009	6'-4"	.281 - 7 3/8"	
5.2	6.36	-33.02 x	LL 2.5 X .230	xx 98	0.988	6'-4 7/8"	.230 - 4 7/8"	
5.3	5.51	-26.74 x	LL 2.5 X .230	xx 98	0.800	6'-4 7/8"	.230 - 3 7/8"	
5.4	12.68	-61.66 x	LL 3.5 X .313	xx 77	0.759	7'-0 7/8"	.313 - 6 5/8"	
Secondary Web Member								
7.1	0.00	-0.98	U 1 x 1 x 0.090	z 160	0.739	4'-0"	.091 - 1 1/2"	
7.2	0.00	-2.55 d	U 1 3/8 x 0.118	z 106	0.581	do	.118 - 1 1/2"	
7.3	0.00	-3.13 d	do	z 106	0.715	do	do	
7.4	0.00	-2.72 d	U 1 3/8 x 0.118	z 106	0.622	4'-0"	.118 - 1 1/2"	
7.5	0.00	-25.94	LL 3 X .224	z 114	0.873	5'-9 1/4"	.224 - 3 7/8"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 41'-2" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 41'-0 3/8" ==> 2 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 19'-10"

KB 29'-10"

 v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
 -U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member 1 = within a panel with no reinforcement
 2 = anywhere within a panel 3 = at any panel point along the joist
 4 = anywhere along the joist 5 = transferred by an additional member and lateral support
 6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2663 (384.21) / 2825 (406.99)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G3 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD 0.00 lb/ft 48G5N25.0 LIVE LOAD ... 0.00 lb/ft

----- CONCENTRATED LOADS -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat. 0-6	Chord 1/2	Incl. Cmp [deg]
1	1	Near	25.00	17.50	6.84	9'-10"	9'-10"	5	1	90 0
2	1	Near	25.00	17.50	6.84	19'-10"	10'-0"	5	1	90 0
3	1	Near	25.00	17.50	6.84	29'-10"	10'-0"	5	1	90 0
4	1	Near	25.00	17.50	6.84	39'-10"	10'-0"	5	1	90 0
5	1	Far	1.10	1.10	0.00	9'-10"	9'-10"	5	1	90 0
6	1	Far	2.50	2.50	0.00	19'-10"	10'-0"	5	1	90 0
7	1	Far	25.00	25.00	0.00	49'-10"	30'-0"	5	1	90 0

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-55.00	55.00	0.00	0.00
(case 2)...	0.00	0.00	55.00	-55.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.71 in (L/ 360)
 Calculated deflection under service live load = 1.23 in (L/ 501)
 Joist inertia = 9118.51 in⁴
 Required camber = 1.08 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.15 in)

Left Reaction = 54.99/ -10.60 kips Right Reaction = 73.67/ -9.87 kips

REQUIRED MATERIAL

REQUIRED WELD

No Tension Compres. x = tied at mid-length Slend. Util. Length Weld-Ea.Side Remarks

Top Chord

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length
1.1	57.24	-69.40	LL 5 X .5	z 58	0.317	4'-11"
1.2	57.24	-69.40	do	z 60	0.630	4'-11"
1.3	78.41	-179.59	do	z 61	0.839	5'-0"
1.4	78.41	-179.59	do	z 61	0.839	do
1.5	86.19	-219.75 x	do	yy 49	0.941	do
1.6	86.19	-219.75 x	do	yy 49	0.941	do
1.7	80.36	-190.12	do	z 61	0.888	do
1.8	80.36	-190.12	do	z 61	0.888	5'-0"
1.9	58.73	-83.25 x	do	xx 78	0.667	10'-0"
1.10	58.73	-110.93	LL 5 X .5	z 18	0.410	1'-8"

Bottom Chord

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length
2.1	0.00	0.00	LL 5 X .438	z 58	0.482	4'-11"
2.2	141.23	-27.26	do	z 121	0.743	9'-11"
2.3	217.94	-41.86	do	z 122	0.867	10'-0"
2.4	221.54	-42.83	do	z 122	0.882	10'-0"
2.5	158.68	-30.20	do	z 132	0.809	10'-10"
2.6	0.00	0.00	LL 5 X .438	z 69	0.570	5'-10"

End Diagonal

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	Weld-Ea.Side	Remarks
3.1	88.54	-22.14	LL 3 X .281	z 123	0.918	6'-2 1/2"	.281 - 10 5/8"	
3.2	133.16	-33.29	LL 3.5 X .375	z 119	0.893	6'-11 1/4"	.313 - 14 3/8"	T45

Diagonal Towards End

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	Weld-Ea.Side
4.1	48.01	-12.00 x	LL 2 X .216	xx122	0.979	6'-4 7/8"	.216 - 7 1/2"
4.2	30.63	-7.66 x	LL 2.5 X .230	xx 97	0.465	do	.230 - 4 1/2"
4.3	0.62	-30.63 x	LL 2.5 X .230	xx 97	0.911	do	.230 - 4 1/2"
4.4	39.35	-9.84 x	LL 2 X .216	xx122	0.802	6'-4 7/8"	.216 - 6 1/8"

Diagonal Towards Center

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	Weld-Ea.Side
5.1	17.47	-90.45 x	LL 3.5 X .344	xx 69	0.934	6'-4"	.313 - 9 3/4"
5.2	9.14	-48.00 x	LL 3 X .25	xx 81	0.905	6'-4 7/8"	.250 - 6 1/2"
5.3	7.91	-39.33 x	LL 3 X .25	xx 81	0.742	6'-4 7/8"	.250 - 5 3/8"
5.4	18.23	-89.77 x	LL 3.5 X .344	xx 77	1.002	7'-0 7/8"	.313 - 9 3/4"

Secondary Web Member

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	Weld-Ea.Side
7.1	0.00	-1.44	U 1 x 1 x 0.118	z 153	0.761	4'-0"	.118 - 1 1/2"
7.2	0.00	-3.72 d	U 1 3/8 x 0.118	z 104	0.831	do	.118 - 1 1/2"
7.3	0.00	-4.55 d	U 1 3/8 x 0.157	z 102	0.554	do	.158 - 1 1/2"
7.4	0.00	-3.93 d	U 1 3/8 x 0.118	z 104	0.880	4'-0"	.118 - 1 1/2"
7.5	0.00	-37.30	LL 3 X .313	z 114	0.917	5'-9 1/4"	.313 - 4"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 49'-3 3/4" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 49'-2 1/4" ==> 1 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 19'-10"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault

Shop: Canam Sunnyside [Production]

3785 (609.41) / 4002 (644.23)

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.16 in (L/ 538)
 Joist inertia = 5099.19 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.87 in)

Left Reaction = 30.14/ -5.35 kips Right Reaction = 34.94/ -6.21 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	73.65	-78.75	LL 4 X .375	z 58	0.599	4'-0"		
1.2	73.65	-78.75	do	z 61	0.611	4'-0"		
1.3	83.25	-97.42	do	z 76	0.862	5'-0"		
1.4	73.25	-97.42	do	z 76	0.862	do		
1.5	88.19	-111.85	do	z 76	0.990	do		
1.6	88.19	-111.85	do	z 76	0.990	do		
1.7	87.07	-105.56	do	z 76	0.934	do		
1.8	87.07	-105.56	do	z 76	0.934	do		
1.9	79.88	-90.89	do	z 76	0.804	5'-0"		
1.10	79.88	-90.89	do	z 38	0.692	2'-6"		
1.11	74.79	-80.95	do	z 38	0.692	2'-6"		
1.12	74.79	-80.95	LL 4 X .375	z 61	0.628	4'-2"		
Bottom Chord								
2.1	0.00	0.00	LL 3.5 X .313	z 67	0.507	4'-0"		
2.2	61.72	-10.99	do	z 157	0.727	9'-0"		
2.3	106.48	-18.96	do	z 174	0.918	10'-0"		
2.4	117.21	-20.87 x	do	yy156	0.933	do		
2.5	93.90	-16.72	do	z 174	0.816	10'-0"		
2.6	50.90	-9.05	do	z 87	0.654	5'-0"		
2.7	0.00	0.00	LL 3.5 X .313	z 70	0.354	4'-2"		
End Diagonal								
3.1	42.66	-10.67 x	LL 2 X .188	xx105	0.992	5'-6 1/2"	.188 - 7 5/8"	
3.2	50.56	-12.64 x	LL 2 X .250	xx109	0.899	5'-7 7/8"	.250 - 6 7/8"	
Diagonal Towards End								
4.1	28.18	-7.05 x	LLV 1.75 x .143	xx139	0.978	6'-4 7/8"	.143 - 6 5/8"	
4.2	14.38	-3.60 x	LL 1.5 X .156	xx164	0.729	do	.156 - 3 1/8"	
4.3	14.68	-3.67 x	do	xx164	0.744	6'-4 7/8"	.156 - 3 1/4"	
4.4	26.20	-6.55 x	LL 1.5 X .156	xx119	0.984	4'-8 5/8"	.156 - 5 5/8"	
Diagonal Towards Center								
5.1	7.77	-43.59 x	LL 3 X .224	xx 71	0.862	5'-7 7/8"	.224 - 6 5/8"	
5.2	5.02	-28.16 x	LL 2.5 X .250	xx 98	0.784	6'-4 7/8"	.250 - 3 7/8"	
5.3	1.21	-14.38 x	LL 2 X .216	xx123	0.893	do	.216 - 2 1/4"	
5.4	2.62	-14.66 x	LL 2 X .216	xx123	0.910	do	.216 - 2 1/4"	
5.5	6.44	-36.08 x	LL 2.5 X .250	xx 98	1.004	6'-4 7/8"	.250 - 4 7/8"	
5.6	4.65	-26.21 x	LL 2 X .216	xx 89	0.939	4'-8 5/8"	.216 - 4 1/8"	
Secondary Web Member								
7.1	0.00	-1.66	LL 2 X .163	z 116	0.119	4'-0"	.163 - 1 1/2"	
7.2	0.00	-2.05 d	U 1 3/8 x 0.118	z 106	0.471	do	.118 - 1 1/2"	
7.3	0.00	-2.35 d	do	z 106	0.541	do	do	
7.4	0.00	-2.22 d	do	z 106	0.510	do	do	
7.5	0.00	-1.91 d	U 1 3/8 x 0.118	z 106	0.439	do	.118 - 1 1/2"	

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	REQUIRED WELD	Remarks
7.6	2.33	-13.00	LL 2 X .163	z 116	0.938	4'-0"	Weld-Ea.Side .163 - 2 5/8"	

BRIDGING

Maximum spacing between rows of bridging

POSITION	@ Top Chord	@ Bottom Chord	KB	28'-0"

POSITION

@ Top Chord

@ Bottom Chord

KB 18'-0"

KB 28'-0"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2180 (320.16) / 2266 (333.05)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G5 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- **LOADING CONDITIONS** -----
(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G6N17.5 LIVE LOAD ...: 0.00 lb/ft

----- **CONCENTRATED LOADS** -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat. 0-6	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	17.50	12.25	4.80	8'-0"	8'-0"	5	1	90	0
2	1	Near	17.50	12.25	4.80	18'-0"	10'-0"	5	1	90	0
3	1	Near	17.50	12.25	4.80	28'-0"	10'-0"	5	1	90	0
4	1	Near	17.50	12.25	4.80	38'-0"	10'-0"	5	1	90	0
5	1	Near	17.50	12.25	4.80	48'-0"	10'-0"	5	1	90	0

----- **END MOMENTS [ft-kip] & AXIAL LOADS [kips]** -----

MOMENTS

AXIAL LOADS

	---L---	---R---	---L---	---R---	---L---	---R---
			<<< Top Chord >>>		< Bottom Chord >	
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

6840 N CUTTER CIRCLE

DFS-01

CO-00-160942

2.

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.23 in (L/ 504)
 Joist inertia = 6428.75 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.70 in)

Left Reaction = 40.55/ -8.31 kips Right Reaction = 47.03/ -9.63 kips

			REQUIRED MATERIAL			REQUIRED WELD			
No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks	
Top Chord									
1.1	39.09	-43.76	LL 4 X .438	z 59	0.288	4'-0"			
1.2	39.09	-43.76	do	z 61	0.572	4'-0"			
1.3	54.02	-113.62	do	z 76	0.870	5'-0"			
1.4	54.02	-113.62	do	z 76	0.870	do			
1.5	61.71	-151.10 x	do	yy 58	0.990	do			
1.6	61.71	-151.10 x	do	yy 58	0.990	do			
1.7	59.97	-142.60 x	do	yy 58	0.935	do			
1.8	59.97	-142.60 x	do	yy 58	0.935	do			
1.9	48.79	-88.13	do	z 76	0.718	5'-0"			
1.10	48.79	-88.13	do	z 38	0.578	2'-6"			
1.11	40.85	-49.38	do	z 38	0.578	2'-6"			
1.12	40.85	-49.38	LL 4 X .438	z 61	0.331	4'-2"			
Bottom Chord									
2.1	0.00	0.00	LL 4 X .375	z 58	0.417	4'-0"			
2.2	83.38	-17.11	do	z 137	0.719	9'-0"			
2.3	143.85	-29.51	do	z 152	0.838	10'-0"			
2.4	158.34	-32.48	do	z 152	0.923	do			
2.5	126.85	-26.02	do	z 152	0.791	10'-0"			
2.6	68.76	-14.09	do	z 76	0.634	5'-0"			
2.7	0.00	0.00	LL 4 X .375	z 61	0.344	4'-2"			
End Diagonal									
3.1	57.53	-14.38	LL 2.5 X .230	z 132	0.874	5'-6 1/2"	.230 - 8 1/2"	T45	
3.2	68.18	-17.05	LL 2.5 X .250	z 135	0.957	5'-7 7/8"	.250 - 9 1/4"	T45	
Diagonal Towards End									
4.1	38.01	-9.50 x	LL 2 X .188	xx122	0.884	6'-4 7/8"	.188 - 6 7/8"		
4.2	19.40	-4.85 x	LL 1.5 X .156	xx164	0.980	do	.156 - 4 1/4"		
4.3	19.80	-4.95 x	LL 1.5 X .156	xx164	1.000	6'-4 7/8"	.156 - 4 1/4"		
4.4	35.30	-8.82 x	LL 2 X .163	xx 88	0.941	4'-8 5/8"	.163 - 7 3/8"		
Diagonal Towards Center									
5.1	12.07	-58.78 x	LL 3 X .281	xx 72	0.886	5'-7 7/8"	.281 - 7 1/8"		
5.2	7.80	-38.00 x	LL 3 X .25	xx 81	0.719	6'-4 7/8"	.250 - 5 1/8"		
5.3	1.87	-19.40 x	LL 2.5 X .188	xx 97	0.715	do	.188 - 3 1/2"		
5.4	4.07	-19.78 x	LL 2.5 X .188	xx 97	0.729	do	.188 - 3 1/2"		
5.5	10.00	-48.68 x	LL 3 X .25	xx 81	0.921	6'-4 7/8"	.250 - 6 5/8"		
5.6	7.23	-35.31 x	LL 2.5 X .188	xx 70	0.990	4'-8 5/8"	.188 - 6 3/8"		
Secondary Web Member									
7.1	0.00	-0.92	LL 2 X .216	z 116	0.051	4'-0"	.216 - 1 1/2"		
7.2	0.00	-2.38 d	U 1 3/8 x 0.118	z 106	0.543	do	.118 - 1 1/2"		
7.3	0.00	-3.16 d	do	z 106	0.723	do	do		
7.4	0.00	-2.99 d	do	z 106	0.682	do	do		
7.5	0.00	-1.85 d	U 1 3/8 x 0.118	z 106	0.422	do	.118 - 1 1/2"		

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.	REQUIRED MATERIAL		Slend.	Util.	Length	REQUIRED WELD		Remarks
			x = tied at mid-length					Weld-Ea.Side		
7.6	3.60	-17.50	LL 2 X .216		z 116	0.972	4'-0"	.216 - 2 3/4"		

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	41'-3 1/2" ==>	0 Row(s) Minimum	Laterals supports
@ Bottom Chord:	41'-0 3/8" ==>	2 Row(s) Minimum	Concentrated loads
			Acc. to the force

POSITION	@ Top Chord	@ Bottom Chord	
			KB 18'-0"
			KB 28'-0"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member	1 = within a panel with no reinforcement
2 = anywhere within a panel	3 = at any panel point along the joist
4 = anywhere along the joist	5 = transferred by an additional member and lateral support
6 = within a panel with no reinforcement and lateral support	

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal Composite (Cmp): 0 = standard, 1 = non-composite

Projects no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2688 (384.93) / 2798 (400.44)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G6 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G6N25.0 LIVE LOAD ...: 0.00 lb/ft

----- CONCENTRATED LOADS -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. Cmp [deg]
1	1	Near	25.00	17.50	6.84	8'-0"	8'-0"	5	1	90 0
2	1	Near	25.00	17.50	6.84	18'-0"	10'-0"	5	1	90 0
3	1	Near	25.00	17.50	6.84	28'-0"	10'-0"	5	1	90 0
4	1	Near	25.00	17.50	6.84	38'-0"	10'-0"	5	1	90 0
5	1	Near	25.00	17.50	6.84	48'-0"	10'-0"	5	1	90 0

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

	--L--	--R--	<<< Top Chord >>>	< Bottom Chord >		
			--L--	--R--	--L--	--R--
(Q) Wind or Seism (case 1)...	0.00	0.00	-55.00	55.00	0.00	0.00
(case 2)...	0.00	0.00	55.00	-55.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.17 in (L/ 533)
 Joist inertia = 9720.08 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.13 in)

Left Reaction = 57.92/ -11.85 kips

Right Reaction = 67.16/ -13.74 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length
1.1	55.95	-62.76	LL 5 X .5	z 47	0.266	4'-0"
1.2	55.95	-62.76	do	z 49	0.577	4'-0"
1.3	77.52	-164.33	do	z 61	0.767	5'-0"
1.4	77.52	-164.33	do	z 61	0.767	do
1.5	88.62	-218.54 x	do	yy 49	0.936	do
1.6	88.62	-218.54 x	do	yy 49	0.936	do
1.7	86.10	-206.25	do	z 61	0.963	do
1.8	86.10	-206.25	do	z 61	0.963	do
1.9	69.96	-127.45	do	z 61	0.724	5'-0"
1.10	69.96	-127.45	do	z 31	0.546	2'-6"
1.11	58.50	-71.42	do	z 31	0.546	2'-6"
1.12	58.50	-71.42	LL 5 X .5	z 49	0.307	4'-2"

Bottom Chord

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length
2.1	0.00	0.00	LL 5 X .5	z 47	0.363	4'-0"
2.2	120.60	-24.70	do	z 110	0.626	9'-0"
2.3	208.05	-42.61	do	z 122	0.901	10'-0"
2.4	229.01	-46.90	do	z 122	0.901	do
2.5	183.47	-37.57	do	z 122	0.901	10'-0"
2.6	99.44	-20.35	do	z 61	0.722	5'-0"
2.7	0.00	0.00	LL 5 X .5	z 49	0.391	4'-2"

End Diagonal

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
3.1	82.66	-20.67	LL 3 X .25	z 109	0.958	5'-6 1/2"	.250 - 11 1/8"	T45
3.2	98.01	-24.50	LL 3 X .313	z 112	0.918	5'-7 7/8"	.313 - 10 5/8"	T45

Diagonal Towards End

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
4.1	54.71	-13.68 x	LL 2.5 X .188	xx 96	1.008	6'-4 7/8"	.188 - 9 7/8"	
4.2	27.92	-6.98 x	LLV 1.75 x .143	xx138	0.969	do	.143 - 6 5/8"	
4.3	28.49	-7.12 x	LLV 1.75 x .143	xx138	0.989	6'-4 7/8"	.143 - 6 3/4"	
4.4	50.60	-12.65 x	LL 2.5 X .188	xx 70	0.932	4'-8 5/8"	.188 - 9 1/8"	

Diagonal Towards Center

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
5.1	17.31	-84.50 x	LL 3.5 X .313	xx 61	0.903	5'-7 7/8"	.313 - 9 1/8"	
5.2	11.21	-54.69 x	LL 3.5 X .313	xx 69	0.626	6'-4 7/8"	.313 - 5 7/8"	
5.3	2.69	-27.92 x	LL 2.5 X .230	xx 97	0.830	do	.230 - 4 1/8"	
5.4	5.84	-28.48 x	LL 2.5 X .230	xx 97	0.847	do	.230 - 4 1/8"	
5.5	14.36	-70.07 x	LL 3.5 X .313	xx 69	0.802	6'-4 7/8"	.313 - 7 1/2"	
5.6	10.35	-50.61 x	LL 3 X .224	xx 58	0.909	4'-8 5/8"	.224 - 7 5/8"	

Secondary Web Member

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
7.1	0.00	-1.30	LL 2.5 X .188	z 91	0.045	4'-0"	.188 - 1 1/2"	
7.2	0.00	-3.40 d	U 1 3/8 x 0.118	z 104	0.759	do	.118 - 1 1/2"	
7.3	0.00	-4.52 d	do	z 104	1.010	do	do	
7.4	0.00	-4.27 d	do	z 104	0.953	do	do	
7.5	0.00	-2.64 d	U 1 3/8 x 0.118	z 104	0.589	do	.118 - 1 1/2"	

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

No	Tension	Compres.	x = tied at mid-length
7.6	5.13	-25.00	LL 2.5 X .188

Slend.	Util.
z 91	0.859

Length
4'-0"

REQUIRED WELD

Weld-Ea.Side
.188 - 4 1/2"

Remarks

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	49'-5 1/4" ==>
@ Bottom Chord:	49'-5 1/4" ==>

0 Row(s) Minimum
1 Row(s) Minimum

Laterals supports
Concentrated loads
Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 18'-0"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,
-U = 1 U profile,

BL = 2 angles welded in box,

UU = 2 U profiles one inside the other,

BR = Round bar

-CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

2 = anywhere within a panel

4 = anywhere along the joist

6 = within a panel with no reinforcement and lateral support

1 = within a panel with no reinforcement

3 = at any panel point along the joist

5 = transfered by an additional member and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside (Production)

4012 (663.26) / 4172 (690.10)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G7 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 0.00 lb/ft 48G6N13.0 LIVE LOAD ..: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	13.00	9.10	3.00	5'-6"	5'-6"	5	1	90	0
2	1	Near	13.00	9.10	3.00	15'-6"	10'-0"	5	1	90	0
3	1	Near	13.00	9.10	3.00	25'-6"	10'-0"	5	1	90	0
4	1	Near	13.00	9.10	3.00	35'-6"	10'-0"	5	1	90	0
5	1	Near	13.00	9.10	3.00	45'-6"	10'-0"	5	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-87.00	87.00	0.00	0.00
(case 2)...	0.00	0.00	87.00	-87.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth .. [in]: at left.: 7 1/2"

at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.16 in (L/ 534)
 Joist inertia = 5099.19 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)
 (Fy = 50 Ksi U/N)

(Eff. depth = 45.87 in)

Left Reaction = 33.27/ -5.72 kips Right Reaction = 31.81/ -5.47 kips

REQUIRED MATERIAL

REQUIRED WELD

No Tension Compres. x = tied at mid-length Slend. Util. Length Weld-Ea.Side Remarks

Top Chord

1.1	76.27	-84.63	LL 4 X .375	z 81	0.789	5'-6"		
1.2	76.27	-84.63	do	z 38	0.715	2'-6"		
1.3	80.83	-93.96	do	z 38	0.715	2'-6"		
1.4	80.83	-93.96	do	z 76	0.831	5'-0"		
1.5	87.03	-108.85	do	z 76	0.963	do		
1.6	87.03	-108.85	do	z 76	0.963	do		
1.7	87.36	-110.76	do	z 76	0.980	do		
1.8	87.36	-110.76	do	z 76	0.980	do		
1.9	81.82	-95.98	do	z 76	0.849	do		
1.10	81.82	-95.98	do	z 76	0.849	5'-0"		
1.11	74.25	-80.49	do	z 36	0.559	2'-4"		
1.12	74.25	-80.49	LL 4 X .375	z 63	0.636	4'-4"		

Bottom Chord

2.1	0.00	0.00	LL 3.5 X .313	z 93	0.447	5'-6"		
2.2	59.66	-10.27	do	z 87	0.746	5'-0"		
2.3	99.38	-17.12	do	z 174	0.888	10'-0"		
2.4	118.31	-20.38	do	z 174	0.987	do		
2.5	103.20	-17.78	do	z 174	0.972	10'-0"		
2.6	54.07	-9.32	do	z 128	0.848	7'-4"		
2.7	0.00	0.00	LL 3.5 X .313	z 72	0.444	4'-4"		

End Diagonal

3.1	56.99	-14.25	x	LL 2.5 X .230	xx102	0.866	6'-8"	.230 - 8 3/8"
3.2	46.97	-11.74	x	LL 2 X .216	xx111	0.958	5'-9 1/4"	.216 - 7 3/8"

Diagonal Towards End

4.1	24.18	-6.04	x	LL 1.5 X .156	xx119	0.908	4'-8 5/8"	.156 - 5 1/4"
4.2	13.67	-3.42	x	do	xx164	0.693	6'-4 7/8"	.156 - 3"
4.3	13.67	-3.42	x	LL 1.5 X .156	xx164	0.693	do	.156 - 3"
4.4	30.88	-7.72	x	LL 1.75 X .155	xx139	0.993	6'-4 7/8"	.155 - 6 3/4"

Diagonal Towards Center

5.1	4.15	-24.19	x	LL 2 X .188	xx 89	0.981	4'-8 5/8"	.188 - 4 3/8"
5.2	5.74	-33.27	x	LL 2.5 X .230	xx 98	0.998	6'-4 7/8"	.230 - 4 7/8"
5.3	2.06	-13.67	x	LL 2 X .188	xx122	0.956	do	.188 - 2 1/2"
5.4	1.64	-13.67	x	LL 2 X .188	xx122	0.956	do	.188 - 2 1/2"
5.5	5.33	-30.87	x	LL 2.5 X .230	xx 98	0.925	6'-4 7/8"	.230 - 4 1/2"
5.6	6.42	-37.22	x	LL 2.5 X .230	xx 70	0.809	4'-7 5/8"	.230 - 5 1/2"

Secondary Web Member

7.1	2.25	-13.00		LL 2 X .163	z 116	0.938	4'-0"	.163 - 2 5/8"
7.2	0.00	-1.98	d	U 1 3/8 X 0.118	z 106	0.454	do	.118 - 1 1/2"
7.3	0.00	-2.29	d	do	z 106	0.526	do	do
7.4	0.00	-2.33	d	do	z 106	0.535	do	do
7.5	0.00	-2.02	d	U 1 3/8 X 0.118	z 106	0.464	do	.118 - 1 1/2"

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.	REQUIRED MATERIAL		Slend.	Util.	Length	REQUIRED WELD		Remarks
			x = tied at mid-length					Weld-Ea.Side		
7.6	0.00	-1.69	LL 2 X .163		z 116	0.122	4'-0"	.163	- 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging
 @ Top Chord: 41'-0 3/8" ==> 0 Row(s) Minimum
 @ Bottom Chord: 36'-10 1/8" ==> 1 Row(s) Minimum
 Laterals supports
 Concentrated loads
 Acc. to the force

POSITION @ Top Chord @ Bottom Chord
 KB 25'-6"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
 -U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member 1 = within a panel with no reinforcement
 2 = anywhere within a panel 3 = at any panel point along the joist
 4 = anywhere along the joist 5 = transfered by an additional member and lateral support
 6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2139 (313.37) / 2249 (329.95)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G8 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G6N17.5 LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 0-6 1/2	Incl. Cmp [deg]
1	1	Near	17.50	12.25	4.80	5'-6"	5'-6"	5	1	90 0
2	1	Near	17.50	12.25	4.80	15'-6"	10'-0"	5	1	90 0
3	1	Near	17.50	12.25	4.80	25'-6"	10'-0"	5	1	90 0
4	1	Near	17.50	12.25	4.80	35'-6"	10'-0"	5	1	90 0
5	1	Near	17.50	12.25	4.80	45'-6"	10'-0"	5	1	90 0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 7 1/2"

at right: 7 1/2"

DEFLECTION

Allowed deflection under live load	=	1.73 in (L/ 360)
Calculated deflection under service live load	=	1.24 in (L/ 500)
Joist inertia	=	6428.75 in ⁴
Required camber	=	1.11 in

FORCES IN MEMBERS [kips]

(THAT SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.70 in)


Left Reaction = 44.77/ -9.17 kips Right Reaction = 42.81/ -8.77 kips

			REQUIRED MATERIAL		Slend.	Util.	Length	REQUIRED WELD		Remarks		
No	Tension	Compres.	x = tied at mid-length					Weld-Ea.Side				
Top Chord												
1.1	43.58	-62.69		LL 4 X .438	z 82	0.506	5'-6"					
1.2	43.58	-62.69		do	z 38	0.645	2'-6"					
1.3	50.91	-98.48		do	z 38	0.645	2'-6"					
1.4	50.91	-98.48		do	z 76	0.754	5'-0"					
1.5	60.87	-147.04	x	do	yy 58	0.964	do					
1.6	60.87	-147.04	x	do	yy 58	0.964	do					
1.7	61.41	-149.63	x	do	yy 58	0.981	do					
1.8	61.41	-149.63	x	do	yy 58	0.981	do					
1.9	52.51	-106.23		do	z 76	0.814	do					
1.10	52.51	-106.23		do	z 76	0.814	5'-0"					
1.11	40.32	-46.82		do	z 36	0.535	2'-4"					
1.12	40.32	-46.82		LL 4 X .438	z 64	0.320	4'-4"					
Bottom Chord												
2.1	0.00	0.00		LL 4 X .375	z 81	0.425	5'-6"					
2.2	80.59	-16.52		do	z 76	0.708	5'-0"					
2.3	134.25	-27.53		do	z 152	0.843	10'-0"					
2.4	159.82	-32.78		do	z 152	0.932	do					
2.5	139.42	-28.60		do	z 152	0.922	10'-0"					
2.6	73.04	-14.98		do	z 112	0.805	7'-4"					
2.7	0.00	0.00		LL 4 X .375	z 63	0.422	4'-4"					
End Diagonal												
3.1	77.03	-19.26		LL 3 X .281	z 133	0.799	6'-8"	.281 - 9 1/4"		T45		
3.2	63.43	-15.86		LL 2.5 X .230	z 138	0.964	5'-9 1/4"	.230 - 9 3/8"		T45		
Diagonal Towards End												
4.1	32.60	-8.15	x	LL 2 X .142	xx 88	0.992	4'-8 5/8"	.142 - 7 3/4"		T45		
4.2	18.47	-4.62	x	LL 1.5 X .156	xx164	0.933	6'-4 7/8"	.156 - 4"				
4.3	18.47	-4.62	x	LL 1.5 X .156	xx164	0.933	do	.156 - 4"				
4.4	41.73	-10.43	x	LL 2 X .188	xx122	0.970	6'-4 7/8"	.188 - 7 1/2"				
Diagonal Towards Center												
5.1	6.68	-32.61	x	LL 2.5 X .188	xx 70	0.915	4'-8 5/8"	.188 - 5 7/8"				
5.2	9.23	-44.96	x	LL 3 X .224	xx 81	0.969	6'-4 7/8"	.224 - 6 3/4"				
5.3	3.31	-18.47	x	LL 2.5 X .188	xx 97	0.681	do	.188 - 3 1/4"				
5.4	2.64	-18.47	x	LL 2.5 X .188	xx 97	0.681	do	.188 - 3 1/4"				
5.5	8.56	-41.71	x	LL 3 X .224	xx 81	0.899	6'-4 7/8"	.224 - 6 1/4"				
5.6	10.30	-50.19	x	LL 2.5 X .250	xx 70	1.006	4'-7 5/8"	.250 - 6 3/4"				
Secondary Web Member												
7.1	3.60	-17.50		LL 2 X .216	z 116	0.972	4'-0"	.216 - 2 3/4"				
7.2	0.00	-2.06	d	U 1 3/8 x 0.118	z 106	0.471	do	.118 - 1 1/2"				
7.3	0.00	-3.08	d	do	z 106	0.703	do	do				
7.4	0.00	-3.13	d	do	z 106	0.716	do	do				
7.5	0.00	-2.23	d	U 1 3/8 x 0.118	z 106	0.508	do	.118 - 1 1/2"				

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G9 (JOIST GIRDER, Asymmetrical, Parallel, Free ends)



----- **LOADING CONDITIONS** -----
(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G6N25.0 LIVE LOAD ...: 0.00 lb/ft

----- **CONCENTRATED LOADS** -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat. 0-6	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	25.00	17.50	6.84	5'-6"	5'-6"	5	1	90	0
2	1	Near	25.00	17.50	6.84	15'-6"	10'-0"	5	1	90	0
3	1	Near	25.00	17.50	6.84	25'-6"	10'-0"	5	1	90	0
4	1	Near	25.00	17.50	6.84	35'-6"	10'-0"	5	1	90	0
5	1	Near	25.00	17.50	6.84	45'-6"	10'-0"	5	1	90	0

----- **END MOMENTS [ft-kip] & AXIAL LOADS [kips]** -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-55.00	55.00	0.00	0.00
(case 2)...	0.00	0.00	55.00	-55.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

No	Tension	Compres.	x = tied at mid-length
7.6	0.00	-1.40	LL 2.5 X .188

Slend.	Util.	Length
z 91	0.048	4'-0"

REQUIRED WELD

Weld-Ea.Side	Remarks
.188 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top	Chord:	49'-5 1/4" ==>	0 Row(s) Minimum
@ Bottom	Chord:	49'-2 1/4" ==>	1 Row(s) Minimum

Laterals supports
Concentrated loads
Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 25'-6"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,
-U = 1 U profile,

BL = 2 angles welded in box,

BR = Round bar

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transfered by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

3742 (606.74) / 3932 (637.26)

Project: COLUMBIA DISTRIBUTION A04061 JOIST CALCULATION ACCORDING TO SJI CODE

ADD
MEMBER

Mark.....: G10 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G5N13.0 LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat. 0-6	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	13.00	9.10	2.76	13'-0"	13'-0"	5	1	90	0
2	1	Near	13.00	9.10	2.76	23'-0"	10'-0"	5	1	90	0
3	1	Near	13.00	9.10	2.76	33'-0"	10'-0"	5	1	90	0
4	1	Near	13.00	9.10	2.76	43'-0"	10'-0"	5	1	90	0
5	1	Far	13.00	13.00	0.00	3'-0"*	3'-0"	5	1	90	0
6	1	Far	1.20	1.20	0.00	13'-0"	10'-0"	5	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-87.00	87.00	0.00	0.00
(case 2)...	0.00	0.00	87.00	-87.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.21 in (L/ 516)
 Joist inertia = 5099.19 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.87 in)

Left Reaction = 37.30/ -3.81 kips Right Reaction = 28.97/ -4.42 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	74.60	-94.35 x	LL 4 X .375	xx 62	0.735	6'-6"		
1.2	74.60	-90.36 x	do	xx 63	0.718	6'-6"		
1.3	83.40	-109.92	do	z 76	0.973	5'-0"		
1.4	83.40	-109.92	do	z 76	0.973	do		
1.5	85.30	-113.71	do	z 76	1.006	do		
1.6	85.30	-113.71	do	z 76	1.006	do		
1.7	81.80	-102.29	do	z 76	0.905	do		
1.8	81.80	-102.29	do	z 76	0.905	5'-0"		
1.9	73.39	-80.97	do	z 70	0.675	4'-7"		
1.10	73.39	-80.97	LL 4 X .375	z 67	0.661	4'-7"		
Bottom Chord								
2.1	0.00	0.00	LL 3.5 X .313	z 110	0.622	6'-6"		
2.2	91.17	-12.82	do	z 200	0.821	11'-6"		
2.3	117.54	-17.42	do	z 174	0.995	10'-0"		
2.4	109.87	-16.62	do	z 174	0.995	10'-0"		
2.5	68.16	-10.43	do	z 167	0.949	9'-7"		
2.6	0.00	0.00	LL 3.5 X .313	z 77	0.596	4'-7"		
End Diagonal								
3.1	72.17	-18.04	LL 3 X .281	z 150	0.849	7'-5 7/8"	.281 - 8 5/8"	
3.2	44.25	-11.06 x	LL 2 X .216	xx114	0.902	5'-11 1/2"	.216 - 6 7/8"	
Diagonal Towards End								
4.1	16.60	-4.15 x	LLV 1.75 x .143	xx139	0.576	6'-4 7/8"	.143 - 3 7/8"	
4.2	0.51	-15.35 x	LL 2 X .216	xx123	0.953	do	.216 - 2 3/8"	
4.3	15.35	-3.84 x	LL 2 X .216	xx123	0.313	do	.216 - 2 3/8"	
4.4	26.26	-6.56 x	LLV 1.75 x .143	xx139	0.912	6'-4 7/8"	.143 - 6 1/4"	
Diagonal Towards Center								
5.1	7.54	-47.90 x	LL 3 X .281	xx 98	0.979	7'-7 5/8"	.281 - 5 3/4"	
5.2	2.90	-16.59 x	LL 2.5 X .188	xx 97	0.612	6'-4 7/8"	.188 - 3"	
5.3	3.90	-26.24 x	LL 2.5 X .188	xx 97	0.969	6'-4 7/8"	.188 - 4 3/4"	
5.4	6.92	-45.19 x	LL 3 X .224	xx 77	0.938	6'-1"	.224 - 6 3/4"	
Secondary Web Member								
7.1	0.00	-1.98 d	U 1 3/8 x 0.118	z 106	0.456	4'-0"	.118 - 1 1/2"	
7.2	0.00	-2.31 d	do	z 106	0.531	do	do	
7.3	0.00	-2.39 d	do	z 106	0.550	do	do	
7.4	0.00	-2.15 d	do	z 106	0.494	do	do	
7.5	0.00	-1.70 d	U 1 3/8 x 0.118	z 106	0.391	4'-0"	.118 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 41'-0 3/8" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 36'-10 1/8" ==> 1 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 23'-0"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2164 (317.32) / 2293 (336.66)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G11 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft

48G5N17.5

LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 0-6 1/2	Incl. Cmp [deg]
1	1	Near	17.50	12.25	4.80	13'-0"	13'-0"	5	1	90 0
2	1	Near	17.50	12.25	4.80	23'-0"	10'-0"	5	1	90 0
3	1	Near	17.50	12.25	4.80	33'-0"	10'-0"	5	1	90 0
4	1	Near	17.50	12.25	4.80	43'-0"	10'-0"	5	1	90 0
5	1	Far	17.50	17.50	0.00	3'-0"	3'-0"	5	1	90 0
6	1	Far	2.00	2.00	0.00	13'-0"	10'-0"	5	1	90 0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.23 in (L/ 507)
 Joist inertia = 6789.90 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.68 in)

Left Reaction = 50.48/ -6.65 kips Right Reaction = 39.08/ -7.71 kips

No	Tension	Compres.	REQUIRED MATERIAL x = tied at mid-length	Slend.	Util.	Length	REQUIRED WELD Weld-Ea.Side	Remarks
Top Chord								
1.1	41.81	-83.98	LL 4 X .500	z 43	0.442	3'-0"		
1.2	41.81	-67.89 x	do	xx 99	0.631	10'-0"		
1.3	57.19	-141.90	do	z 77	0.962	5'-0"		
1.4	57.19	-141.90	do	z 77	0.962	do		
1.5	60.51	-154.28 x	do	yy 58	0.891	do		
1.6	60.51	-154.28 x	do	yy 58	0.891	do		
1.7	54.40	-120.67	do	z 77	0.818	do		
1.8	54.40	-120.67	do	z 77	0.818	5'-0"		
1.9	39.69	-45.95	do	z 70	0.536	4'-7"		
1.10	39.69	-45.95	LL 4 X .500	z 68	0.287	4'-7"		
Bottom Chord								
2.1	0.00	0.00	LL 4 X .375	z 96	0.621	6'-6"		
2.2	124.20	-22.44	do	z 175	0.807	11'-6"		
2.3	159.58	-30.48	do	z 152	0.930	10'-0"		
2.4	148.97	-29.08	do	z 152	0.868	10'-0"		
2.5	92.35	-18.25	do	z 146	0.744	9'-7"		
2.6	0.00	0.00	LL 4 X .375	z 67	0.461	4'-7"		
End Diagonal								
3.1	97.95	-24.49 x	LL 3 X .313	xx 96	0.917	7'-5 7/8"	.313 - 10 5/8"	T45
3.2	59.82	-14.96	LL 2.5 X .230	z 142	0.921	5'-11 1/2"	.230 - 8 3/4"	T45
Diagonal Towards End								
4.1	22.24	-5.56 x	LL 2 X .163	xx121	0.593	6'-4 7/8"	.163 - 4 5/8"	
4.2	0.88	-20.83 x	LL 2.5 X .188	xx 97	0.768	do	.188 - 3 3/4"	
4.3	20.83	-5.21 x	LL 2.5 X .188	xx 97	0.384	do	.188 - 3 3/4"	
4.4	35.57	-8.89 x	LL 2 X .163	xx121	0.948	6'-4 7/8"	.163 - 7 3/8"	
Diagonal Towards Center								
5.1	13.17	-65.23 x	LL 3.5 X .313	xx 84	0.857	7'-7 5/8"	.313 - 7"	
5.2	5.06	-22.22 x	LL 2.5 X .250	xx 98	0.617	6'-4 7/8"	.250 - 3"	
5.3	6.81	-35.56 x	LL 2.5 X .250	xx 98	0.987	6'-4 7/8"	.250 - 4 3/4"	
5.4	12.08	-61.11 x	LL 3 X .281	xx 77	0.972	6'-1"	.281 - 7 3/8"	
Secondary Web Member								
7.1	0.00	-23.77	LL 3 X .224	z 104	0.682	5'-3 3/4"	.224 - 3 5/8"	
7.2	0.00	-2.97 d	U 1 3/8 x 0.118	z 106	0.678	4'-0"	.118 - 1 1/2"	
7.3	0.00	-3.23 d	do	z 106	0.737	do	do	
7.4	0.00	-2.53 d	U 1 3/8 x 0.118	z 106	0.576	do	.118 - 1 1/2"	
7.5	0.00	-0.96	U 1 x 1 x 0.090	z 160	0.724	4'-0"	.091 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging
 @ Top Chord: 41'-5 1/8" ==> 0 Row(s) Minimum Laterals supports
 Concentrated loads

@ Bottom Chord: 41'-0 3/8" ==> 2 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 23'-0"

KB 33'-0"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2868 (416.57) / 3036 (440.29)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G12 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 0.00 lb/ft 48G5N25.0 LIVE LOAD ...: 0.00 lb/ft

----- CONCENTRATED LOADS -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 0-6 1/2	Incl. Cmp [deg]
1	1	Near	25.00	17.50	6.84	13'-0"	13'-0"	5	1	90 0
2	1	Near	25.00	17.50	6.84	23'-0"	10'-0"	5	1	90 0
3	1	Near	25.00	17.50	6.84	33'-0"	10'-0"	5	1	90 0
4	1	Near	25.00	17.50	6.84	43'-0"	10'-0"	5	1	90 0
5	1	Far	25.00	25.00	0.00	3'-0"	3'-0"	5	1	90 0
6	1	Far	2.90	2.90	0.00	13'-0"	10'-0"	5	1	90 0

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-55.00	55.00	0.00	0.00
(case 2)...	0.00	0.00	55.00	-55.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.31 in (L/ 476)
 Joist inertia = 9118.51 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.15 in)

Left Reaction = 72.14/ -9.48 kips Right Reaction = 55.82/ -10.99 kips

REQUIRED MATERIAL

REQUIRED WELD

No Tension Compres. x = tied at mid-length Slend. Util. Length Weld-Ea.Side Remarks

Top Chord

1.1	59.82	-121.41		LL 5 X .5	z 35	0.481	3'-0"		
1.2	59.82	-98.15	x	do	xx 78	0.720	10'-0"		
1.3	82.01	-205.13		do	z 61	0.958	5'-0"		
1.4	82.01	-205.13		do	z 61	0.958	do		
1.5	86.80	-222.99	x	do	yy 49	0.955	do		
1.6	86.80	-222.99	x	do	yy 49	0.955	do		
1.7	77.98	-174.39		do	z 61	0.814	do		
1.8	77.98	-174.39		do	z 61	0.814	5'-0"		
1.9	56.76	-65.86		do	z 56	0.612	4'-7"		
1.10	56.76	-65.86		LL 5 X .5	z 54	0.292	4'-7"		

Bottom Chord

2.1	0.00	0.00		LL 5 X .438	z 77	0.613	6'-6"		
2.2	179.57	-32.37		do	z 140	0.787	11'-6"		
2.3	230.67	-43.96		do	z 122	0.918	10'-0"		
2.4	215.30	-41.95		do	z 122	0.857	10'-0"		
2.5	133.47	-26.32		do	z 117	0.734	9'-7"		
2.6	0.00	0.00		LL 5 X .438	z 54	0.455	4'-7"		

End Diagonal

3.1	141.22	-35.30		LL 3.5 X .375	z 129	0.947	7'-5 7/8"	.313 - 15 1/4"	T45
3.2	86.05	-21.51		LL 3 X .25	z 118	0.998	5'-11 1/2"	.250 - 11 5/8"	T45

Diagonal Towards End

4.1	31.98	-8.00	x	LL 2.5 X .188	xx 96	0.589	6'-4 7/8"	.188 - 5 3/4"	
4.2	1.27	-29.99	x	LL 2.5 X .230	xx 97	0.892	do	.230 - 4 3/8"	
4.3	29.99	-7.50	x	LL 2.5 X .230	xx 97	0.456	do	.230 - 4 3/8"	
4.4	51.22	-12.80	x	LL 2.5 X .188	xx 96	0.944	6'-4 7/8"	.188 - 9 1/4"	

Diagonal Towards Center

5.1	18.94	-94.08	x	LL 4 X .375	xx 73	0.807	7'-7 5/8"	.313 - 10 1/8"	
5.2	7.26	-31.97	x	LL 3 X .25	xx 81	0.603	6'-4 7/8"	.250 - 4 3/8"	
5.3	9.79	-51.20	x	LL 3 X .25	xx 81	0.966	6'-4 7/8"	.250 - 6 7/8"	
5.4	17.35	-87.93	x	LL 3.5 X .313	xx 66	0.977	6'-1"	.313 - 9 1/2"	

Secondary Web Member

7.1	0.00	-34.14		LL 3 X .224	z 104	0.970	5'-3 3/4"	.224 - 5 1/8"	
7.2	0.00	-4.25	d	U 1 3/8 x 0.118	z 104	0.949	4'-0"	.118 - 1 1/2"	
7.3	0.00	-4.61	d	U 1 3/8 x 0.157	z 102	0.562	do	.158 - 1 1/2"	
7.4	0.00	-3.61	d	U 1 3/8 x 0.118	z 104	0.807	do	.118 - 1 1/2"	
7.5	0.00	-1.36		U 1 x 1 x 0.090	z 158	1.003	4'-0"	.091 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 49'-3 3/4" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 49'-2 1/4" ==> 1 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 23'-0"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,
-U = 1 U profile,

BL = 2 angles welded in box,

BR = Round bar

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

3828 (618.16) / 4054 (654.55)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G13 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 0.00 lb/ft 48G5N17.5 LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 0-6 1/2	Incl. [deg]	Cmp
1	1	Near	17.50	12.25	4.80	10'-6"	10'-6"	5	1	90	0
2	1	Near	17.50	12.25	4.80	20'-6"	10'-0"	5	1	90	0
3	1	Near	17.50	12.25	4.80	30'-6"	10'-0"	5	1	90	0
4	1	Near	17.50	12.25	4.80	40'-6"	10'-0"	5	1	90	0
5	1	Far	17.50	17.50	0.00	0'-6 1/4"	0'-6 1/4"	6	1	90	0
6	1	Far	1.20	12.00	0.00	10'-6"	9'-11 3/4"	5	1	90	0
7	1	Far	17.50	17.50	0.00	50'-6"	40'-0"	5	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.44 in (L/ 432)
 Joist inertia = 6428.75 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)
 (Fy = 50 Ksi U/N)

(Eff. depth = 45.70 in)

Left Reaction = 54.65/ -7.35 kips Right Reaction = 51.59/ -7.02 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	40.53	-57.22	LL 4 X .438	z 78	0.850	5'-3"		
1.2	40.53	-57.22	do	z 80	0.658	5'-3"		
1.3	55.59	-126.66	do	z 76	0.980	5'-0"		
1.4	55.59	-126.66	do	z 76	0.976	do		
1.5	60.73	-152.10 x	do	yy 58	0.998	do		
1.6	60.73	-152.10 x	do	yy 58	0.998	do		
1.7	56.44	-131.57	do	z 76	1.008	do		
1.8	56.44	-131.57	do	z 76	1.008	5'-0"		
1.9	41.18	-57.60 x	do	xx 98	0.662	10'-0"		
1.10	41.18	-76.75	LL 4 X .438	z 23	0.414	1'-8"		
Bottom Chord								
2.1	0.00	0.00	LL 4 X .375	z 77	0.512	5'-3"		
2.2	102.43	-19.94	do	z 156	0.754	10'-3"		
2.3	150.87	-29.80	do	z 152	0.879	10'-0"		
2.4	153.32	-30.23	do	z 152	0.894	10'-0"		
2.5	109.80	-21.22	do	z 165	0.766	10'-10"		
2.6	0.00	0.00	LL 4 X .375	z 86	0.549	5'-10"		
End Diagonal								
3.1	64.00	-16.00 x	LL 2.5 X .230	xx 99	0.972	6'-5 5/8"	.230 - 9 3/8"	T45
3.2	92.47	-23.12	LL 3 X .313	z 139	0.866	6'-11 1/4"	.313 - 10"	T45
Diagonal Towards End								
4.1	30.45	-7.61 x	LL 1.75 X .155	xx139	0.979	6'-4 7/8"	.155 - 6 5/8"	
4.2	22.55	-5.64 x	LL 2.5 X .188	xx 97	0.415	do	.188 - 4"	
4.3	2.07	-22.55 x	LL 2.5 X .188	xx 97	0.831	do	.188 - 4"	
4.4	27.36	-6.84 x	LL 1.75 X .155	xx139	0.880	6'-4 7/8"	.155 - 6"	
Diagonal Towards Center								
5.1	12.52	-63.27 x	LL 3 X .313	xx 84	0.981	6'-7 1/4"	.313 - 6 7/8"	
5.2	6.20	-30.43 x	LL 2.5 X .230	xx 98	0.911	6'-4 7/8"	.230 - 4 1/2"	
5.3	5.67	-27.35 x	LL 2.5 X .230	xx 98	0.818	6'-4 7/8"	.230 - 4"	
5.4	12.85	-62.34 x	LL 3.5 X .313	xx 77	0.767	7'-0 7/8"	.313 - 6 3/4"	
Secondary Web Member								
7.1	0.00	-1.22	U 1 x 1 x 0.090	z 160	0.921	4'-0"	.091 - 1 1/2"	
7.2	0.00	-2.65 d	U 1 3/8 x 0.118	z 106	0.606	do	.118 - 1 1/2"	
7.3	0.00	-3.19 d	do	z 106	0.728	do	do	
7.4	0.00	-2.76 d	U 1 3/8 x 0.118	z 106	0.629	4'-0"	.118 - 1 1/2"	
7.5	0.00	-25.94	LL 3 X .224	z 114	0.873	5'-9 1/4"	.224 - 3 7/8"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:

41'-2" ==>

0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 41'-0 3/8" ==> 2 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 20'-6"

KB 30'-6"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transfered by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2696 (389.32) / 2864 (413.05)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G14 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft

48G5N25.0

LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	25.00	17.50	6.84	10'-6"	10'-6"	5	1	90	0
2	1	Near	25.00	17.50	6.84	20'-6"	10'-0"	5	1	90	0
3	1	Near	25.00	17.50	6.84	30'-6"	10'-0"	5	1	90	0
4	1	Near	25.00	17.50	6.84	40'-6"	10'-0"	5	1	90	0
5	1	Far	25.00	25.00	0.00	0'-6 1/4"	0'-6 1/4"	6	1	90	0
6	1	Far	1.80	1.80	0.00	10'-6"	9'-11 3/4"	5	1	90	0
7	1	Far	25.00	25.00	0.00	50'-6"	40'-0"	5	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	--L--	--R--	--L--	--R--	--L--	--R--
(Q) Wind or Seism (case 1)...	0.00	0.00	-55.00	55.00	0.00	0.00
(case 2)...	0.00	0.00	55.00	-55.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 7 1/2"

at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.73 in (L/ 360)
 Calculated deflection under service live load = 1.26 in (L/ 495)
 Joist inertia = 9118.51 in⁴
 Required camber = 1.11 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.15 in)

Left Reaction = 78.13/ -10.48 kips Right Reaction = 73.71/ -10.01 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	58.01	-74.14	LL 5 X .5	z 62	0.716	5'-3"		
1.2	58.01	-74.14	do	z 64	0.659	5'-3"		
1.3	79.74	-183.27	do	z 61	0.863	5'-0"		
1.4	79.74	-183.27	do	z 61	0.860	do		
1.5	87.16	-220.00 x	do	yy 49	0.943	do		
1.6	87.16	-220.00 x	do	yy 49	0.943	do		
1.7	80.96	-190.28	do	z 61	0.889	do		
1.8	80.96	-190.28	do	z 61	0.889	5'-0"		
1.9	58.94	-83.30 x	do	xx 78	0.668	10'-0"		
1.10	58.94	-110.98	LL 5 X .5	z 18	0.410	1'-8"		
Bottom Chord								
2.1	0.00	0.00	LL 5 X .438	z 62	0.506	5'-3"		
2.2	148.27	-28.78	do	z 125	0.753	10'-3"		
2.3	218.24	-43.00	do	z 122	0.869	10'-0"		
2.4	221.75	-43.62	do	z 122	0.882	10'-0"		
2.5	158.79	-30.62	do	z 132	0.756	10'-10"		
2.6	0.00	0.00	LL 5 X .438	z 69	0.542	5'-10"		
End Diagonal								
3.1	92.24	-23.06	LL 3 X .281	z 128	0.957	6'-5 5/8"	.281 - 11 1/8"	T45
3.2	133.22	-33.31	LL 3.5 X .375	z 119	0.894	6'-11 1/4"	.313 - 14 3/8"	T45
Diagonal Towards End								
4.1	43.79	-10.95 x	LL 2 X .216	xx122	0.893	6'-4 7/8"	.216 - 6 7/8"	
4.2	32.48	-8.12 x	LL 2.5 X .230	xx 97	0.493	do	.230 - 4 3/4"	
4.3	0.39	-32.48 x	LL 2.5 X .230	xx 97	0.966	do	.230 - 4 3/4"	
4.4	39.41	-9.85 x	LL 2 X .216	xx122	0.804	6'-4 7/8"	.216 - 6 1/8"	
Diagonal Towards Center								
5.1	17.99	-91.21 x	LL 3.5 X .344	xx 72	0.968	6'-7 1/4"	.313 - 9 7/8"	
5.2	8.91	-43.78 x	LL 3 X .224	xx 80	0.941	6'-4 7/8"	.224 - 6 5/8"	
5.3	8.14	-39.39 x	LL 3 X .224	xx 80	0.846	6'-4 7/8"	.224 - 6"	
5.4	18.48	-89.83 x	LL 3.5 X .344	xx 77	1.003	7'-0 7/8"	.313 - 9 3/4"	
Secondary Web Member								
7.1	0.00	-1.75	U 1 x 1 x 0.118	z 153	0.924	4'-0"	.118 - 1 1/2"	
7.2	0.00	-3.79 d	U 1 3/8 x 0.118	z 104	0.848	do	.118 - 1 1/2"	
7.3	0.00	-4.55 d	U 1 3/8 x 0.157	z 102	0.555	do	.158 - 1 1/2"	
7.4	0.00	-3.94 d	U 1 3/8 x 0.118	z 104	0.880	4'-0"	.118 - 1 1/2"	
7.5	0.00	-37.30	LL 3 X .313	z 114	0.917	5'-9 1/4"	.313 - 4"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 49'-3 3/4" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 49'-2 1/4" ==> 1 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 30'-6"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,
-U = 1 U profile,

BL = 2 angles welded in box,
UU = 2 U profiles one inside the other,

BR = Round bar
-CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transfered by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

3811 (618.39) / 4037 (654.78)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G15 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft 48G6N17.5 LIVE LOAD ...: 0.00 lb/ft

----- CONCENTRATED LOADS -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. Cmp [deg]
1	1	Near	17.50	12.25	4.80	14'-0 1/4"	14'-0 1/4"	5	1	90 0
2	1	Near	17.50	12.25	4.80	24'-0 1/4"	10'-0"	5	1	90 0
3	1	Near	17.50	12.25	4.80	34'-0 1/4"	10'-0"	5	1	90 0
4	1	Near	17.50	12.25	4.80	44'-0 1/4"	10'-0"	5	1	90 0
5	1	Near	17.50	12.25	4.80	54'-0 1/4"	10'-0"	5	1	90 0
6	1	Far	8.80	8.80	0.00	4'-0 1/4"*	4'-0 1/4"	6	1	90 0

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 7 1/2"

at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.97 in (L/ 360)
 Calculated deflection under service live load = 1.74 in (L/ 408)
 Joist inertia = 7663.38 in⁴
 Required camber = 1.48 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)
 (Fy = 50 Ksi U/N)

(Eff. depth = 45.43 in)

Left Reaction = 45.70/ -7.69 kips Right Reaction = 50.66/ -10.27 kips

			REQUIRED MATERIAL					REQUIRED WELD		Remarks
No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side			
Top Chord										
1.1	44.80	-75.68	LL 5 X .438	z 83	0.942	7'-0 1/8"				
1.2	44.80	-75.68	do	z 43	0.942	3'-6 1/8"				
1.3	59.04	-144.02	do	z 43	0.760	3'-6 1/8"				
1.4	59.04	-144.02	do	z 61	0.953	5'-0"				
1.5	69.86	-195.24 x	do	YY 49	0.968	do				
1.6	69.86	-195.24 x	do	YY 49	0.974	do				
1.7	71.19	-200.20 x	do	YY 49	0.991	do				
1.8	71.19	-200.20 x	do	YY 49	0.991	do				
1.9	63.03	-158.90	do	z 61	0.974	do				
1.10	63.03	-158.90	do	z 61	0.854	do				
1.11	45.39	-71.35	do	z 61	0.773	5'-0"				
1.12	45.39	-71.35	LL 5 X .438	z 65	0.396	5'-6"				
Bottom Chord										
2.1	0.00	0.00	LL 4 X .438	z 105	0.474	7'-0 1/8"				
2.2	109.86	-21.01	do	z 107	0.732	7'-0 1/8"				
2.3	169.64	-33.54	do	z 153	0.854	10'-0"				
2.4	197.72	-39.62	do	z 153	0.995	do				
2.5	179.56	-36.20	do	z 153	0.904	do				
2.6	115.14	-23.30	do	z 153	0.794	10'-0"				
2.7	0.00	0.00	LL 4 X .438	z 82	0.511	5'-6"				
End Diagonal										
3.1	86.49	-21.62 x	LL 3 X .281	xx101	0.897	7'-11 1/8"	.281 - 10 3/8"			
3.2	87.50	-21.88	LL 3 X .313	z 133	0.819	6'-8"	.313 - 9 1/2"			
Diagonal Towards End										
4.1	50.28	-12.57 x	LL 2.5 X .188	xx 80	0.926	5'-3 7/8"	.188 - 9"			
4.2	32.11	-8.03 x	LL 2 X .142	xx121	0.977	6'-4 7/8"	.142 - 7 5/8"			
4.3	25.89	-6.47 x	LL 2 X .142	xx121	0.788	do	.142 - 6 1/8"			
4.4	54.90	-13.72 x	LL 2 X .250	xx124	0.976	6'-4 7/8"	.250 - 7 3/8"			
Diagonal Towards Center										
5.1	10.47	-50.30 x	LL 3 X .224	xx 66	0.958	5'-3 7/8"	.224 - 7 5/8"			
5.2	6.78	-32.13 x	LL 2.5 X .230	xx 97	0.958	6'-4 7/8"	.230 - 4 3/4"			
5.3	0.83	-20.98 x	LL 2.5 X .188	xx 97	0.771	do	.188 - 3 3/4"			
5.4	20.98	-5.25 x	LL 2.5 X .188	xx 97	0.387	do	.188 - 3 3/4"			
5.5	5.11	-25.91 x	LL 2.5 X .230	xx 97	0.773	do	.230 - 3 7/8"			
5.6	11.06	-54.91 x	LL 3 X .281	xx 81	0.911	6'-4 7/8"	.281 - 6 5/8"			
Secondary Web Member										
7.1	0.00	-4.96	LL 2 X .216	z 116	0.272	4'-0"	.216 - 1 1/2"			
7.2	3.50	-17.50	do	z 116	0.961	do	.216 - 2 3/4"			
7.3	3.60	-17.50	do	z 116	0.961	do	do			
7.4	3.60	-17.50	do	z 116	0.961	do	do			
7.5	3.60	-17.50	do	z 116	0.961	do	do			

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	REQUIRED WELD	Remarks
7.6	3.60	-17.50	LL 2 X .216	z 116	0.961	4'-0"	Weld-Ea.Side .216 - 2 3/4"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	49'-2 1/4" ==>	0 Row(s) Minimum
@ Bottom Chord:	41'-3 1/2" ==>	2 Row(s) Minimum

Lateral supports
Concentrated loads
Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB	24'-0 1/4"
KB	34'-0 1/4"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,	BL = 2 angles welded in box,	BR = Round bar
-U = 1 U profile,	UU = 2 U profiles one inside the other,	-CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member	1 = within a panel with no reinforcement
2 = anywhere within a panel	3 = at any panel point along the joist
4 = anywhere along the joist	5 = transferred by an additional member and lateral support
6 = within a panel with no reinforcement and lateral support	

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

3609 (548.39) / 3836 (580.73)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G16 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 0.00 lb/ft 48G6N17.5 LIVE LOAD ...: 0.00 lb/ft

----- CONCENTRATED LOADS -----

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat. 0-6	Chord 1/2	Incl. Cmp [deg]
1	1	Near	17.50	12.25	4.80	10'-2"	10'-2"	5	1	90 0
2	1	Near	17.50	12.25	4.80	20'-2"	10'-0"	5	1	90 0
3	1	Near	17.50	12.25	4.80	30'-2"	10'-0"	5	1	90 0
4	1	Near	17.50	12.25	4.80	40'-2"	10'-0"	5	1	90 0
5	1	Near	17.50	12.25	4.80	50'-2"	10'-0"	5	1	90 0

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.84 in (L/ 360)
 Calculated deflection under service live load = 1.38 in (L/ 480)
 Joist inertia = 7353.08 in⁴
 Required camber = 1.28 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.66 in)

Left Reaction = 40.10/ -8.21 kips Right Reaction = 47.48/ -9.73 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	41.37	-51.81	LL 4 X .500	z 75	0.347	5'-1"		
1.2	41.37	-51.81	do	z 78	0.600	5'-1"		
1.3	58.45	-135.03	do	z 77	0.916	5'-0"		
1.4	58.45	-135.03	do	z 77	0.916	do		
1.5	65.90	-171.35 x	do	yy 58	0.989	do		
1.6	65.90	-171.35 x	do	yy 58	0.989	do		
1.7	63.90	-161.65 x	do	yy 58	0.933	do		
1.8	63.90	-161.65 x	do	yy 58	0.933	do		
1.9	52.47	-105.93	do	z 77	0.718	5'-0"		
1.10	52.47	-105.93	do	z 38	0.612	2'-6"		
1.11	44.40	-66.54	do	z 38	0.612	2'-6"		
1.12	44.40	-66.54	LL 4 X .500	z 82	0.476	5'-6"		
Bottom Chord								
2.1	0.00	0.00	LL 4 X .438	z 75	0.454	5'-1"		
2.2	105.36	-21.61	do	z 154	0.710	10'-1"		
2.3	164.69	-33.78	do	z 153	0.829	10'-0"		
2.4	178.00	-36.51	do	z 153	0.896	do		
2.5	145.29	-29.80	do	z 153	0.800	10'-0"		
2.6	86.24	-17.68	do	z 76	0.653	5'-0"		
2.7	0.00	0.00	LL 4 X .438	z 82	0.388	5'-6"		
End Diagonal								
3.1	65.51	-16.38 x	LL 2.5 X .230	xx 97	0.995	6'-4"	.230 - 9 5/8"	T45
3.2	81.74	-20.44	LL 3 X .313	z 133	0.765	6'-8"	.313 - 8 7/8"	T45
Diagonal Towards End								
4.1	37.29	-9.32 x	LL 2 X .163	xx121	0.994	6'-4 7/8"	.163 - 7 3/4"	
4.2	19.60	-4.90 x	LLV 1.75 x .143	xx139	0.681	do	.143 - 4 5/8"	
4.3	20.56	-5.14 x	LLV 1.75 x .143	xx139	0.714	6'-4 7/8"	.143 - 4 7/8"	
4.4	35.85	-8.96 x	LL 2 X .163	xx 88	0.955	4'-8 5/8"	.163 - 7 1/2"	
Diagonal Towards Center								
5.1	13.73	-66.89 x	LL 3.5 X .313	xx 70	0.773	6'-5 5/8"	.313 - 7 1/4"	
5.2	7.65	-37.27 x	LL 3 X .25	xx 81	0.705	6'-4 7/8"	.250 - 5"	
5.3	1.72	-19.60 x	LL 2.5 X .188	xx 97	0.722	do	.188 - 3 1/2"	
5.4	4.22	-20.54 x	LL 2.5 X .188	xx 97	0.757	do	.188 - 3 3/4"	
5.5	10.16	-49.46 x	LL 3 X .25	xx 81	0.936	6'-4 7/8"	.250 - 6 3/4"	
5.6	7.34	-35.86 x	LL 2.5 X .188	xx 70	1.005	4'-8 5/8"	.188 - 6 1/2"	
Secondary Web Member								
7.1	0.00	-1.08	LL 2 X .216	z 116	0.060	4'-0"	.216 - 1 1/2"	
7.2	0.00	-2.83 d	U 1 3/8 x 0.118	z 106	0.644	do	.118 - 1 1/2"	
7.3	0.00	-3.59 d	do	z 106	0.817	do	do	
7.4	0.00	-3.38 d	do	z 106	0.771	do	do	
7.5	0.00	-2.22 d	U 1 3/8 x 0.118	z 106	0.505	do	.118 - 1 1/2"	

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

No Tension Compres.
7.6 3.60 -17.50

x = tied at mid-length
LL 2 X .216

Slend. Util.
z 116 0.970

Length
4'-0"

REQUIRED WELD

Weld-Ea.Side
.216 - 2 3/4"

Remarks

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 41'-6 5/8" ==>
@ Bottom Chord: 41'-3 1/2" ==>

0 Row(s) Minimum
2 Row(s) Minimum

Laterals supports
Concentrated loads
Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 20'-2"
KE 30'-2"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,
-U = 1 U profile,

BL = 2 angles welded in box,
UU = 2 U profiles one inside the other,

BR = Round bar
-CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member

2 = anywhere within a panel

4 = anywhere along the joist

6 = within a panel with no reinforcement and lateral support

1 = within a panel with no reinforcement

3 = at any panel point along the joist

5 = transferred by an additional member and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

3179 (461.05) / 3361 (487.05)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G17 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 0.00 lb/ft

48G6N17.5

LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat. 0-6	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	17.50	12.25	4.80	6'-3 5/8"	6'-3 5/8"	5	1	90	0
2	1	Near	17.50	12.25	4.80	16'-3 5/8"	10'-0"	5	1	90	0
3	1	Near	17.50	12.25	4.80	26'-3 5/8"	10'-0"	5	1	90	0
4	1	Near	17.50	12.25	4.80	36'-3 5/8"	10'-0"	5	1	90	0
5	1	Near	17.50	12.25	4.80	46'-3 5/8"	10'-0"	5	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

	MOMENTS		AXIAL LOADS			
	---L---	---R---	<<< Top Chord >>>		< Bottom Chord >	
			---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-39.00	39.00	0.00	0.00
(case 2)...	0.00	0.00	39.00	-39.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 7 1/2"

Imposed Rows of Bridging Y/N.: No
at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.72 in (L/ 360)
 Calculated deflection under service live load = 1.24 in (L/ 499)
 Joist inertia = 6287.13 in⁴
 Required camber = 1.09 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.80 in)

Left Reaction = 43.10/ -8.84 kips Right Reaction = 44.46/ -9.12 kips

REQUIRED MATERIAL

REQUIRED WELD

No Tension Compres. x = tied at mid-length Slend. Util. Length Weld-Ea.Side Remarks

Top Chord

1.1	44.87	-69.26	LL 4 X .500	z 94	0.576	6'-3 5/8"		
1.2	44.87	-69.26	do	z 77	0.787	5'-0"		
1.3	58.62	-136.28	do	z 77	0.924	do		
1.4	58.62	-136.28	do	z 77	0.924	do		
1.5	62.96	-157.43 x	do	yy 58	0.909	do		
1.6	62.96	-157.43 x	do	yy 58	0.909	do		
1.7	57.89	-132.71	do	z 77	0.909	do		
1.8	57.89	-132.71	do	z 77	0.900	do		
1.9	43.40	-62.11	do	z 77	0.766	5'-0"		
1.10	43.40	-62.11	LL 4 X .500	z 82	0.444	5'-6"		

Bottom Chord

2.1	0.00	0.00	LL 3.5 X .375	z 107	0.591	6'-3 5/8"		
2.2	102.77	-21.09	do	z 175	0.867	10'-0"		
2.3	146.86	-30.13 x	do	yy129	0.985	do		
2.4	145.08	-29.77 x	do	yy129	0.973	do		
2.5	97.42	-19.99	do	z 175	0.834	10'-0"		
2.6	0.00	0.00	LL 3.5 X .375	z 93	0.560	5'-6"		

End Diagonal

3.1	81.57	-20.39	LL 3.5 X .375	z 126	0.547	7'-3 7/8"	.313 - 8 7/8"	T45
3.2	76.38	-19.09	LL 3 X .313	z 134	0.715	6'-8"	.313 - 8 1/4"	T45

Diagonal Towards End

4.1	42.15	-10.54 x	LL 2 X .216	xx123	0.860	6'-4 7/8"	.216 - 6 5/8"	
4.2	18.32	-4.58 x	LL 1.5 X .156	xx164	0.927	do	.156 - 4"	
4.3	18.32	-4.58 x	LL 1.5 X .156	xx164	0.927	do	.156 - 4"	
4.4	44.40	-11.10 x	LL 2 X .216	xx123	0.905	6'-4 7/8"	.216 - 6 7/8"	

Diagonal Towards Center

5.1	8.64	-42.17 x	LL 3 X .224	xx 81	0.910	6'-4 7/8"	.224 - 6 3/8"	
5.2	2.72	-18.32 x	LL 2.5 X .188	xx 97	0.676	do	.188 - 3 1/4"	
5.3	3.18	-18.32 x	LL 2.5 X .188	xx 97	0.676	do	.188 - 3 1/4"	
5.4	9.11	-44.42 x	LL 3 X .224	xx 81	0.958	6'-4 7/8"	.224 - 6 3/4"	

Secondary Web Member

7.1	3.60	-17.50	LL 2 X .216	z 117	0.977	4'-0"	.216 - 2 3/4"	
7.2	3.60	-17.50	do	z 117	0.977	do	do	
7.3	3.60	-17.50	do	z 117	0.977	do	do	
7.4	3.60	-17.50	do	z 117	0.977	do	do	
7.5	3.60	-17.50	LL 2 X .216	z 117	0.977	4'-0"	.216 - 2 3/4"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 41'-6 5/8" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 37'-1 1/4" ==> 2 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 16'-3 5/8"

KB 36'-3 5/8"

v3.6 12/05/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transfered by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2717 (399.88) / 2881 (424.26)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: G18 (JOIST GIRDER, Asymetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 0.00 lb/ft

48G5N25.0

LIVE LOAD ...: 0.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. Cmp [deg]
1	1	Near	25.00	17.50	6.84	12'-5 3/8"	12'-5 3/8"	5	1	90 0
2	1	Near	25.00	17.50	6.84	22'-5 3/8"	10'-0"	5	1	90 0
3	1	Near	25.00	17.50	6.84	32'-5 3/8"	10'-0"	5	1	90 0
4	1	Near	25.00	17.50	6.84	42'-5 3/8"	10'-0"	5	1	90 0
5	1	Far	8.80	8.80	0.00	2'-5 3/8"	2'-5 3/8"	6	1	90 0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-55.00	55.00	0.00	0.00
(case 2)...	0.00	0.00	55.00	-55.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 7 1/2"

at right: 7 1/2"

DEFLECTION

Allowed deflection under live load = 1.59 in (L/ 360)
 Calculated deflection under service live load = 1.03 in (L/ 554)
 Joist inertia = 7663.38 in⁴
 Required camber = 0.92 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 45.43 in)

Left Reaction = 51.10/ -8.75 kips Right Reaction = 57.75/ -11.74 kips

REQUIRED MATERIAL

REQUIRED WELD

No Tension Compres. x = tied at mid-length Slend. Util. Length Weld-Ea.Side Remarks

Top Chord

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
1.1	57.58	-72.99	LL 5 X .438	z 74	0.964	6'-2 3/4"		
1.2	57.58	-72.99	do	z 38	0.781	3'-1 3/8"		
1.3	71.97	-142.54	do	z 38	0.738	3'-1 3/8"		
1.4	71.97	-142.54	do	z 61	0.918	5'-0"		
1.5	81.56	-188.21 x	do	yy 49	0.933	do		
1.6	81.56	-188.21 x	do	yy 49	0.933	do		
1.7	77.61	-167.81	do	z 61	0.916	do		
1.8	77.61	-167.81	do	z 61	0.902	do		
1.9	60.13	-81.34	do	z 61	0.816	5'-0"		
1.10	60.13	-81.34	LL 5 X .438	z 65	0.451	5'-6"		

Bottom Chord

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
2.1	0.00	0.00	LL 4 X .438	z 93	0.465	6'-2 3/4"		
2.2	107.77	-21.19	do	z 95	0.713	6'-2 3/4"		
2.3	165.38	-33.17	do	z 153	0.832	10'-0"		
2.4	178.02	-35.99	do	z 153	0.896	do		
2.5	124.58	-25.28	do	z 153	0.789	10'-0"		
2.6	0.00	0.00	LL 4 X .438	z 82	0.554	5'-6"		

End Diagonal

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
3.1	86.07	-21.52	LL 3 X .313	z 145	0.857	7'-3 1/8"	.313 - 9 1/4"	
3.2	99.75	-24.94	LL 3.5 X .375	z 114	0.669	6'-8"	.313 - 10 3/4"	

Diagonal Towards End

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
4.1	54.75	-13.69 x	LL 2 X .250	xx 97	0.973	5'-0 7/8"	.250 - 7 3/8"	
4.2	28.63	-7.16 x	LLV 1.75 x .143	xx139	0.994	6'-4 7/8"	.143 - 6 3/4"	
4.3	23.92	-5.98 x	LLV 1.75 x .143	xx139	0.830	do	.143 - 5 5/8"	
4.4	54.22	-13.55 x	LL 2.5 X .188	xx 97	0.999	6'-4 7/8"	.188 - 9 3/4"	

Diagonal Towards Center

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
5.1	11.32	-54.76 x	LL 3 X .25	xx 63	0.886	5'-0 7/8"	.250 - 7 3/8"	
5.2	6.00	-28.65 x	LL 2.5 X .230	xx 97	0.855	6'-4 7/8"	.230 - 4 1/4"	
5.3	2.47	-23.92 x	LL 2.5 X .230	xx 97	0.713	do	.230 - 3 1/2"	
5.4	10.96	-54.24 x	LL 3 X .281	xx 81	0.900	6'-4 7/8"	.281 - 6 1/2"	

Secondary Web Member

No	Tension	Compres.	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
7.1	0.00	-3.31	LL 2.5 X .188	z 92	0.115	4'-0"	.188 - 1 1/2"	
7.2	5.13	-25.00	do	z 92	0.865	do	.188 - 4 1/2"	
7.3	5.13	-25.00	do	z 92	0.865	do	do	
7.4	5.13	-25.00	do	z 92	0.865	do	do	
7.5	5.13	-25.00	LL 2.5 X .188	z 92	0.865	4'-0"	.188 - 4 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 49'-2 1/4" ==> 0 Row(s) Minimum

Laterals supports
Concentrated loads

@ Bottom Chord: 41'-3 1/2" ==> 1 Row(s) Minimum Acc. to the force

POSITION

@ Top Chord

@ Bottom Chord

KB 22'-5 3/8"

v3.6 12/06/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member

1 = within a panel with no reinforcement

2 = anywhere within a panel

3 = at any panel point along the joist

4 = anywhere along the joist

5 = transferred by an additional member and lateral support

6 = within a panel with no reinforcement and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault

Shop: Canam Sunnyside [Production]


2961 (450.39) / 3170 (480.15)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C1 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

$$\Delta = \frac{81 \frac{1}{8}}{12} \quad 1 \frac{1}{8}"$$



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD 652.02 lb/ft

44LH15

LIVE LOAD ... 382.29 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N..... Yes
Bearing Depth... [in]: at left: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 2.40 in (L/ 360)
 Calculated deflection under service live load = 2.27 in (L/ 379)
 Joist inertia = 4017.73 in⁴
 Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THAT SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 42.00 in)

Left Reaction = 23.60/ -4.00 kips

Right Reaction = 23.60/ -4.00 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

1.1	16.49	-57.07	x	LL 3.5 X .375	xx 73	0.827	6'-8"
1.2	16.11	-54.32		do	z 68	0.827	3'-10 1/2"
1.3	19.28	-77.43		do	z 48	0.673	3'-8"
1.4	19.24	-77.19		do	z 48	0.806	do
1.5	22.64	-102.00		do	z 48	0.862	do
1.6	22.61	-101.77		do	z 48	0.908	do
1.7	24.63	-116.56		do	z 48	0.980	do
1.8	24.60	-116.33		do	z 48	0.978	do
1.9	25.25	-121.10	x	do	zz 32	0.939	do
1.10	25.22	-120.86	x	do	zz 32	0.939	do
1.11	24.50	-115.62		do	z 48	0.972	do
1.12	24.47	-115.39		do	z 48	0.971	do
1.13	22.38	-100.13		do	z 48	0.900	do
1.14	22.35	-99.89		do	z 48	0.844	do
1.15	18.89	-74.61		do	z 48	0.792	do
1.16	18.86	-74.38		do	z 48	0.648	3'-8"
1.17	15.63	-50.79		do	z 68	0.799	3'-10 1/2"
1.18	15.92	-52.87	x	LL 3.5 X .375	xx 73	0.799	6'-8"

Bottom Chord

2.1	0.00	0.00		LL 3.5 X .313	z 163	0.407	9'-6 1/8"
2.2	59.62	-8.16		do	z 88	0.612	5'-0 1/2"
2.3	89.68	-12.27		do	z 128	0.749	7'-4"
2.4	109.71	-15.01		do	z 128	0.874	do
2.5	119.73	-16.38		do	z 128	0.953	do
2.6	119.73	-16.38		do	z 128	0.953	do
2.7	109.71	-15.01		do	z 128	0.874	do
2.8	89.68	-12.27		do	z 128	0.749	7'-4"
2.9	59.62	-8.16		do	z 88	0.612	5'-0 1/2"
2.10	0.00	0.00		LL 3.5 X .313	z 151	0.407	8'-9 7/8"

End Diagonal

3.1	58.98	-8.07	x	LL 2.5 X .230	zz118	0.896	9'-8 5/8"	.230 - 8 5/8"
3.2	58.98	-8.07	x	LL 2.5 X .230	zz118	0.896	9'-8 5/8"	.230 - 8 5/8"

Diagonal Towards End

4.1	22.50	-3.08	x	LL 1.5 X .156	zz103	0.845	5'-2 1/4"	.156 - 4 7/8"
4.2	15.58	-2.13	d	U 1 3/8 x 0.157	yy113	0.895	do	.158 - 3 3/8"
4.3	8.66	-1.18		U 1 x 1 x 0.118	yy161	0.977	do	.118 - 2 1/2"
4.4	8.54	-0.24		do	yy161	0.965	do	do
4.5	8.54	-0.24		do	yy161	0.965	do	do
4.6	8.66	-1.18		U 1 x 1 x 0.118	yy161	0.977	do	.118 - 2 1/2"
4.7	15.58	-2.13	d	U 1 3/8 x 0.157	yy113	0.895	do	.158 - 3 3/8"
4.8	22.50	-3.08	x	LL 1.5 X .156	zz103	0.845	5'-2 1/4"	.156 - 4 7/8"

Diagonal Towards Center

5.1	2.65	-19.33	x	LLV 1.75 x .143	zz 65	0.957	3'-11"	.143 - 4 5/8"
5.2	2.61	-19.04	x	LL 2 X .142	zz 77	0.949	5'-2 1/4"	.142 - 4 1/2"
5.3	1.66	-12.12	x	LL 1.5 X .156	zz103	0.979	do	.156 - 2 5/8"
5.4	0.71	-8.54	x	do	zz103	0.990	do	.156 - 1 7/8"
5.5	0.71	-8.54	x	do	zz103	0.990	do	.156 - 1 7/8"
5.6	1.66	-12.12	x	LL 1.5 X .156	zz103	0.979	do	.156 - 2 5/8"
5.7	2.61	-19.04	x	LL 2 X .142	zz 77	0.949	5'-2 1/4"	.142 - 4 1/2"

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.	x	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
				x = tied at mid-length LLV 1.75 x .143				Weld-Ea.Side .143 - 4 5/8"	
5.8	2.65	-19.33	x		zz 65	0.957	3'-11"		
Secondary Web Member									
7.1	0.57	-4.46	d	U 1 3/8 x 0.118	z 119	0.807	4'-5 1/4"	.118 - 1 1/2"	
7.2	0.33	-2.80		U 1 x 1 x 0.090	z 147	1.001	3'-8"	.091 - 1 1/2"	
7.3	0.33	-2.93		U 1 x 1 x 0.118	yy111	0.815	do	.118 - 1 1/2"	
7.4	0.33	-3.00		do	yy111	0.836	do	do	
7.5	0.33	-3.03		do	yy111	0.843	do	do	
7.6	0.33	-3.00		do	yy111	0.835	do	do	
7.7	0.33	-2.92		U 1 x 1 x 0.118	yy111	0.812	do	.118 - 1 1/2"	
7.8	0.33	-2.78		U 1 x 1 x 0.090	z 147	0.996	3'-8"	.091 - 1 1/2"	
7.9	0.57	-4.44	d	U 1 3/8 x 0.118	z 119	0.803	4'-5 1/4"	.118 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging
 @ Top Chord: 26'-2 3/8" ==> 3 Row(s) Minimum
 @ Bottom Chord: 36'-8 5/8" ==> 5 Row(s) Minimum
 Laterals supports
 Deck (36")
 Acc. to the code

POSITION

	@ Top Chord	@ Bottom Chord
XB	18'-1 1/4" (18'-0 1/4")	9'-2" (9'-1 1/2")
XB	36'-2 1/2" (36'-0 5/8")	XB 18'-1 1/4" (18'-0 1/4")
XB	54'-3 3/4" (54'-0 7/8")	XB 36'-2 1/2" (36'-0 5/8")
		XB 54'-3 3/4" (54'-0 7/8")
		63'-3" (62'-11 3/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
 -U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061 Designer: Philippe Theriault
 2477 (378.17) / 2712 (413.53)


Shop: Canam Sunnyside [Production]

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C2 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

$$\Delta = \frac{81 \frac{1}{8}}{12} \quad 1 \frac{1}{8}"$$



----- **LOADING CONDITIONS** -----
(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 652.40 lb/ft 44LH15 LIVE LOAD ...: 382.73 lb/ft

----- **END MOMENTS [ft-kip] & AXIAL LOADS [kips]** -----

MOMENTS

AXIAL LOADS

	---L---	---R---	<<< Top Chord >>>	< Bottom Chord >	
			---L---	---R---	
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

----- **UPLIFT** -----

Net uplift uniform load : 120.00 lb/ft

----- **DEFLECTION** -----

Allowed deflection under live load = 2.40 in (L/ 360)
Calculated deflection under service live load = 2.27 in (L/ 380)
Joist inertia = 4017.73 in⁴
Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THAT SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 42.00 in)

Left Reaction = 23.60/ -4.00 kips

Right Reaction = 23.60/ -4.00 kips

No	Tension	Compres.	REQUIRED MATERIAL x = tied at mid-length	Slend.	Util.	Length	REQUIRED WELD Weld-Ea.Side	Remarks
Top Chord								
1.1	16.49	-57.07	x LL 3.5 X .375	xx 73	0.827	6'-8"		
1.2	16.11	-54.32	do	z 67	0.827	3'-10 1/4"		
1.3	19.26	-77.33	do	z 48	0.672	3'-8"		
1.4	19.22	-77.10	do	z 48	0.805	do		
1.5	22.62	-101.92	do	z 48	0.861	do		
1.6	22.59	-101.69	do	z 48	0.908	do		
1.7	24.61	-116.49	do	z 48	0.980	do		
1.8	24.58	-116.25	do	z 48	0.978	do		
1.9	25.23	-121.03	x do	zz 32	0.939	do		
1.10	25.20	-120.79	x do	zz 32	0.939	do		
1.11	24.48	-115.55	do	z 48	0.972	do		
1.12	24.45	-115.31	do	z 48	0.970	do		
1.13	22.36	-100.04	do	z 48	0.900	do		
1.14	22.33	-99.81	do	z 48	0.844	do		
1.15	18.87	-74.51	do	z 48	0.791	do		
1.16	18.84	-74.28	do	z 48	0.647	3'-8"		
1.17	15.63	-50.79	do	z 67	0.799	3'-10 1/4"		
1.18	15.91	-52.87	x LL 3.5 X .375	xx 73	0.799	6'-8"		
Bottom Chord								
2.1	0.00	0.00	LL 3.5 X .313	z 163	0.406	9'-6 1/8"		
2.2	59.52	-8.14	do	z 87	0.611	5'-0 1/4"		
2.3	89.59	-12.25	do	z 128	0.748	7'-4"		
2.4	109.64	-14.99	do	z 128	0.873	do		
2.5	119.66	-16.36	do	z 128	0.953	do		
2.6	119.66	-16.36	do	z 128	0.953	do		
2.7	109.64	-14.99	do	z 128	0.873	do		
2.8	89.59	-12.25	do	z 128	0.748	7'-4"		
2.9	59.52	-8.14	do	z 87	0.611	5'-0 1/4"		
2.10	0.00	0.00	LL 3.5 X .313	z 151	0.406	8'-9 7/8"		
End Diagonal								
3.1	54.98	-8.07	x LL 2.5 X .230	zz118	0.896	9'-8 5/8"	.230 - 8 5/8"	
3.2	58.98	-8.07	x LL 2.5 X .230	zz118	0.896	9'-8 5/8"	.230 - 8 5/8"	
Diagonal Towards End								
4.1	22.52	-3.08	x LL 1.5 X .156	zz103	0.846	5'-2 1/4"	.156 - 4 7/8"	
4.2	15.59	-2.13	d U 1 3/8 x 0.157	yy113	0.895	do	.158 - 3 3/8"	
4.3	8.66	-1.18	U 1 x 1 x 0.118	yy161	0.978	do	.118 - 2 1/2"	
4.4	8.54	-0.24	do	yy161	0.965	do	do	
4.5	8.54	-0.24	do	yy161	0.965	do	do	
4.6	8.66	-1.18	U 1 x 1 x 0.118	yy161	0.978	do	.118 - 2 1/2"	
4.7	15.59	-2.13	d U 1 3/8 x 0.157	yy113	0.895	do	.158 - 3 3/8"	
4.8	22.52	-3.08	x LL 1.5 X .156	zz103	0.846	5'-2 1/4"	.156 - 4 7/8"	
Diagonal Towards Center								
5.1	2.64	-19.30	x LLV 1.75 x .143	zz 55	0.954	3'-10 7/8"	.143 - 4 5/8"	
5.2	2.61	-19.05	x LL 2 X .142	zz 77	0.949	5'-2 1/4"	.142 - 4 1/2"	
5.3	1.66	-12.12	x LL 1.5 X .156	zz103	0.980	do	.156 - 2 5/8"	
5.4	0.71	-8.54	x do	zz103	0.690	do	.156 - 1 7/8"	
5.5	0.71	-8.54	x do	zz103	0.690	do	.156 - 1 7/8"	
5.6	1.66	-12.12	x LL 1.5 X .156	zz103	0.980	do	.156 - 2 5/8"	
5.7	2.61	-19.05	x LL 2 X .142	zz 77	0.949	5'-2 1/4"	.142 - 4 1/2"	

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.	x	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
				x = tied at mid-length LLV 1.75 x .143				Weld-Ea.Side .143 - 4 5/8"	
5.8	2.64	-19.30	x		zz 65	0.954	3'-10 7/8"		
Secondary Web Member									
7.1	0.57	-4.45	d	U 1 3/8 x 0.118	z 119	0.806	4'-5 1/4"	.118 - 1 1/2"	
7.2	0.33	-2.80		U 1 x 1 x 0.090	z 147	1.001	3'-8"	.091 - 1 1/2"	
7.3	0.33	-2.93		U 1 x 1 x 0.118	yy111	0.815	do	.118 - 1 1/2"	
7.4	0.33	-3.00		do	yy111	0.837	do	do	
7.5	0.33	-3.03		do	yy111	0.843	do	do	
7.6	0.33	-3.00		do	yy111	0.835	do	do	
7.7	0.33	-2.92		U 1 x 1 x 0.118	yy111	0.813	do	.118 - 1 1/2"	
7.8	0.33	-2.78		U 1 x 1 x 0.090	z 147	0.996	3'-8"	.091 - 1 1/2"	
7.9	0.57	-4.43	d	U 1 3/8 x 0.118	z 119	0.802	4'-5 1/4"	.118 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	26'-2 3/8" ==>	3 Row(s) Minimum	Laterals supports Deck (36")
@ Bottom Chord:	36'-8 5/8" ==>	5 Row(s) Minimum	Acc. to the code

POSITION

	@ Top Chord	@ Bottom Chord
XB	18'-1 1/8" (18'-0 1/8")	9'-2" (9'-1 1/2")
XB	36'-2 1/4" (36'-0 3/8")	XB 18'-1 1/8" (18'-0 1/8")
XB	54'-3 3/8" (54'-0 1/2")	XB 36'-2 1/4" (36'-0 3/8")
		XB 54'-3 3/8" (54'-0 1/2")
		63'-2 1/2" (62'-11 1/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2475 (377.96) / 2710 (413.32)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C3 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = 81 \frac{1}{8}$ 1 1/8"
12


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 652.02 lb/ft

44LH15

LIVE LOAD ...: 382.29 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 2.40 in (L/ 360)
Calculated deflection under service live load = 2.27 in (L/ 379)
Joist inertia = 4017.73 in⁴
Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 42.00 in)

Left Reaction = 23.60/ -4.00 kips Right Reaction = 23.60/ -4.00 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

1.1	16.49	-57.07	x	LL 3.5 X .375	xx 73	0.827	6'-8"
1.2	16.11	-54.32		do	z 68	0.827	3'-10 1/2"
1.3	19.28	-77.43		do	z 48	0.673	3'-8"
1.4	19.24	-77.19		do	z 48	0.806	do
1.5	22.64	-102.00		do	z 48	0.862	do
1.6	22.61	-101.77		do	z 48	0.908	do
1.7	24.63	-116.56		do	z 48	0.980	do
1.8	24.60	-116.33		do	z 48	0.978	do
1.9	25.25	-121.10	x	do	zz 32	0.939	do
1.10	25.22	-120.86	x	do	zz 32	0.939	do
1.11	24.50	-115.62		do	z 48	0.972	do
1.12	24.47	-115.39		do	z 48	0.971	do
1.13	22.38	-100.13		do	z 48	0.900	do
1.14	22.35	-99.89		do	z 48	0.844	do
1.15	18.89	-74.61		do	z 48	0.792	do
1.16	18.86	-74.38		do	z 48	0.648	3'-8"
1.17	15.63	-50.79		do	z 68	0.799	3'-10 1/2"
1.18	15.92	-52.87	x	LL 3.5 X .375	xx 73	0.799	6'-8"

Bottom Chord

2.1	0.00	0.00		LL 3.5 X .313	z 163	0.407	9'-6 1/8"
2.2	59.62	-8.16		do	z 88	0.612	5'-0 1/2"
2.3	89.68	-12.27		do	z 128	0.749	7'-4"
2.4	109.71	-15.01		do	z 128	0.874	do
2.5	119.73	-16.38		do	z 128	0.953	do
2.6	119.73	-16.38		do	z 128	0.953	do
2.7	109.71	-15.01		do	z 128	0.874	do
2.8	89.68	-12.27		do	z 128	0.749	7'-4"
2.9	59.62	-8.16		do	z 88	0.612	5'-0 1/2"
2.10	0.00	0.00		LL 3.5 X .313	z 151	0.407	8'-9 7/8"

End Diagonal

3.1	58.98	-8.07	x	LL 2.5 X .230	zz118	0.896	9'-8 5/8"	.230 - 8 5/8"
3.2	58.98	-8.07	x	LL 2.5 X .230	zz118	0.896	9'-8 5/8"	.230 - 8 5/8"

Diagonal Towards End

4.1	22.50	-3.08	x	LL 1.5 X .156	zz103	0.845	5'-2 1/4"	.156 - 4 7/8"
4.2	15.58	-2.13	d	U 1 3/8 x 0.157	yy113	0.895	do	.158 - 3 3/8"
4.3	8.66	-1.18		U 1 x 1 x 0.118	yy161	0.977	do	.118 - 2 1/2"
4.4	8.54	-0.24		do	yy161	0.965	do	do
4.5	8.54	-0.24		do	yy161	0.965	do	do
4.6	8.66	-1.18		U 1 x 1 x 0.118	yy161	0.977	do	.118 - 2 1/2"
4.7	15.58	-2.13	d	U 1 3/8 x 0.157	yy113	0.895	do	.158 - 3 3/8"
4.8	22.50	-3.08	x	LL 1.5 X .156	zz103	0.845	5'-2 1/4"	.156 - 4 7/8"

Diagonal Towards Center

5.1	2.65	-19.33	x	LLV 1.75 x .143	zz 65	0.957	3'-11"	.143 - 4 5/8"
5.2	2.61	-19.04	x	LL 2 X .142	zz 77	0.949	5'-2 1/4"	.142 - 4 1/2"
5.3	1.66	-12.12	x	LL 1.5 X .156	zz103	0.979	do	.156 - 2 5/8"
5.4	0.71	-8.54	x	do	zz103	0.690	do	.156 - 1 7/8"
5.5	0.71	-8.54	x	do	zz103	0.690	do	.156 - 1 7/8"
5.6	1.66	-12.12	x	LL 1.5 X .156	zz103	0.979	do	.156 - 2 5/8"
5.7	2.61	-19.04	x	LL 2 X .142	zz 77	0.949	5'-2 1/4"	.142 - 4 1/2"

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.		REQUIRED MATERIAL		Slend.	Util.	Length	REQUIRED WELD		Remarks
				x = tied at mid-length					Weld-Ea.Side		
5.8	2.65	-19.33	x	LLV 1.75 x .143		zz 65	0.957	3'-11"	.143	- 4 5/8"	
Secondary Web Member											
7.1	0.57	-4.46	d	U 1 3/8 x 0.118		z 119	0.807	4'-5 1/4"	.118	- 1 1/2"	
7.2	0.33	-2.80		U 1 x 1 x 0.090		z 147	1.001	3'-8"	.091	- 1 1/2"	
7.3	0.33	-2.93		U 1 x 1 x 0.118		yy111	0.815	do	.118	- 1 1/2"	
7.4	0.33	-3.00		do		yy111	0.836	do	do		
7.5	0.33	-3.03		do		yy111	0.843	do	do		
7.6	0.33	-3.00		do		yy111	0.835	do	do		
7.7	0.33	-2.92		U 1 x 1 x 0.118		yy111	0.812	do	.118	- 1 1/2"	
7.8	0.33	-2.78		U 1 x 1 x 0.090		z 147	0.996	3'-8"	.091	- 1 1/2"	
7.9	0.57	-4.44	d	U 1 3/8 x 0.118		z 119	.803	4'-5 1/4"	.118	- 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	26'-2 3/8" ==>	3 Row(s) Minimum	Laterals supports Deck (36")
@ Bottom Chord:	36'-8 5/8" ==>	5 Row(s) Minimum	Acc. to the code

POSITION

	@ Top Chord	@ Bottom Chord
XB	18'-1 1/4" (18'-0 1/4")	9'-2" (9'-1 1/2")
XB	36'-2 1/2" (36'-0 5/8")	XB 18'-1 1/4" (18'-0 1/4")
XB	54'-3 3/4" (54'-0 7/8")	XB 36'-2 1/2" (36'-0 5/8")
		XB 54'-3 3/4" (54'-0 7/8")
		63'-3" (62'-11 3/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2477 (378.17) / 2712 (413.53)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C4 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = 81 \frac{1}{8}$ 1 1/8"
12


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 542.00 lb/ft

44LHSP542/291

LIVE LOAD ...: 291.00 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(Q) Wind or Seism (case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 2.40 in (L/ 360)
Calculated deflection under service live load = 2.01 in (L/ 429)
Joist inertia = 3425.01 in⁴
Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

($F_y = 50$ Ksi U/N)

(Eff. depth = 42.14 in)

Left Reaction = 19.45/ -4.00 kips

Right Reaction = 19.45/ -4.00 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
----	---------	----------	------------------------	--------	-------	--------	--------------	---------

Top Chord

1.1	16.43	-46.86	x	LL 3.5 X .313	xx 72	0.805	6'-8"	
1.2	16.06	-44.61		do	z 67	0.805	3'-10 1/2"	
1.3	19.21	-63.58		do	z 48	0.661	3'-8"	
1.4	19.18	-63.39		do	z 48	0.785	do	
1.5	22.56	-83.76		do	z 48	0.847	do	
1.6	22.53	-83.57		do	z 48	0.885	do	
1.7	24.54	-95.71		do	z 48	0.964	do	
1.8	24.51	-95.52		do	z 48	0.962	do	
1.9	25.16	-99.44		do	z 48	1.000	do	
1.10	25.13	-99.25		do	z 48	0.998	do	
1.11	24.42	-94.94		do	z 48	0.956	do	
1.12	24.38	-94.75		do	z 48	0.954	do	
1.13	22.30	-82.22		do	z 48	0.877	do	
1.14	22.27	-82.02		do	z 48	0.830	do	
1.15	18.82	-61.27		do	z 48	0.771	do	
1.16	18.79	-61.07		do	z 48	0.636	3'-8"	
1.17	15.58	-41.70		do	z 67	0.777	3'-10 1/2"	
1.18	15.86	-43.41	x	LL 3.5 X .313	xx 72	0.777	6'-8"	

Bottom Chord

2.1	0.00	0.00		LL 3 X .313	z 190	0.393	9'-6 1/8"	
2.2	48.96	-8.13		do	z 103	0.591	5'-0 1/2"	
2.3	73.64	-12.23		do	z 149	0.723	7'-4"	
2.4	90.09	-14.96		do	z 149	0.950	do	
2.5	98.31	-16.33		do	z 149	0.967	do	
2.6	98.31	-16.33		do	z 149	0.967	do	
2.7	90.09	-14.96		do	z 149	0.950	do	
2.8	73.64	-12.23		do	z 149	0.723	7'-4"	
2.9	48.96	-8.13		do	z 103	0.591	5'-0 1/2"	
2.10	0.00	0.00		LL 3 X .313	z 176	0.393	8'-9 7/8"	

End Diagonal

3.1	48.45	-8.05	x	LL 2 X .216	zz148	0.988	9'-8 5/8"	.216 - 7 5/8"
3.2	48.45	-8.05	x	LL 2 X .216	zz148	0.988	9'-8 5/8"	.216 - 7 5/8"

Diagonal Towards End

4.1	18.51	-3.07	d	U 1 3/8 X 0.176	yy115	0.959	5'-2 1/4"	.176 - 3 1/2"
4.2	12.81	-2.13	d	U 1 3/8 X 0.118	z 141	0.975	do	.118 - 3 5/8"
4.3	7.12	-1.18		U 1 X 1 X 0.118	yy161	0.804	do	.118 - 2"
4.4	7.03	-0.24		do	yy161	0.793	do	do
4.5	7.03	-0.24		do	yy161	0.793	do	do
4.6	7.12	-1.18		U 1 X 1 X 0.118	yy161	0.804	do	.118 - 2"
4.7	12.81	-2.13	d	U 1 3/8 X 0.118	z 141	0.975	do	.118 - 3 5/8"
4.8	18.51	-3.07	d	U 1 3/8 X 0.176	yy115	0.959	5'-2 1/4"	.176 - 3 1/2"

Diagonal Towards Center

5.1	2.64	-15.92	x	LL 1.5 X .156	zz 77	0.914	3'-11"	.156 - 3 1/2"
5.2	2.60	-15.66	x	LLV 1.75 X .143	zz 88	0.962	5'-2 1/4"	.143 - 3 3/4"
5.3	1.65	-9.97	x	LL 1.5 X .156	zz103	0.808	do	.156 - 2 1/8"
5.4	0.71	-7.03	d	U 1 3/8 X 0.176	yy115	0.973	do	.176 - 1 1/2"
5.5	0.71	-7.03	d	U 1 3/8 X 0.176	yy115	0.973	do	.176 - 1 1/2"
5.6	1.65	-9.97	x	LL 1.5 X .156	zz103	0.808	do	.156 - 2 1/8"
5.7	2.60	-15.66	x	LLV 1.75 X .143	zz 88	0.962	5'-2 1/4"	.143 - 3 3/4"

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.	x	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
				x = tied at mid-length				Weid-Ea.Side	
5.8	2.64	-15.92	x	LL 1.5 X .156	zz 77	0.914	3'-11"	.156 - 3 1/2"	
Secondary Web Member									
7.1	0.57	-3.67	d	U 1 3/8 x 0.118	z 120	0.666	4'-5 1/4"	.118 - 1 1/2"	
7.2	0.33	-2.30		U 1 x 1 x 0.090	z 147	0.831	3'-8"	.091 - 1 1/2"	
7.3	0.33	-2.41		do	z 147	0.869	do	do	
7.4	0.33	-2.47		do	z 147	0.892	do	do	
7.5	0.33	-2.49		do	z 147	0.899	do	do	
7.6	0.33	-2.47		do	z 147	0.890	do	do	
7.7	0.33	-2.40		do	z 147	0.866	do	do	
7.8	0.33	-2.29		U 1 x 1 x 0.090	z 147	0.826	3'-8"	.091 - 1 1/2"	
7.9	0.57	-3.65	d	U 1 3/8 x 0.118	z 120	0.663	4'-5 1/4"	.118 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	26'-0 1/8" ==>	2 Row(s) Minimum	Laterals supports
@ Bottom Chord:	32'-9 3/4" ==>	4 Row(s) Minimum	Deck (36")
			Acc. to the code

POSITION

@ Top Chord		@ Bottom Chord
XB 24'-1 5/8" (24'-0 3/8")		9'-2" (9'-1 1/2")
48'-3 3/9" (48'-0 3/4")	XB	24'-1 5/8" (24'-0 3/8")
		48'-3 3/8" (48'-0 3/4")
		63'-3" (62'-11 3/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,	BL = 2 angles welded in box,	BR = Round bar
-U = 1 U profile,	UU = 2 U profiles one inside the other,	-CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2082 (317.96) / 2285 (346.92)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C5 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = \frac{81 \frac{1}{8}}{12}$ 1 1/8"


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 562.00 lb/ft

44LHSP562/311

LIVE LOAD ...: 311.00 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

	---L---	---R---	<<< Top Chord >>>	< Bottom Chord >	
			---L---	---R---	
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00
(Q) Wind or Seism (case 2)...	0.00	0.00	11.00	-11.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 2.40 in (L/ 360)
Calculated deflection under service live load = 2.15 in (L/ 401)
Joist inertia = 3425.01 in⁴
Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THAT SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 42.14 in)

Left Reaction = 20.16/ -4.00 kips Right Reaction = 20.16/ -4.00 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

1.1	16.43	-48.59	x	LL 3.5 X .313	xx 72	0.834	6'-8"
1.2	16.06	-46.25		do	z 67	0.834	3'-10 1/2"
1.3	19.21	-65.93		do	z 48	0.685	3'-8"
1.4	19.18	-65.73		do	z 48	0.814	do
1.5	22.56	-86.85		do	z 48	0.879	do
1.6	22.53	-86.65		do	z 48	0.918	do
1.7	24.54	-99.24		do	z 48	0.999	do
1.8	24.51	-99.04		do	z 48	0.997	do
1.9	25.16	-103.11	x	do	zz 32	0.955	do
1.10	25.13	-102.91	x	do	zz 32	0.953	do
1.11	24.42	-98.44		do	z 48	0.991	do
1.12	24.38	-98.24		do	z 48	0.990	do
1.13	22.30	-85.25		do	z 48	0.910	do
1.14	22.27	-85.05		do	z 48	0.861	do
1.15	18.82	-63.53		do	z 48	0.800	do
1.16	18.79	-63.33		do	z 48	0.660	3'-8"
1.17	15.58	-43.24		do	z 67	0.806	3'-10 1/2"
1.18	15.86	-45.02	x	LL 3.5 X .313	xx 72	0.806	6'-8"

Bottom Chord

2.1	0.00	0.00		LL 3 X .313	z 190	0.407	9'-6 1/8"
2.2	50.77	-8.13		do	z 103	0.613	5'-0 1/2"
2.3	76.35	-12.23		do	z 149	0.750	7'-4"
2.4	93.41	-14.96		do	z 149	0.950	do
2.5	101.94	-16.33		do	z 149	0.967	do
2.6	101.94	-16.33		do	z 149	0.967	do
2.7	93.41	-14.96		do	z 149	0.950	do
2.8	76.35	-12.23		do	z 149	0.750	7'-4"
2.9	50.77	-8.13		do	z 103	0.613	5'-0 1/2"
2.10	0.00	0.00		LL 3 X .313	z 176	0.407	8'-9 7/8"

End Diagonal

3.1	50.24	-8.05	x	LL 2.5 X .188	zz117	0.926	9'-8 5/8"	.188 - 9"
3.2	50.24	-8.05	x	LL 2.5 X .188	zz117	0.926	9'-8 5/8"	.188 - 9"

Diagonal Towards End

4.1	19.19	-3.07	d	U 1 3/8 X 0.176	yy115	0.994	5'-2 1/4"	.176 - 3 3/4"
4.2	13.29	-2.13	d	U 1 3/8 X 0.157	yy113	0.763	do	.158 - 2 7/8"
4.3	7.38	-1.18		U 1 x 1 x 0.118	yy161	0.833	do	.118 - 2 1/8"
4.4	7.29	-0.24		do	yy161	0.823	do	do
4.5	7.29	-0.24		do	yy161	0.823	do	do
4.6	7.38	-1.18		U 1 x 1 x 0.118	yy161	0.833	do	.118 - 2 1/8"
4.7	13.29	-2.13	d	U 1 3/8 X 0.157	yy113	0.763	do	.158 - 2 7/8"
4.8	19.19	-3.07	d	U 1 3/8 X 0.176	yy115	0.994	5'-2 1/4"	.176 - 3 3/4"

Diagonal Towards Center

5.1	2.64	-16.51	x	LL 1.5 X .156	zz 77	0.947	3'-11"	.156 - 3 5/8"
5.2	2.60	-16.24	x	LLV 1.75 x .143	zz 88	0.998	5'-2 1/4"	.143 - 3 7/8"
5.3	1.65	-10.33	x	LL 1.5 X .156	zz103	0.837	do	.156 - 2 1/4"
5.4	0.71	-7.29	d	U 1 3/8 X 0.176	yy115	1.009	do	.176 - 1 1/2"
5.5	0.71	-7.29	d	U 1 3/8 X 0.176	yy115	1.009	do	.176 - 1 1/2"
5.6	1.65	-10.33	x	LL 1.5 X .156	zz103	0.837	do	.156 - 2 1/4"
5.7	2.60	-16.24	x	LLV 1.75 x .143	zz 88	0.998	5'-2 1/4"	.143 - 3 7/8"

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.	x	REQUIRED MATERIAL	Slend.	Util.	Length	REQUIRED WELD	Remarks
				x = tied at mid-length				Weld-Ea.Side	
5.8	2.64	-16.51	x	LL 1.5 X .156	zz 77	0.947	3'-11"	.156 - 3 5/8"	
Secondary Web Member									
7.1	0.57	-3.81	d	U 1 3/8 x 0.118	z 120	0.690	4'-5 1/4"	.118 - 1 1/2"	
7.2	0.33	-2.39		U 1 x 1 x 0.090	z 147	0.861	3'-8"	.091 - 1 1/2"	
7.3	0.33	-2.50		do	z 147	0.901	do	do	
7.4	0.33	-2.57		do	z 147	0.924	do	do	
7.5	0.33	-2.59		do	z 147	0.932	do	do	
7.6	0.33	-2.56		do	z 147	0.923	do	do	
7.7	0.33	-2.49		do	z 147	0.898	do	do	
7.8	0.33	-2.38		U 1 x 1 x 0.090	z 147	0.857	3'-8"	.091 - 1 1/2"	
7.9	0.57	-3.79	d	U 1 3/8 x 0.118	z 120	0.687	4'-5 1/4"	.118 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	26'-0 1/8" ==>	2 Row(s) Minimum	Laterals supports
@ Bottom Chord:	32'-9 3/4" ==>	4 Row(s) Minimum	Deck (36")
			Acc. to the code

POSITION

@ Top Chord		@ Bottom Chord
XB 24'-1 5/8" (24'-0 3/8")		9'-2" (9'-1 1/2")
48'-3 3/8" (48'-0 3/4")	XB	24'-1 5/8" (24'-0 3/8")
		48'-3 3/8" (48'-0 3/4")
		63'-3" (62'-11 3/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2099 (322.26) / 2302 (351.22)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C6 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = 81 \frac{1}{8}$
12 1 1/8"


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 652.02 lb/ft

44LH15

LIVE LOAD ...: 382.29 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	0.58	0.58	0.00	21'-0"*	21'-0"	0	1	90	0
2	1	Near	0.58	0.58	0.00	29'-0"*	8'-0"	0	1	90	0
3	1	Near	0.58	0.58	0.00	37'-0"*	8'-0"	0	1	90	0
4	1	Near	0.58	0.58	0.00	45'-0"*	8'-0"	0	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left.: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 2.40 in (L/ 360)
 Calculated deflection under service live load = 2.40 in (L/ 360)
 Joist inertia = 4211.80 in⁴
 Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)
 (Fy = 50 Ksi U/N)

(Eff. depth = 41.99 in)

Left Reaction = 24.86/ -4.00 kips Right Reaction = 24.66/ -4.00 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

1.1	16.49	-60.43	x	LL 3.5 X .375	xx 73	0.849	6'-8"
1.2	16.12	-57.68		do	z 68	0.849	3'-10 1/2"
1.3	19.28	-82.60		do	z 48	0.715	3'-8"
1.4	19.25	-82.37		do	z 48	0.858	do
1.5	22.64	-109.79		do	z 48	0.926	do
1.6	22.61	-109.44		do	z 48	0.969	do
1.7	24.64	-125.65	x	do	zz 32	0.970	do
1.8	24.60	-125.41	x	do	zz 32	1.001	do
1.9	25.26	-130.39	x	do	zz 32	1.004	do
1.10	25.23	-130.22	x	do	zz 32	1.003	do
1.11	24.51	-124.00	x	do	zz 32	1.000	do
1.12	24.48	-123.88	x	do	zz 32	0.959	do
1.13	22.39	-106.50		do	z 48	0.957	do
1.14	22.36	-106.27		do	z 48	0.897	do
1.15	18.90	-78.77		do	z 48	0.834	do
1.16	18.86	-78.53		do	z 48	0.682	3'-8"
1.17	15.63	-53.41		do	z 68	0.816	3'-10 1/2"
1.18	15.92	-55.50	x	LL 3.5 X .375	xx 73	0.816	6'-8"

Bottom Chord

2.1	0.00	0.00		LL 3.5 X .344	z 163	0.395	9'-6 1/8"
2.2	63.36	-8.16		do	z 88	0.599	5'-0 1/2"
2.3	96.04	-12.27		do	z 128	0.736	7'-4"
2.4	118.03	-15.02		do	z 128	0.859	do
2.5	128.90	-16.39		do	z 128	0.938	do
2.6	128.66	-16.39		do	z 128	0.937	do
2.7	117.30	-15.02		do	z 128	0.854	do
2.8	95.05	-12.27		do	z 128	0.732	7'-4"
2.9	62.77	-8.16		do	z 88	0.593	5'-0 1/2"
2.10	0.00	0.00		LL 3.5 X .344	z 151	.392	8'-9 7/8"

End Diagonal

3.1	62.45	-8.07	x	LL 2.5 X .230	zz118	0.949	9'-8 5/8"	.230 - 9 1/8"
-----	-------	-------	---	---------------	-------	-------	-----------	---------------

3.2 61.91 -8.07 x LL 2.5 X .230 zz118 0.940 9'-8 5/8" .230 - 9 1/8"

Diagonal Towards End

4.1	24.32	-3.08	x	LL 1.5 X .156	zz103	0.914	5'-2 1/4"	.156 - 5 1/4"
4.2	17.40	-2.13	d	U 1 3/8 x 0.157	yy113	0.999	do	.158 - 3 3/4"
4.3	9.63	-1.18	d	U 1 3/8 x 0.118	z 141	0.733	do	.118 - 2 3/4"
4.4	9.00	-0.24	d	do	z 141	0.685	do	.118 - 2 1/2"
4.5	9.00	-0.24	d	do	z 141	0.685	do	.118 - 2 1/2"
4.6	10.17	-1.18	d	U 1 3/8 x 0.118	z 141	0.774	do	.118 - 2 7/8"
4.7	17.11	-2.13	d	U 1 3/8 x 0.157	yy113	0.983	do	.158 - 3 5/8"
4.8	24.04	-3.08	x	LL 1.5 X .156	zz103	0.903	5'-2 1/4"	.156 - 5 1/4"

FORCES IN MEMBERS (Cont.) [kips]

No	Tension	Compres.		REQUIRED MATERIAL x = tied at mid-length	Slend.	Util.	Length	REQUIRED WELD Weld-Er.Side	Remarks
Diagonal Towards Center									
5.1	2.65	-20.68	x	LL 1.75 X .155	zz 65	0.927	3'-11"	.155 - 4 1/2"	
5.2	2.61	-20.86	x	LL 2 X .163	zz 77	0.876	5'-2 1/4"	.163 - 4 3/8"	
5.3	1.66	-13.10	x	LLV 1.75 x .143	zz 88	0.803	do	.143 - 3 1/8"	
5.4	0.71	-9.00	x	LL 1.5 X .156	zz103	0.727	do	.156 - 2"	
5.5	0.71	-9.00	x	LL 1.5 X .156	zz103	0.727	do	.156 - 2"	
5.6	1.66	-13.65	x	LLV 1.75 x .143	zz 88	0.837	do	.143 - 3 1/4"	
5.7	2.61	-20.57	x	LL 2 X .163	zz 77	0.864	5'-2 1/4"	.163 - 4 1/4"	
5.8	2.65	-20.47	x	LL 1.75 X .155	zz 65	0.917	3'-11"	.155 - 4 1/2"	

Secondary Web Member

7.1	0.57	-4.48	d	U 1 3/8 x 0.118	z 119	0.810	4'-5 1/4"	.118 - 1 1/2"
7.2	0.33	-2.82		U 1 x 1 x 0.090	z 147	1.010	3'-8"	.091 - 1 1/2"
7.3	0.33	-2.96		U 1 x 1 x 0.118	yy111	0.823	do	.118 - 1 1/2"
7.4	0.33	-3.05		do	yy111	0.849	do	do
7.5	0.33	-3.08		do	yy111	0.858	do	do
7.6	0.33	-3.05		do	yy111	0.850	do	do
7.7	0.33	-2.95		U 1 x 1 x 0.118	yy111	0.821	do	.118 - 1 1/2"
7.8	0.33	-2.80		U 1 x 1 x 0.090	z 147	1.003	3'-8"	.091 - 1 1/2"
7.9	0.57	-4.45	d	U 1 3/8 x 0.118	z 119	0.805	4'-5 1/4"	.118 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging
 @ Top Chord: 26'-2 3/8" ==> 3 Row(s) Minimum
 @ Bottom Chord: 36'-11 5/8" ==> 5 Row(s) Minimum
 Laterals supports Deck (36")
 Acc. to the code

POSITION

	@ Top Chord	@ Bottom Chord
XB	18'-1 1/4" (18'-0 1/4")	9'-2" (9'-1 1/2")
XB	36'-2 1/2" (36'-0 5/8")	XB 18'-1 1/4" (18'-0 1/4")
XB	54'-3 3/4" (54'-0 7/8")	XB 36'-2 1/2" (36'-0 5/8")
		XB 54'-3 3/4" (54'-0 7/8")
		63'-3" (62'-11 3/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
 -U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle
 Value of the forces reduced by 25% when there are some wind loads

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transfered by an additional member

2 = anywhere within a panel

4 = anywhere along the joist

6 = within a panel with no reinforcement and lateral support

1 = within a panel with no reinforcement

3 = at any panel point along the joist

5 = transfered by an additional member and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2565 (388.69) / 2819 (425.94)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: C7 (W-N LONG SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = \frac{81 \frac{1}{8}}{12}$ 1 1/8"


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 542.00 lb/ft

44LHSP542/291

LIVE LOAD ...: 291.00 lb/ft

CONCENTRATED LOADS

No	Sp	Side	Total load [kips]	Live load [kips]	Net uplift [kips]	Position [ft]	Spacing [ft]	Cat.	Chord 1/2	Incl. [deg]	Cmp
1	1	Near	0.15	0.15	0.00	21'-0"	21'-0"	1	1	90	0
2	1	Near	0.15	0.15	0.00	29'-0"	8'-0"	1	1	90	0
3	1	Near	0.15	0.15	0.00	37'-0"	8'-0"	1	1	90	0
4	1	Near	0.15	0.15	0.00	45'-0"	8'-0"	1	1	90	0

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>> < Bottom Chord >

	--L--	--R--	--L--	--R--	--L--	--R--
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes
Bearing Depth... [in]: at left: 5"

Imposed Rows of Bridging Y/N.: No
at right: 5"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 2.40 in (L/ 360)
 Calculated deflection under service live load = 2.09 in (L/ 412)
 Joist inertia = 3425.01 in⁴
 Required camber = 2.18 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 42.14 in)

Left Reaction = 19.77/ -4.00 kips Right Reaction = 19.72/ -4.00 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	16.43	-47.72	x	LL 3.5 X .313	xx 72 0.811	6'-8"		
1.2	16.06	-45.47		do	z 67 0.811	3'-10 1/2"		
1.3	19.21	-64.91		do	z 48 0.674	3'-8"		
1.4	19.18	-64.71		do	z 48 0.803	do		
1.5	22.56	-85.74		do	z 48 0.868	do		
1.6	22.53	-85.54		do	z 48 0.901	do		
1.7	24.54	-98.05		do	z 48 0.986	do		
1.8	24.51	-97.84		do	z 48 0.986	do		
1.9	25.16	-101.82	x	do	zz 32 0.943	do		
1.10	25.13	-101.62	x	do	zz 32 0.944	do		
1.11	24.42	-97.09		do	z 48 0.975	do		
1.12	24.38	-96.89		do	z 48 0.983	do		
1.13	22.30	-83.85		do	z 48 0.903	do		
1.14	22.27	-83.66		do	z 48 0.847	do		
1.15	18.82	-62.33		do	z 48 0.785	do		
1.16	18.79	-62.14		do	z 48 0.647	3'-8"		
1.17	15.58	-42.38		do	z 67 0.782	3'-10 1/2"		
1.18	15.86	-44.09	x	LL 3.5 X .313	xx 72 0.782	6'-8"		
Bottom Chord								
2.1	0.00	0.00		LL 3 X .313	z 190 0.401	9'-6 1/8"		
2.2	49.92	-8.13		do	z 103 0.604	5'-0 1/2"		
2.3	75.27	-12.23		do	z 149 0.740	7'-4"		
2.4	92.22	-14.96		do	z 149 0.950	do		
2.5	100.67	-16.33		do	z 149 0.967	do		
2.6	100.61	-16.33		do	z 149 0.967	do		
2.7	92.04	-14.96		do	z 149 0.950	do		
2.8	75.01	-12.23		do	z 149 0.739	7'-4"		
2.9	49.77	-8.13		do	z 103 0.602	5'-0 1/2"		
2.10	0.00	0.00		LL 3 X .313	z 176 0.303	8'-9 7/8"		
End Diagonal								
3.1	49.34	-8.05	x	LL 2 X .216	zz148 1.006	9'-8 5/8"	.216 - 7 3/4"	

6840 N CUTTER CIRCLE

DFS-01

CO-00-160942

3.

3.2 49.20 -8.05 x LL 2 X .216 zz148 1.003 9'-8 5/8" .216 - 7 3/4"

Diagonal Towards End

4.1	18.98	-3.07	d	U 1 3/8 X 0.176	yy115	0.983	5'-2 1/4"	.176 - 3 5/8"
4.2	13.26	-2.13	d	U 1 3/8 x 0.118	z 141	1.008	do	.118 - 3 3/4"
4.3	7.37	-1.18		U 1 x 1 x 0.118	yy161	0.832	do	.118 - 2 1/8"
4.4	7.15	-0.24		do	yy161	0.807	do	.118 - 2"
4.5	7.15	-0.24		do	yy161	0.807	do	.118 - 2"
4.6	7.42	-1.18		U 1 x 1 x 0.118	yy161	0.837	do	.118 - 2 1/8"
4.7	13.21	-2.13	d	U 1 3/8 x 0.118	z 141	1.005	do	.118 - 3 3/4"
4.8	18.90	-3.07	d	U 1 3/8 X 0.176	yy115	0.979	5'-2 1/4"	.176 - 3 5/8"

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.		x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Diagonal Towards Center									
5.1	2.64	-16.27	x	LL 1.5 X .156	zz 77	0.934	3'-11"	.156 - 3 1/2"	
5.2	2.60	-16.13	x	LLV 1.75 x .143	zz 88	0.991	5'-2 1/4"	.143 - 3 7/8"	
5.3	1.65	-10.22	x	LL 1.5 X .156	zz103	0.828	do	.156 - 2 1/4"	
5.4	0.71	-7.15	d	U 1 3/8 X 0.176	yy115	0.989	do	.176 - 1 1/2"	
5.5	0.71	-7.15	d	U 1 3/8 X 0.176	yy115	0.989	do	.176 - 1 1/2"	
5.6	1.65	-10.36	x	LL 1.5 X .156	zz103	0.840	do	.156 - 2 1/4"	
5.7	2.60	-16.06	x	LLV 1.75 x .143	zz 88	0.986	5'-2 1/4"	.143 - 3 7/8"	
5.8	2.64	-16.22	x	LL 1.5 X .156	zz 77	0.931	3'-11"	.156 - 3 1/2"	

Secondary Web Member

7.1	0.57	-3.68	d	U 1 3/8 x 0.118	z 120	0.667	4'-5 1/4"	.118 - 1 1/2"
7.2	0.33	-2.31		U 1 x 1 x 0.090	z 147	0.833	3'-8"	.091 - 1 1/2"
7.3	0.33	-2.55		do	z 147	0.920	do	do
7.4	0.33	-2.63		do	z 147	0.946	do	do
7.5	0.33	-2.62		do	z 147	0.943	do	do
7.6	0.33	-2.56		do	z 147	0.924	do	do
7.7	0.33	-2.41		do	z 147	0.869	do	do
7.8	0.33	-2.30		U 1 x 1 x 0.090	z 147	0.828	3'-8"	.091 - 1 1/2"
7.9	0.57	-3.66	d	U 1 3/8 x 0.118	z 120	0.663	4'-5 1/4"	.118 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:	26'-0 1/8" ==>	2 Row(s) Minimum	Laterals supports Deck (36")
@ Bottom Chord:	32'-9 3/4" ==>	4 Row(s) Minimum	Acc. to the code

POSITION

	@ Top Chord	@ Bottom Chord
XB	24'-1 5/8" (24'-0 3/8")	9'-2" (9'-1 1/2")
	48'-3 3/8" (48'-0 3/4")	24'-1 5/8" (24'-0 3/8")
		48'-3 3/8" (48'-0 3/4")
		63'-3" (62'-11 3/4")

v3.6 12/08/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are scm wind loads

CONCENTRATED LOADS (* indicates that the conc. load is not directly on the panel point.)

Span: 1 = Main Joist, 2 = Left Extension, 3 = Right Extension

Side: Near Side, Far Side (if the side Far is not present, the side Near is not applicable)

Definition of the categories (Cat.) 0 @ 6:

0 = transferred by an additional member

2 = anywhere within a panel

4 = anywhere along the joist

6 = within a panel with no reinforcement and lateral support

1 = within a panel with no reinforcement

3 = at any panel point along the joist

5 = transferred by an additional member and lateral support

Chord: 1 = Top, 2 = Bottom

Inclination (Incl.): 90 = Vertical, 0 = Horizontal

Composite (Cmp): 0 = standard, 1 = non-composite

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

2082 (317.96) / 2285 (346.92)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J1 (W-N MID SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = \frac{35}{12} = 2.917$


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 439.61 lb/ft

30K10

LIVE LOAD ...: 317.63 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

	--L--	--R--	<<< Top Chord >>>	< Bottom Chord >	
			--L--	--R--	
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.26 in (L/ 376)
Joist inertia	=	545.35 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

($F_y = 50$ Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.71/ -2.38 kips Right Reaction = 8.71/ -2.38 kips

REQUIRED MATERIAL


REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
Top Chord								
1.1	11.54	-14.48	LL 2 X .188	z 85	0.836	2'-11 1/2"		
1.2	11.38	-13.68	do	z 90	0.842	2'-11 5/8"		
1.3	13.09	-22.08	do	z 61	0.758	2'-0"		
1.4	13.10	-22.14	do	z 61	0.686	do		
1.5	14.61	-29.52	do	z 61	0.913	do		
1.6	14.62	-29.58	do	z 61	0.915	do		
1.7	15.53	-34.04 x	do	xx 39	0.914	do		
1.8	15.54	-34.10 x	do	xx 39	0.916	do		
1.9	15.85	-35.63 x	do	xx 39	0.957	do		
1.10	15.86	-35.70 x	do	xx 39	0.958	do		
1.11	15.58	-34.30 x	do	xx 39	0.921	do		
1.12	15.59	-34.37 x	do	xx 39	0.923	do		
1.13	14.71	-30.05	do	z 61	0.930	do		
1.14	14.73	-30.12	do	z 61	0.932	do		
1.15	13.25	-22.88	do	z 61	0.708	do		
1.16	13.27	-22.95	do	z 61	0.778	2'-0"		
1.17	11.59	-14.71	do	z 90	0.868	2'-11 5/8"		
1.18	11.79	-15.71	LL 2 X .188	z 85	0.868	2'-11 1/2"		
Bottom Chord								
2.1	0.00	0.00	LL 2 X .156	z 131	0.423	4'-5 7/8"		
2.2	17.76	-3.62	do	z 99	0.632	3'-3 1/8"		
2.3	26.53	-5.40	do	z 121	0.771	4'-0"		
2.4	32.38	-6.59	do	z 121	0.900	do		
2.5	35.30	-7.19	do	z 121	0.981	do		
2.6	35.30	-7.19	do	z 121	0.981	do		
2.7	32.38	-6.59	do	z 121	0.900	do		
2.8	26.53	-5.40	do	z 121	0.771	4'-0"		
2.9	17.76	-3.62	do	z 99	0.632	3'-3 1/8"		
2.10	0.00	0.00	LL 2 X .156	z 142	0.423	4'-10 1/4"		
End Diagonal								
3.1	17.12	-3.49	SQUARE BAR 1" (50 ksi)	z 208	0.649	5'-1 3/4"	.250 - 2 3/8"	
3.2	17.12	-3.49	SQUARE BAR 1" (50 ksi)	z 209	0.652	5'-1 3/4"	.250 - 2 3/8"	
Diagonal Towards End								
4.1	7.43	-1.51	U 1 x 1 x 0.118	z 124	0.839	3'-2 3/8"	.118 - 2 1/8"	
4.2	5.14	-1.05	U 1 x 1 x 0.090	z 127	0.757	do	.091 - 1 7/8"	
4.3	2.86	-0.58	do	z 127	0.421	do	.091 - 1 1/2"	
4.4	2.83	-0.12	do	z 127	0.417	do	do	
4.5	2.83	-0.12	do	z 128	0.417	do	do	
4.6	2.86	-0.58	do	z 128	0.421	do	.091 - 1 1/2"	
4.7	5.14	-1.05	U 1 x 1 x 0.090	z 128	0.757	do	.091 - 1 7/8"	
4.8	7.43	-1.51	U 1 x 1 x 0.118	z 124	0.839	3'-2 3/8"	.118 - 2 1/8"	
Diagonal Towards Center								
5.1	1.56	-7.68 d	U 1 3/8 x 0.157	z 72	0.642	2'-9 5/8"	.158 - 1 5/8"	
5.2	1.28	-6.29 d	U 1 3/8 x 0.157	z 83	0.589	3'-2 3/8"	.158 - 1 1/2"	
5.3	0.81	-4.00 d	U 1 3/8 x 0.118	z 85	0.684	do	.118 - 1 1/2"	
5.4	0.35	-2.83	U 1 x 1 x 0.118	z 124	0.985	do	do	
5.5	0.35	-2.83	U 1 x 1 x 0.118	z 124	0.979	do	do	
5.6	0.81	-4.00 d	U 1 3/8 x 0.118	z 84	0.682	do	.118 - 1 1/2"	
5.7	1.28	-6.29 d	U 1 3/8 x 0.157	z 83	0.587	3'-2 3/8"	.158 - 1 1/2"	

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J2 (W-N MID SPAN, Symmetrical, Parallel, Free ends)

 $\Delta = -34 \frac{7}{8}$
12 - 0 7/8"


LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 440.52 lb/ft

30K10

LIVE LOAD ...: 319.13 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

	MOMENTS		AXIAL LOADS			
			<<< Top Chord >>>		< Bottom Chord >	
	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 1.31 in (L/ 360)
 Calculated deflection under service live load = 1.26 in (L/ 376)
 Joist inertia = 545.35 in⁴
 Required camber = 0.62 in

----- F O R C E S I N M E M B E R S [kips] -----

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.71/ -2.37 kips

Right Reaction = 8.71/ -2.37 kips

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
----	---------	----------	------------------------	--------	-------	--------	--------------	---------

Top Chord

1.1	11.54	-14.48	LL 2 X .188	z 85	0.830	2'-11 3/8"		
1.2	11.37	-13.68	do	z 90	0.837	2'-11 3/8"		
1.3	13.06	-21.97	do	z 61	0.753	2'-0"		
1.4	13.07	-22.04	do	z 61	0.684	do		
1.5	14.58	-29.43	do	z 61	0.910	do		
1.6	14.59	-29.49	do	z 61	0.912	do		
1.7	15.50	-33.95 x	do	xx 39	0.912	do		
1.8	15.51	-34.02 x	do	xx 39	0.913	do		
1.9	15.82	-35.55 x	do	xx 39	0.954	do		
1.10	15.83	-35.62 x	do	xx 39	0.956	do		
1.11	15.55	-34.22 x	do	xx 39	0.919	do		
1.12	15.56	-34.29 x	do	xx 39	0.921	do		
1.13	14.68	-29.96	do	z 61	0.927	do		
1.14	14.70	-30.03	do	z 61	0.929	do		
1.15	13.22	-22.78	do	z 61	0.705	do		
1.16	13.24	-22.84	do	z 61	0.774	2'-0"		
1.17	11.59	-14.71	do	z 90	0.862	2'-11 3/8"		
1.18	11.79	-15.71	LL 2 X .188	z 85	0.862	2'-11 3/8"		

Bottom Chord

2.1	0.00	0.00	LL 2 X .156	z 131	0.420	4'-5 7/8"		
2.2	17.65	-3.59	do	z 98	0.630	3'-2 5/8"		
2.3	26.43	-5.37	do	z 121	0.769	4'-0"		
2.4	32.29	-6.56	do	z 121	0.897	do		
2.5	35.22	-7.16	do	z 121	0.979	do		
2.6	35.22	-7.16	do	z 121	0.979	do		
2.7	32.29	-6.56	do	z 121	0.897	do		
2.8	26.43	-5.37	do	z 121	0.769	4'-0"		
2.9	17.65	-3.59	do	z 98	0.630	3'-2 5/8"		
2.10	0.00	0.00	LL 2 X .156	z 142	0.420	4'-10 1/4"		

End Diagonal

3.1	17.12	-3.48	SQUARE BAR 1" (50 ksi)	z 208	0.648	5'-1 3/4"	.250 - 2 3/8"	
3.2	17.12	-3.48	SQUARE BAR 1" (50 ksi)	z 209	0.651	5'-1 3/4"	.250 - 2 3/8"	

Diagonal Towards End

4.1	7.45	-1.51	U 1 x 1 x 0.118	z 124	0.841	3'-2 3/8"	.118 - 2 1/8"	
4.2	5.15	-1.05	U 1 x 1 x 0.090	z 127	0.759	do	.091 - 1 7/8"	
4.3	2.86	-0.58	do	z 127	0.421	do	.091 - 1 1/2"	
4.4	2.83	-0.12	do	z 127	0.417	do	do	
4.5	2.83	-0.12	do	z 128	0.417	do	do	
4.6	2.86	-0.58	do	z 128	0.421	do	.091 - 1 1/2"	
4.7	5.15	-1.05	U 1 x 1 x 0.090	z 128	0.759	do	.091 - 1 7/8"	
4.8	7.45	-1.51	U 1 x 1 x 0.118	z 124	0.841	3'-2 3/8"	.118 - 2 1/8"	

Diagonal Towards Center

5.1	1.55	-7.64 d	U 1 3/8 x 0.157	z 71	0.636	2'-9 3/8"	.158 - 1 5/8"	
5.2	1.28	-6.30 d	U 1 3/8 x 0.157	z 83	0.590	3'-2 3/8"	.158 - 1 1/2"	
5.3	0.81	-4.01 d	U 1 3/8 x 0.118	z 85	0.686	do	.118 - 1 1/2"	
5.4	0.35	-2.83	U 1 x 1 x 0.118	z 124	0.985	do	do	
5.5	0.35	-2.83	U 1 x 1 x 0.118	z 124	0.979	do	do	
5.6	0.81	-4.01 d	U 1 3/8 x 0.118	z 84	0.684	do	.118 - 1 1/2"	
5.7	1.28	-6.30 d	U 1 3/8 x 0.157	z 83	0.588	3'-2 3/8"	.158 - 1 1/2"	

FORCES IN MEMBERS (Cont.) [kips]

REQUIRED MATERIAL

REQUIRED WELD

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	Weld-Ea.Side	Remarks
5.8	1.55	-7.64	d	U 1 3/8 x 0.157	z 71	0.635	2'-9 3/8"	.158 - 1 5/8"

Secondary Web Member

7.1	0.31	-1.63	U 1 x 1 x 0.090	z 120	0.698	3'-0 1/2"	.091 - 1 1/2"
7.2	0.18	-1.00	do	z 97	0.288	2'-6"	do
7.3	0.18	-1.04	do	z 97	0.299	do	do
7.4	0.18	-1.06	do	z 97	0.306	do	do
7.5	0.18	-1.07	do	z 97	0.309	do	do
7.6	0.18	-1.06	do	z 97	0.307	do	do
7.7	0.18	-1.04	do	z 97	0.300	do	do
7.8	0.18	-1.00	do	z 97	0.289	2'-6"	do
7.9	0.31	-1.63	U 1 x 1 x 0.090	z 121	0.704	3'-0 1/2"	.091 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging						Laterals supports
@ Top Chord:	14'-10"	==>	3 Row(s) Minimum			Deck (36")
@ Bottom Chord:	24'-4 7/8"	==>	5 Row(s) Minimum			Acc. to the code

POSITION

@ Top Chord	@ Bottom Chord
9'-11 3/8" (9'-11")	4'-8" (4'-7 7/8")
19'-10 5/8" (19'-10")	9'-11 3/8" (9'-11")
29'-9 7/8" (29'-9")	19'-10 5/8" (19'-10")
	29'-9 7/8" (29'-9")
	35'-1 1/4" (35'-0 1/8")

v3.6 11/29/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,	BL = 2 angles welded in box,	BR = Round bar
-U = 1 U profile,	UU = 2 U profiles one inside the other,	-CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

449 (76.25) / 482 (81.25)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J3 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 438.92 lb/ft

30K10

LIVE LOAD ...: 316.50 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	--L--	--R--	--L--	--R--	--L--	--R--
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.27 in (L/ 374)
Joist inertia	=	545.35 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THAT SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.69/ -1.78 kips

Right Reaction = 8.69/ -1.78 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

No	Tension	Compres.					
1.1	11.67	-15.09	LL 2 X .188	z 86	0.857	2'-11 3/4"	
1.2	11.48	-14.20	do	z 91	0.857	2'-11 3/4"	
1.3	13.20	-22.59	do	z 61	0.772	2'-0"	
1.4	13.20	-22.59	do	z 61	0.699	do	
1.5	14.70	-29.89	do	z 61	0.924	do	
1.6	14.70	-29.89	do	z 61	0.924	do	
1.7	15.60	-34.26 x	do	xx 39	0.920	do	
1.8	15.60	-34.26 x	do	xx 39	0.920	do	
1.9	15.90	-35.72 x	LL 2 X .188	xx 39	0.959	2'-0"	

Bottom Chord

2.1	0.00	0.00	LL 2 X .156	z 137	0.425	4'-8"	
2.2	17.85	-3.66	do	z 100	0.634	3'-3 1/2"	
2.3	26.60	-5.45	do	z 121	0.773	4'-0"	
2.4	32.44	-6.65	do	z 121	0.902	do	
2.5	35.36	-7.25	LL 2 X .156	z 121	0.983	4'-0"	

End Diagonal

3.1	17.11	-3.51	SQUARE BAR 1" (50 ksi)	z 209	0.655	5'-1 3/4"	.250 - 2 3/8"
-----	-------	-------	------------------------	-------	-------	-----------	---------------

Diagonal Towards End

4.1	7.42	-1.52	U 1 x 1 x 0.118	z 124	0.838	3'-2 3/8"	.118 - 2 1/8"
4.2	5.14	-1.05	U 1 x 1 x 0.090	z 128	0.756	do	.091 - 1 7/8"
4.3	2.85	-0.59	do	z 128	0.420	do	.091 - 1 1/2"
4.4	2.82	-0.12	U 1 x 1 x 0.090	z 128	0.416	3'-2 3/8"	.091 - 1 1/2"

Diagonal Towards Center

5.1	1.58	-7.72 d	U 1 3/8 x 0.157	z 72	0.647	2'-9 3/4"	.158 - 1 5/8"
5.2	1.29	-6.28 d	U 1 3/8 x 0.157	z 83	0.587	3'-2 3/8"	.158 - 1 1/2"
5.3	0.82	-3.99 d	U 1 3/8 x 0.118	z 85	0.682	do	.118 - 1 1/2"
5.4	0.35	-2.82	U 1 x 1 x 0.118	z 124	0.979	3'-2 3/8"	.118 - 1 1/2"

Secondary Web Member

7.1	0.32	-1.63	U 1 x 1 x 0.090	z 120	0.692	3'-0 1/4"	.091 - 1 1/2"
7.2	0.18	-1.00	U 1 x 5/8 x 0.090	z 159	1.007	2'-6"	do
7.3	0.18	-1.04	U 1 x 1 x 0.090	z 97	0.299	do	do
7.4	0.18	-1.06	do	z 97	0.306	do	do
7.5	0.18	-1.07	U 1 x 1 x 0.090	z 97	0.308	2'-6"	.091 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-10" ==>
@ Bottom Chord: 24'-4 7/8" ==>

3 Row(s) Minimum
5 Row(s) Minimum

Laterals supports

Deck (36")
Acc. to the code

POSITION

@ Top Chord

9'-11 3/4"
19'-11 1/2"
29'-11 1/4"

@ Bottom Chord

4'-8"
9'-11 3/4"
19'-11 1/2"
29'-11 1/4"
35'-3"



Mark: J3

Project: COLUMBIA DISTRIBUTION A04061

12/01/00

19:47:20

v3.6 11/29/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

450 (76.24) / 483 (81.23)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J4 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 439.83 lb/ft

30K10

LIVE LOAD ...: 318.00 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	--L--	--R--	--L--	--R--	--L--	--R--
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.26 in (L/ 375)
Joist inertia	=	545.35 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.69/ -1.78 kips Right Reaction = 8.69/ -1.78 kips

			REQUIRED MATERIAL		Slend.	Util.	Length	REQUIRED WELD		Remarks
No	Tension	Compres.	x = tied at mid-length					Weld-Ea.Side		
Top Chord										
1.1	11.66	-15.10	LL 2 X .188		z 85	0.851	2'-11 1/2"			
1.2	11.48	-14.20	do		z 90	0.852	2'-11 1/2"			
1.3	13.17	-22.49	do		z 61	0.767	2'-0"			
1.4	13.17	-22.49	do		z 61	0.696	do			
1.5	14.67	-29.80	do		z 61	0.922	do			
1.6	14.67	-29.80	do		z 61	0.922	do			
1.7	15.57	-34.18 x	do		xx 39	0.918	do			
1.8	15.57	-34.18 x	do		xx 39	0.918	do			
1.9	15.87	-35.65 x	LL 2 X .188		xx 39	0.957	2'-0"			
Bottom Chord										
2.1	0.00	0.00	LL 2 X .156		z 137	0.423	4'-8"			
2.2	17.73	-3.63	do		z 99	0.631	3'-3"			
2.3	26.51	-5.42	do		z 121	0.771	4'-0"			
2.4	32.36	-6.62	do		z 121	0.899	do			
2.5	35.28	-7.22	LL 2 X .156		z 121	0.981	4'-0"			
End Diagonal										
3.1	17.12	-3.50	SQUARE BAR 1" (50 ksi)		z 209	0.654	5'-1 3/4"	.250 - 2 3/8"		
Diagonal Towards End										
4.1	7.43	-1.52	U 1 x 1 x 0.118		z 124	0.839	3'-2 3/8"	.118 - 2 1/8"		
4.2	5.15	-1.05	U 1 x 1 x 0.090		z 128	0.757	do	.091 - 1 7/8"		
4.3	2.86	-0.59	do		z 128	0.421	do	.091 - 1 1/2"		
4.4	2.82	-0.12	U 1 x 1 x 0.090		z 128	0.416	3'-2 3/8"	.091 - 1 1/2"		
Diagonal Towards Center										
5.1	1.57	-7.67 d	U 1 3/8 x 0.157		z 72	0.640	2'-9 1/2"	.158 - 1 5/8"		
5.2	1.29	-6.29 d	U 1 3/8 x 0.157		z 83	0.588	3'-2 3/8"	.158 - 1 1/2"		
5.3	0.82	-4.00 d	U 1 3/8 x 0.118		z 85	0.684	do	.118 - 1 1/2"		
5.4	0.35	-2.82	U 1 x 1 x 0.118		z 124	0.979	3'-2 3/8"	.118 - 1 1/2"		
Secondary Web Member										
7.1	0.32	-1.63	U 1 x 1 x 0.090		z 120	0.697	3'-0 3/8"	.091 - 1 1/2"		
7.2	0.18	-1.00	U 1 x 5/8 x 0.090		z 159	1.008	2'-6"	do		
7.3	0.18	-1.04	U 1 x 1 x 0.090		z 97	0.299	do	do		
7.4	0.18	-1.06	do		z 97	0.306	do	do		
7.5	0.18	-1.07	U 1 x 1 x 0.090		z 97	0.308	2'-6"	.091 - 1 1/2"		

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-10" ==> 3 Row(s) Minimum

@ Bottom Chord: 24'-4 7/8" ==> 5 Row(s) Minimum

Laterals supports Deck (36")

Acc. to the code

POSITION

@ Top Chord

9'-11 1/2"

19'-11"

29'-10 1/2"

@ Bottom Chord

4'-8"

9'-11 1/2"

19'-11"

29'-10 1/2"

35'-2"

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

449 (76.11) / 482 (81.10)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J5 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 439.38 lb/ft 30K10 LIVE LOAD ...: 317.25 lb/ft

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

----- UPLIFT -----

Net uplift uniform load : 120.00 lb/ft

----- DEFLECTION -----

Allowed deflection under live load = 1.32 in (L/ 360)
 Calculated deflection under service live load = 1.27 in (L/ 374)
 Joist inertia = 545.35 in⁴
 Required camber = 0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.69/ -1.78 kips

Right Reaction = 8.69/ -1.78 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

No	Tension	Compres.				
1.1	11.66	-15.09	LL 2 X .188	z 85	0.854	2'-11 5/8"
1.2	11.48	-14.20	do	z 90	0.855	2'-11 5/8"
1.3	13.19	-22.54	do	z 61	0.769	2'-0"
1.4	13.19	-22.54	do	z 61	0.697	do
1.5	14.68	-29.84	do	z 61	0.923	do
1.6	14.68	-29.84	do	z 61	0.923	do
1.7	15.58	-34.22 x	do	xx 39	0.919	do
1.8	15.58	-34.22 x	do	xx 39	0.919	do
1.9	15.88	-35.68 x	LL 2 X .188	xx 39	0.958	2'-0"

Bottom Chord

2.1	0.00	0.00	LL 2 X .156	z 137	0.424	4'-8"
2.2	17.79	-3.64	do	z 99	0.633	3'-3 1/4"
2.3	26.55	-5.44	do	z 121	0.772	4'-0"
2.4	32.40	-6.64	do	z 121	0.900	do
2.5	35.32	-7.23	LL 2 X .156	z 121	0.982	4'-0"

End Diagonal

3.1	17.11	-3.51	SQUARE BAR 1" (50 ksi)	z 209	0.654	5'-1 3/4" .250 - 2 3/8"
-----	-------	-------	------------------------	-------	-------	-------------------------

Diagonal Towards End

4.1	7.43	-1.52	U 1 x 1 x 0.118	z 124	0.838	3'-2 3/8" .118 - 2 1/8"
4.2	5.14	-1.05	U 1 x 1 x 0.090	z 128	0.757	do .091 - 1 7/8"
4.3	2.86	-0.59	do	z 128	0.420	do .091 - 1 1/2"
4.4	2.82	-0.12	U 1 x 1 x 0.090	z 128	0.416	3'-2 3/8" .091 - 1 1/2"

Diagonal Towards Center

5.1	1.58	-7.69 d	U 1 3/8 x 0.157	z 72	0.643	2'-9 5/8" .158 - 1 5/8"
5.2	1.29	-6.28 d	U 1 3/8 x 0.157	z 83	0.587	3'-2 3/8" .158 - 1 1/2"
5.3	0.82	-4.00 d	U 1 3/8 x 0.118	z 85	0.683	do .118 - 1 1/2"
5.4	0.35	-2.82	U 1 x 1 x 0.118	z 124	0.979	3'-2 3/8" .118 - 1 1/2"

Secondary Web Member

7.1	0.32	-1.63	U 1 x 1 x 0.090	z 120	0.694	3'-0 1/4" .091 - 1 1/2"
7.2	0.18	-1.00	U 1 x 5/8 x 0.090	z 159	1.007	2'-6" do
7.3	0.18	-1.04	U 1 x 1 x 0.090	z 97	0.299	do do
7.4	0.18	-1.06	do	z 97	0.306	do do
7.5	0.18	-1.07	U 1 x 1 x 0.090	z 97	0.308	2'-6" .091 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-10" ==>
@ Bottom Chord: 24'-4 7/8" ==>

3 Row(s) Minimum
5 Row(s) Minimum

Laterals supports

Deck (36")

Acc. to the code

POSITION

@ Top Chord

9'-11 5/8"
19'-11 1/4"
29'-10 7/8"

@ Bottom Chord

4'-8"
9'-11 5/8"
19'-11 1/4"
29'-10 7/8"
35'-2 1/2"



Mark: J5

Project: COLUMBIA DISTRIBUTION A04061

12/01/00

19:47:22

v3.6 11/29/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

449 (76.17) / 482 (81.17)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J6 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.68/ -1.77 kips

Right Reaction = 8.68/ -1.77 kips

No	Tension	Compres.	REQUIRED MATERIAL		Slen/i.	Util.	Length	REQUIRED WELD		Remarks
			x = tied at mid-length					Weld-Ea.Side		
Top Chord										
1.1	11.66	-15.10		LL 2 X .188	z 84	0.845	2'-11 1/4"			
1.2	11.47	-14.20		do	z 90	0.847	2'-11 1/4"			
1.3	13.14	-22.38		do	z 61	0.762	2'-0"			
1.4	13.14	-22.38		do	z 61	0.692	do			
1.5	14.64	-29.71		do	z 61	0.919	do			
1.6	14.64	-29.71		do	z 61	0.919	do			
1.7	15.54	-34.10	x	do	xx 39	0.916	do			
1.8	15.54	-34.10	x	do	xx 39	0.916	do			
1.9	15.84	-35.57	x	LL 2 X .188	xx 39	0.955	2'-0"			
Bottom Chord										
2.1	0.00	0.00		LL 2 X .156	z 137	0.420	4'-8"			
2.2	17.62	-3.60		do	z 97	0.629	3'-2 1/2"			
2.3	26.41	-5.39		do	z 121	0.769	4'-0"			
2.4	32.27	-6.59		do	z 121	0.897	do			
2.5	35.20	-7.19		LL 2 X .156	z 121	0.978	4'-0"			
End Diagonal										
3.1	17.12	-3.50		SQUARE BAR 1" (50 ksi)	z 209	0.652	5'-1 3/4"	.250 -	2 3/8"	
Diagonal Towards End										
4.1	7.45	-1.52		U 1 x 1 x 0.118	z 124	0.841	3'-2 3/8"	.118 -	2 1/0"	
4.2	5.16	-1.05		U 1 x 1 x 0.090	z 128	0.759	do	.091 -	1 7/8"	
4.3	2.87	-0.59		do	z 128	0.422	do	.091 -	1 1/2"	
4.4	2.82	-0.12		U 1 x 1 x 0.090	z 128	0.415	3'-2 3/8"	.091 -	1 1/2"	
Diagonal Towards Center										
5.1	1.56	-7.63	d	U 1 3/8 x 0.157	z 71	0.633	2'-9 3/8"	.158 -	1 5/8"	
5.2	1.29	-6.30	d	U 1 3/8 x 0.157	z 83	0.589	3'-2 3/8"	.158 -	1 1/2"	
5.3	0.82	-4.01	d	U 1 3/8 x 0.118	z 85	0.685	do	.118 -	1 1/2"	
5.4	0.35	-2.82		U 1 x 1 x 0.118	z 124	0.979	3'-2 3/8"	.118 -	1 1/2"	
Secondary Web Member										
7.1	0.32	-1.63		U 1 x 1 x 0.090	z 121	0.702	3'-0 1/2"	.091 -	1 1/2"	
7.2	0.18	-1.00		U 1 x 5/8 x 0.090	z 159	1.009	2'-6"	do		
7.3	0.18	-1.04		U 1 x 1 x 0.090	z 97	0.300	do	do		
7.4	0.18	-1.06		do	z 97	0.306	do	do		
7.5	0.18	-1.07		U 1 x 1 x 0.090	z 97	0.309	2'-6"	.091 -	1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-10" ==>
@ Bottom Chord: 24'-4 7/8" ==>

3 Row(s) Minimum
5 Row(s) Minimum

Laterals supports

Deck (36")

Acc. to the code

POSITION

@ Top Chord

9'-11 1/4"
19'-10 1/2"
29'-9 3/4"

@ Bottom Chord

4'-8"
9'-11 1/4"
19'-10 1/2"
29'-9 3/4"
35'-1"



Mark: J6

Project: COLUMBIA DISTRIBUTION A04061

12/01/00

19:47:23

v3.6 11/29/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

448 (75.98) / 481 (80.98)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J7 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 439.60 lb/ft 30K10 LIVE LOAD ...: 317.63 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.26 in (L/ 375)
Joist inertia	=	545.35 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.69/ -1.78 kips Right Reaction = 8.69/ -1.78 kips

REQUIRED MATERIAL

No	Tension	Compres.	x = tied at mid-length	Slend.	Util.	Length	REQUIRED WELD Weld-Ea.Side	Remarks
Top Chord								
1.1	11.66	-15.09	LL 2 X .188	z 85	0.852	2'-11 1/2"		
1.2	11.48	-14.20	do	z 90	0.853	2'-11 1/2"		
1.3	13.18	-22.51	do	z 61	0.768	2'-0"		
1.4	13.18	-22.51	do	z 61	0.696	do		
1.5	14.68	-29.82	do	z 61	0.922	do		
1.6	14.68	-29.82	do	z 61	0.922	do		
1.7	15.57	-34.20 x	do	xx 39	0.918	do		
1.8	15.57	-34.20 x	do	xx 39	0.918	do		
1.9	15.87	-35.66 x	LL 2 X .188	xx 39	0.957	2'-0"		

Bottom Chord

2.1	0.00	0.00	LL 2 X .156	z 137	0.423	4'-8"		
2.2	17.76	-3.64	do	z 99	0.632	3'-3 1/8"		
2.3	26.53	-5.43	do	z 121	0.771	4'-0"		
2.4	32.38	-6.63	do	z 121	0.900	do		
2.5	35.30	-7.23	LL 2 X .156	z 121	0.981	4'-0"		

End Diagonal

3.1	17.12	-3.50	SQUARE BAR 1" (50 ksi)	z 209	0.654	5'-1 3/4"	.250 - 2 3/8"	
-----	-------	-------	------------------------	-------	-------	-----------	---------------	--

Diagonal Towards End

4.1	7.43	-1.52	U 1 x 1 x 0.118	z 124	0.839	3'-2 3/8"	.118 - 2 1/8"	
4.2	5.14	-1.05	U 1 x 1 x 0.090	z 128	0.757	do	.091 - 1 7/8"	
4.3	2.86	-0.59	do	z 128	0.421	do	.091 - 1 1/2"	
4.4	2.82	-0.12	U 1 x 1 x 0.090	z 128	0.416	3'-2 3/8"	.091 - 1 1/2"	

Diagonal Towards Center

5.1	1.57	-7.68 d	U 1 3/8 x 0.157	z 72	0.642	2'-9 5/8"	.158 - 1 5/8"	
5.2	1.29	-6.29 d	U 1 3/8 x 0.157	z 83	0.588	3'-2 3/8"	.158 - 1 1/2"	
5.3	0.82	-4.00 d	U 1 3/8 x 0.118	z 85	0.683	do	.118 - 1 1/2"	
5.4	0.35	-2.82	U 1 x 1 x 0.118	z 124	0.979	3'-2 3/8"	.118 - 1 1/2"	

Secondary Web Member

7.1	0.32	-1.63	U 1 x 1 x 0.090	z 120	0.696	3'-0 1/4"	.091 - 1 1/2"	
7.2	0.18	-1.00	U 1 x 5/8 x 0.090	z 159	1.008	2'-6"	do	
7.3	0.18	-1.04	U 1 x 1 x 0.090	z 97	0.299	do	do	
7.4	0.18	-1.06	do	z 97	0.306	do	do	
7.5	0.18	-1.07	U 1 x 1 x 0.090	z 97	0.308	2'-6"	.091 - 1 1/2"	

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-10" ==>
@ Bottom Chord: 24'-4 7/8" ==>

3 Row(s) Minimum
5 Row(s) Minimum

Laterals supports

Deck (36")
Acc. to the code

POSITION

@ Top Chord

9'-11 5/8"
19'-11 1/8"
29'-10 5/8"


@ Bottom Chord

4'-8"
9'-11 5/8"
19'-11 1/8"
29'-10 5/8"
35'-2 1/4"

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J8 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 468.00 lb/ft

30KSP468/345

LIVE LOAD ...: 345.00 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.27 in (L/ 374)
Joist inertia	=	591.32 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

($F_y = 50$ Ksi U/N)

(Eff. depth = 28.86 in)

Left Reaction = 9.25/ -1.78 kips Right Reaction = 9.25/ -1.78 kips

			REQUIRED MATERIAL		Slend.	Util.	Length	REQUIRED WELD		Remarks			
No	Tension	Compres.	x = tied at mid-length					Weld-Ea.Side					
Top Chord													
1.1	11.67	-16.08		LL 2 X .216	z 86	0.798	2'-11 1/2"						
1.2	11.48	-15.12		do	z 91	0.798	2'-11 1/2"						
1.3	13.19	-23.98		do	z 61	0.718	2'-0"						
1.4	13.19	-23.98		do	z 61	0.651	do						
1.5	14.68	-31.76		do	z 61	0.863	do						
1.6	14.68	-31.76		do	z 61	0.863	do						
1.7	15.58	-36.43		do	z 61	0.990	do						
1.8	15.58	-36.43		do	z 61	0.990	do						
1.9	15.88	-37.99	x	LL 2 X .216	xx 39	0.895	2'-0"						
Bottom Chord													
2.1	0.00	0.00		LL 2 X .163	z 137	0.432	4'-8"						
2.2	18.92	-3.64		do	z 99	0.645	3'-3 1/8"						
2.3	28.26	-5.43		do	z 121	0.788	4'-0"						
2.4	34.48	-6.63		do	z 121	0.919	do						
2.5	37.60	-7.23		LL 2 X .163	z 121	1.002	4'-0"						
End Diagonal													
3.1	18.23	-3.51		SQUARE BAR 1" (50 ksi)	z 209	0.675	5'-1 3/4"	.250 -	2 1/2"				
Diagonal Towards End													
4.1	7.91	-1.52		U 1 x 1 x 0.118	z 124	0.893	3'-2 3/8"	.118 -	2 1/4"				
4.2	5.48	-1.05		U 1 x 1 x 0.090	z 128	0.806	do	.091 -	2"				
4.3	3.04	-0.59		do	z 128	0.448	do	.091 -	1 1/2"				
4.4	3.01	-0.12		U 1 x 1 x 0.090	z 128	0.442	3'-2 3/8"	.091 -	1 1/2"				
Diagonal Towards Center													
5.1	1.57	-8.18	d	U 1 3/8 x 0.157	z 72	0.683	2'-9 5/8"	.158 -	1 3/4"				
5.2	1.29	-6.69	d	U 1 3/8 x 0.157	z 83	0.626	3'-2 3/8"	.158 -	1 1/2"				
5.3	0.82	-4.26	d	U 1 3/8 x 0.118	z 85	0.727	do	.118 -	1 1/2"				
5.4	0.35	-3.01	d	U 1 3/8 x 0.118	z 85	0.513	3'-2 3/8"	.118 -	1 1/2"				
Secondary Web Member													
7.1	0.32	-1.74		U 1 x 1 x 0.090	z 120	0.740	3'-0 1/4"	.091 -	1 1/2"				
7.2	0.18	-1.06		do	z 97	0.306	2'-6"	do					
7.3	0.18	-1.10		do	z 97	0.318	do	do					
7.4	0.18	-1.13		do	z 97	0.325	do	do					
7.5	0.18	-1.14		U 1 x 1 x 0.090	z 97	0.328	2'-6"	.091 -	1 1/2"				

BRIDGING

Maximum spacing between rows of bridging Laterals supports
@ Top Chord: 14'-11" ==> 2 Row(s) Minimum Deck (36")
@ Bottom Chord: 24'-5 1/4" ==> 4 Row(s) Minimum Acc. to the code

POSITION @ Top Chord @ Bottom Chord
13'-3 3/8" 4'-8"
26'-6 7/8" 13'-3 3/8"
26'-6 7/8"
35'-2 1/4"

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

486 (79.59) / 521 (84.80)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J9 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 488.00 lb/ft

30KSP488/365

LIVE LOAD ...: 365.00 lb/ft

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(Q) Wind or Seism (case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

----- UPLIFT -----

Net uplift uniform load : 120.00 lb/ft

----- DEFLECTION -----

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.24 in (L/ 381)
Joist inertia	=	636.86 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.85 in)

Left Reaction = 9.64/ -1.78 kips

Right Reaction = 9.64/ -1.78 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

No Tension Compres.

Top Chord

1.1	11.67	-16.77	LL 2 X .216	z 86	0.832	2'-11 1/2"
1.2	11.49	-15.77	do	z 91	0.833	2'-11 1/2"
1.3	13.19	-25.01	do	z 61	0.749	2'-0"
1.4	13.19	-25.01	do	z 61	0.679	do
1.5	14.69	-33.13	do	z 61	0.900	do
1.6	14.69	-33.13	do	z 61	0.900	do
1.7	15.59	-38.00 x	do	xx 39	0.896	do
1.8	15.59	-38.00 x	do	xx 39	0.896	do
1.9	15.89	-39.62 x	LL 2 X .216	xx 39	0.934	2'-0"

Bottom Chord

2.1	0.00	0.00	LL 2 X .188	z 137	0.393	4'-8"
2.2	19.73	-3.64	do	z 99	0.588	3'-3 1/8"
2.3	29.47	-5.44	do	z 122	0.717	4'-0"
2.4	35.97	-6.63	do	z 122	0.836	do
2.5	39.22	-7.23	LL 2 X .188	z 122	0.912	4'-0"

End Diagonal

3.1	19.01	-3.51	SQUARE BAR 1" (50 ksi)	z 209	0.704	5'-1 3/4" .250 - 2 1/2"
-----	-------	-------	------------------------	-------	-------	-------------------------

Diagonal Towards End

4.1	8.25	-1.52	U 1 x 1 x 0.118	z 124	0.931	3'-2 3/8" .118 - 2 3/8"
4.2	5.71	-1.05	U 1 x 1 x 0.090	z 128	0.841	do .091 - 2 1/8"
4.3	3.17	-0.59	do	z 128	0.467	do .091 - 1 1/2"
4.4	3.14	-0.12	U 1 x 1 x 0.090	z 128	0.461	3'-2 3/8" .091 - 1 1/2"

Diagonal Towards Center

5.1	1.57	-8.53 d	U 1 3/8 x 0.157	z 72	0.712	2'-9 5/8" .158 - 1 3/4"
5.2	1.29	-6.98 d	U 1 3/8 x 0.157	z 83	0.652	3'-2 3/8" .158 - 1 1/2"
5.3	0.82	-4.44 d	U 1 3/8 x 0.118	z 85	0.758	do .118 - 1 1/2"
5.4	0.35	-3.14 d	U 1 3/8 x 0.118	z 85	0.535	3'-2 3/8" .118 - 1 1/2"

Secondary Web Member

7.1	0.32	-1.81	U 1 x 1 x 0.090	z 120	0.772	3'-0 1/4" .091 - 1 1/2"
7.2	0.18	-1.11	do	z 97	0.319	2'-6" do
7.3	0.18	-1.15	do	z 97	0.332	do do
7.4	0.18	-1.18	do	z 97	0.339	do do
7.5	0.18	-1.19	U 1 x 1 x 0.090	z 97	0.342	2'-6" .091 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord:

14'-11" ==>

2 Row(s) Minimum

Laterals supports

Deck (36")

@ Bottom Chord:

24'-6 3/4" ==>

4 Row(s) Minimum

Acc. to the code

POSITION

@ Top Chord

@ Bottom Chord

13'-3 3/8"

4'-8"

26'-6 7/8"

13'-3 3/8"

26'-6 7/8"

35'-2 1/4"



Mark: J9

Project: COLUMBIA DISTRIBUTION A04061

12/01/00

19:47:25

v3.6 11/29/00

Fabrication code unless noted

-LL = 2 angles short legs back to back, BL = 2 angles welded in box, BR = Round bar
-U = 1 U profile, UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault


Shop: Canam Sunnyside [Production]

507 (82.41) / 547 (88.32)

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J10 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



----- LOADING CONDITIONS -----

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 438.92 lb/ft

30K10

LIVE LOAD ...: 316.50 lb/ft

----- END MOMENTS [ft-kip] & AXIAL LOADS [kips] -----

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(Q) Wind or Seism (case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

----- UPLIFT -----

Net uplift uniform load : 120.00 lb/ft

----- DEFLECTION -----

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.27 in (L/ 374)
Joist inertia	=	545.35 in ⁴
Required camber	=	0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

(Fy = 50 Ksi U/N)

(Eff. depth = 28.87 in)

Left Reaction = 8.69/ -1.78 kips Right Reaction = 8.69/ -1.78 kips

REQUIRED MATERIAL

No Tension Compres. x = tied at mid-length Slend. Util. Length REQUIRED WELD Weld-Ea.Side Remarks

Top Chord

1.1	11.67	-15.09	LL 2 X .188	z 86	0.857	2'-11 3/4"
1.2	11.48	-14.20	do	z 91	0.857	2'-11 3/4"
1.3	13.20	-22.59	do	z 61	0.772	2'-0"
1.4	13.20	-22.59	do	z 61	0.699	do
1.5	14.70	-29.89	do	z 61	0.924	do
1.6	14.70	-29.89	do	z 61	0.924	do
1.7	15.60	-34.26 x	do	xx 39	0.920	do
1.8	15.60	-34.26 x	do	xx 39	0.920	do
1.9	15.90	-35.72 x	LL 2 X .188	xx 39	0.959	2'-0"

Bottom Chord

2.1	0.00	0.00	LL 2 X .156	z 137	0.425	4'-8"
2.2	17.85	-3.66	do	z 100	0.634	3'-3 1/2"
2.3	26.60	-5.45	do	z 121	0.773	4'-0"
2.4	32.44	-6.65	do	z 121	0.902	do
2.5	35.36	-7.25	LL 2 X .156	z 121	0.983	4'-0"

End Diagonal

3.1	17.11	-3.51	SQUARE BAR 1" (50 ksi)	z 209	0.655	5'-1 3/4" .250 - 2 3/8"
-----	-------	-------	------------------------	-------	-------	-------------------------

Diagonal Towards End

4.1	7.42	-1.52	U 1 x 1 x 0.118	z 124	0.838	3'-2 3/8" .118 - 2 1/8"
4.2	5.14	-1.05	U 1 x 1 x 0.090	z 128	0.756	do .091 - 1 7/8"
4.3	2.85	-0.59	do	z 128	0.420	do .091 - 1 1/2"
4.4	2.82	-0.12	U 1 x 1 x 0.090	z 128	0.416	3'-2 3/8" .091 - 1 1/2"

Diagonal Towards Center

5.1	1.58	-7.72 d	U 1 3/8 x 0.157	z 72	0.647	2'-9 3/4" .158 - 1 5/8"
5.2	1.29	-6.28 d	U 1 3/8 x 0.157	z 83	0.587	3'-2 3/8" .158 - 1 1/2"
5.3	0.82	-3.99 d	U 1 3/8 x 0.118	z 85	0.682	do .118 - 1 1/2"
5.4	0.35	-2.82	U 1 x 1 x 0.118	z 124	0.979	3'-2 3/8" .118 - 1 1/2"

Secondary Web Member

7.1	0.32	-1.63	U 1 x 1 x 0.090	z 120	0.692	3'-0 1/4" .091 - 1 1/2"
7.2	0.18	-1.00	U 1 x 5/8 x 0.090	z 159	1.007	2'-6" do
7.3	0.18	-1.04	U 1 x 1 x 0.090	z 97	0.299	do do
7.4	0.18	-1.06	do	z 97	0.306	do do
7.5	0.18	-1.07	U 1 x 1 x 0.090	z 97	0.308	2'-6" .091 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-10" ==>
@ Bottom Chord: 24'-4 7/8" ==>

3 Row(s) Minimum
5 Row(s) Minimum

Laterals supports
Deck (36")
Acc. to the code

POSITION

@ Top Chord

@ Bottom Chord


9'-11 3/4"
19'-11 1/2"
29'-11 1/4"

4'-8"
9'-11 3/4"
19'-11 1/2"
29'-11 1/4"
35'-3"

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J11 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 468.00 lb/ft

30KSP468/345

LIVE LOAD ...: 345.00 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load = 1.32 in (L/ 360)
 Calculated deflection under service live load = 1.28 in (L/ 372)
 Joist inertia = 591.32 in⁴
 Required camber = 0.62 in

FORCES IN MEMBERS [kips]

(THE SHOWN FORCES ARE REALS)

($F_y = 50$ Ksi U/N)

(Eff. depth = 28.86 in)

Left Reaction = 9.26/ -1.78 kips

Right Reaction = 9.26/ -1.78 kips

REQUIRED MATERIAL

x = tied at mid-length

Slend.

Util.

Length

REQUIRED WELD

Weld-Ea.Side

Remarks

Top Chord

No	Tension	Compres.				
1.1	11.67	-16.10	LL 2 X .216	z 86	0.803	2'-11 3/4"
1.2	11.49	-15.15	do	z 91	0.803	2'-11 3/4"
1.3	13.21	-24.10	do	z 61	0.723	2'-0"
1.4	13.21	-24.10	do	z 61	0.655	do
1.5	14.71	-31.88	do	z 61	0.866	do
1.6	14.71	-31.88	do	z 61	0.866	do
1.7	15.60	-36.55	do	z 61	0.993	do
1.8	15.60	-36.55	do	z 61	0.993	do
1.9	15.90	-38.11 x	LL 2 X .216	xx 39	0.898	2'-0"

Bottom Chord

2.1	0.00	0.00	LL 2 X .163	z 137	0.435	4'-8"
2.2	19.04	-3.66	do	z 100	0.648	3'-3 1/2"
2.3	28.38	-5.46	do	z 121	0.790	4'-0"
2.4	34.60	-6.65	do	z 121	0.922	do
2.5	37.72	-7.25	LL 2 X .163	z 121	1.005	4'-0"

End Diagonal

3.1	18.25	-3.51	SQUARE BAR 1" (50 ksi)	z 209	0.676	5'-1 3/4" .250 - 2 1/2"
-----	-------	-------	------------------------	-------	-------	-------------------------

Diagonal Towards End

4.1	7.91	-1.52	U 1 x 1 x 0.118	z 124	0.893	3'-2 3/8" .118 - 2 1/4"
4.2	5.48	-1.05	U 1 x 1 x 0.090	z 128	0.806	do .091 - 2"
4.3	3.04	-0.59	do	z 128	0.448	do .091 - 1 1/2"
4.4	3.01	-0.12	U 1 x 1 x 0.090	z 128	0.443	3'-2 3/8" .091 - 1 1/2"

Diagonal Towards Center

5.1	1.58	-8.23 d	U 1 3/8 x 0.157	z 72	0.690	2'-9 3/4" .158 - 1 3/4"
5.2	1.29	-6.69 d	U 1 3/8 x 0.157	z 83	0.626	3'-2 3/8" .158 - 1 1/2"
5.3	0.82	-4.26 d	U 1 3/8 x 0.118	z 85	0.727	do .118 - 1 1/2"
5.4	0.35	-3.01 d	U 1 3/8 x 0.118	z 85	0.514	3'-2 3/8" .118 - 1 1/2"

Secondary Web Member

7.1	0.32	-1.74	U 1 x 1 x 0.090	z 120	0.737	3'-0 1/4" .091 - 1 1/2"
7.2	0.18	-1.06	do	z 97	0.307	2'-6" do
7.3	0.18	-1.10	do	z 97	0.319	do do
7.4	0.18	-1.13	do	z 97	0.326	do do
7.5	0.18	-1.14	U 1 x 1 x 0.090	z 97	0.328	2'-6" .091 - 1 1/2"

BRIDGING

Maximum spacing between rows of bridging

@ Top Chord: 14'-11" ==>
@ Bottom Chord: 24'-5 1/4" ==>

2 Row(s) Minimum
4 Row(s) Minimum

Laterals supports

Deck (36")

Acc. to the code

POSITION

@ Top Chord

13'-3 5/8"
26'-7 3/8"


@ Bottom Chord

4'-8"
13'-3 5/8"
26'-7 3/8"
35'-3"

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J12 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD: 488.00 lb/ft

30KSP488/365

LIVE LOAD ...: 365.00 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

MOMENTS

AXIAL LOADS

<<< Top Chord >>>

< Bottom Chord >

	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft


DEFLECTION

Allowed deflection under live load	=	1.32 in (L/ 360)
Calculated deflection under service live load	=	1.25 in (L/ 379)
Joist inertia	=	636.86 in ⁴
Required camber	=	0.62 in

Project: COLUMBIA DISTRIBUTION A04061

JOIST CALCULATION ACCORDING TO SJI CODE

Mark.....: J13 (W-N MID SPAN, Symmetrical, Parallel, Free ends)



LOADING CONDITIONS

(THE SHOWN VALUES ARE REAL)

TOTAL LOAD ...: 440.75 lb/ft

30K10

LIVE LOAD ... : 319.50 lb/ft

END MOMENTS [ft-kip] & AXIAL LOADS [kips]

	MOMENTS		AXIAL LOADS			
	---L---	---R---	<<< Top Chord >>>		< Bottom Chord >	
	---L---	---R---	---L---	---R---	---L---	---R---
(Q) Wind or Seism (case 1)...	0.00	0.00	-11.00	11.00	0.00	0.00
(case 2)...	0.00	0.00	11.00	-11.00	0.00	0.00
(L) Live Load.....	0.00	0.00	0.00	0.00	0.00	0.00
(D) Dead Load.....	0.00	0.00	0.00	0.00	0.00	0.00

Weld Plate required Y/N.....: Yes

Imposed Rows of Bridging Y/N.: No

Bearing Depth... [in]: at left.: 2 1/2"

at right: 2 1/2"

UPLIFT

Net uplift uniform load : 120.00 lb/ft

DEFLECTION

Allowed deflection under live load	=	1.31 in (L/ 360)
Calculated deflection under service live load	=	1.26 in (L/ 375)
Joist inertia	=	545.35 in ⁴
Required camber	=	0.62 in



Mark: J13

Project: COLUMBIA DISTRIBUTION A04061

12/01/00

19:47:29

v3.6 11/29/00

Fabrication code unless noted

-LL = 2 angles short legs back to back,

BL = 2 angles welded in box,

BR = Round bar

-U = 1 U profile,

UU = 2 U profiles one inside the other, -CL = Crimped angle

Value of the forces reduced by 25% when there are some wind loads

Projets no.: A04061

Designer: Philippe Theriault

Shop: Canam Sunnyside [Production]

448 (75.98) / 481 (80.98)