

## working for clean rivers

SE Claybourne Street at SE 135<sup>th</sup> Avenue Sanitary Sewer Extension Council Item 819

Portland City Council | August 28, 2019

ENVIRONMENTAL SERVICES
CITY OF PORTLAND

NICK FISH, COMMISSIONER MICHAEL JORDAN, DIRECTOR

Joe Dvorak, P.E., Principal Engineer Raechel Frogner, Project Manager







### **Sewer Extensions for High Risk Septic**


- Ensures wastewater system services to the whole community
- Provides municipal sewer service to developed properties that currently use onsite disposal systems
- Ensures that properties have viable access to municipal sewer service in the event that their onsite systems fail
- Protects groundwater, as well as creeks and streams like nearby Johnson Creek



#### **Project Overview**

# SE Claybourne Sanitary Sewer Extension


- ~4,100 feet of new 8" diameter mainline pipe
- ~2,100 feet of new 6" diameter service lateral
- Provide municipal sewer service to 80 developed properties that currently use onsite disposal systems





### **Project Basis**

- Area with septic systems that have either failed or are at risk of failure
  - Threat to public health, watershed health, and groundwater adjacent to Johnson Creek
  - Small lot sizes limit area for replacement if existing system fails
  - ~50% of the properties
    have a public sewer line
    physically available within
    300 feet





#### **Connecting to the Public Sewer System**


#### **Mandatory Sewer Connection**

- Residents are required to connect within 3 years of project completion or upon failure of current onsite disposal system
- Fees are due to the City upon connection
- Financial assistance programs and deferral options are available



### **Public Outreach & Impacts**

- Extensive outreach conducted via mailings, web, email, and social media
- Community workshops and on-site tabling events
- Outreach materials translated and workshops conducted in English and Russian
- Extensive outreach conducted directly with affected property owners



### **Engineer's Estimate & Schedule**

#### Engineer's Estimate:

- \$3,148,000
- High Confidence Level

#### Advertise Project:

October 2019

#### **Begin Construction:**

Spring 2020

#### **Construction Duration:**

Spring 2020 through Spring 2021





### **Questions?**



Thank you.

