

# RESIDENTIAL INFILL PROJECT – PART 2

Bringing Portland Into Compliance with State Legislative Mandates for Middle Housing

**Morgan Tracy** 

Project Manager

**Shannon Buono** 

Senior Planner

**Sandra Wood** 

**Principal Planner** 

JP McNeil

City Planner



#### PSC RIP 2 Work Session #1

#### **PSC Potential Amendments (part 1)**

- 1. Remove or alter the wildfire risk in the proposed 'z' overlay
- 2. Create option for two detached units that can be divided using SB458
- 3. Modify the ADU codes regardless of fee-simple option

#### 1. Remove or alter the wildfire risk

• House Bill 2001 – requires cities to allow duplexes on *all lots*, and other middle housing (triplexes, fourplexes, cottage clusters, attached houses) in *most areas* by June 30, 2022


OAR 660-046-0010: Cities must adopt comprehensive plans (inventories, policies, and implementing measures) to reduce risk to people and property from natural hazards. Such protective measures adopted pursuant to Goal 7 apply to Middle Housing, including, but not limited to, restrictions on use, density, and occupancy.



#### **RIP Zones**








#### Wildfire Risk (2000)

R10/R20

R2.5, R5, R7

Wildfire Risk





## **PSC Objectives**

- Increase total lots eligible for middle housing (beyond duplexes)
- Better address patterns of segregation
- Not add more RIP1 (R2.5, R5 and R7) lots to 'z' overlay



#### **Options – within compliance timeframe**

- a) Retain staff proposal include current wildfire risk map No revisions required
- b) Retain now, update with state wildfire maps post adoption No revisions now, more precautionary approach
- c) Don't apply wildfire risk in R2.5-R7 zones
  Requires some mapping work
  Need rationale for distinguishing between zones



#### **Options – likely to delay project**

- d) Remove wildfire risk, restrict R10/R20 to duplexes and triplexes Requires infrastructure planning work, analysis and mapping
- e) Remove wildfire risk from 'z'
  Requires infrastructure planning work, analysis and mapping
- f) Remove now, apply statewide wildfire mapping post adoption Requires infrastructure planning work, analysis and mapping Creates issues for R10/R20 like RIP1 lots are facing now
- g) Use modified wildfire data inputs

  Need to research and develop data/mapping methodology



# Discussion



## 2. Create option for two detached units

- **Senate Bill 458** requires cities to allow proposals for middle housing to be divided into separate lots through an expedited land division process.
- House Bill 2001 middle housing includes duplexes, triplexes, fourplexes, attached houses and cottage clusters.
  - A city may define a Duplex to include two detached dwelling units on a Lot or Parcel [OAR 660-046-0020]
  - A city is not required to set a minimum number of dwelling units in a Cottage Cluster, but if it chooses to, it may require a minimum of three, four, or five dwelling units [OAR 660-046-0205]



## **PSC Objectives**

- Increase homeownership through fee simple expedited land division (SB458)
- Increase flexible development and site layout options
- Retain existing houses
- Allow 2nd unit to be larger than an ADU, less limited by existing house size



#### **Options – within compliance timeframe**

- a) Detached duplex (staff preference)
  - Need revised standards to address two primary structures.
  - Could have unintended consequences for other parts of code
- b) Two-unit cottage cluster
  - Uses proposed cottage cluster standards
  - Would be ineligible on 'z' zoned lots
  - Clearer distinction between attached/detached housing types



## **Options – likely to delay project**

c) Divide off an ADU

Ineligible under SB458


Requires creation of new land division code

Creates possible conflict with SB1051




#### Comparing Options – existing house


a. Detached duplex



b. Cottage Cluster



c. ADU






## Comparing Options – small existing house


a. Detached duplex



b. Cottage Cluster



c. ADU





#### Considerations

- Should there be added/different development standards?
- Should this be limited to existing home sites?
- Should this be limited to **smaller** (<1,100 sf) existing homes?
- Should there be an affordability requirement?



# Discussion



#### 3. Modify ADU codes to be more flexible

#### Senate Bill 1051 –

- A city shall allow the development of at least one accessory dwelling unit for each detached single-family dwelling, subject to reasonable regulations relating to siting and design.
- "accessory dwelling unit" means an interior, attached or detached residential structure that is used in connection with or that is accessory to a single-family dwelling.



## **PSC Objectives**

- Increase flexible development and site layout options
- Retain existing houses
- Allow ADU to be at least as large as the house, or up to 800 sq ft
- Allow smaller homes same development allowances as larger homes



#### **Options**

- a) Leave ADU program intact, rely on flexibility from item #2
  - Maintains current "accessory" relationship
  - Already well known and understood
  - Prior options better address the desire for larger second unit
  - Keeps a clearer distinction between ADUs and cottage clusters



#### **Options – building coverage**

- b) Change building coverage limits by either:
  - i) Remove 15% building coverage standard for ADUs only
    - Counter to the accessory structures project principle of treating accessory buildings (e.g. sheds, garages, ADUs) similarly
  - ii) Remove 15% coverage limit for all accessory structures
    - Would allow many detached unpermitted accessory structures
    - Can lead to more stormwater runoff issues
    - Can lead to reduced contiguous open area



#### **Options – ADU size**

- c) Allow ADUs to be larger by either:
  - i) Allow any ADU be as large or larger than a house, up to 800 sf
    - When the unit is larger, how is it "accessory"
    - Inconsistent with 2016 Accessory Structures Project
  - ii) Allow any ADU to be up to 99% of house size up to 800 sf
    - Still retains an element of being "accessory"
    - More consistent with 2016 Accessory Structures Project



# Discussion



#### **Next Time (January 25<sup>th</sup> at 5:00pm)**

- Overview of the SB458 land division process
- Review and discuss remaining PSC potential amendments
- Staff's technical amendment Q&A