



### City of Portland, Oregon

### **Bureau of Development Services**

#### **Land Use Services**

FROM CONCEPT TO CONSTRUCTION

Dan Saltzman, Commissioner Paul L. Scarlett, Director Phone: (503) 823-7300 Fax: (503) 823-5630 TTY: (503) 823-6868 www.portlandoregon.gov/bds

**Date:** May 10, 2016

**To:** Interested Person

**From:** Diane Hale, Land Use Services

503-823-7705 / Diane.Hale@portlandoregon.gov

# NOTICE OF A TYPE IX DECISION ON A PROPOSAL IN YOUR NEIGHBORHOOD

The Bureau of Development Services has approved a proposal in your neighborhood. The mailed copy of this document is only a summary of the decision.

The reasons for the decision are included in the version located on the BDS website <a href="http://www.portlandonline.com/bds/index.cfm?c=46429">http://www.portlandonline.com/bds/index.cfm?c=46429</a>. Click on the District Coalition then scroll to the relevant Neighborhood, and case number. If you disagree with the decision, you can appeal. Information on how to do so is included at the end of this decision.

CASE FILE NUMBER: LU 15-282532 LDP

#### GENERAL INFORMATION

**Applicant:** Sarah Radelet, Strata Land Use Planning

Po Box 90833 / Portland, OR 97290 / (503) 320-0273

**Owner:** Structure Redevelopment LLC

Po Box 3026 / Clackamas, OR 97015-3026

**Site Address:** 5117 SE CORA ST

Legal Description: BLOCK 2 LOT 16, IVANHOE

Tax Account No.: R191368

**State ID No.:** 1S2E07DC 16400

**Quarter Section:** 3436

**Neighborhood:** Creston-Kenilworth, contact Zachary Smith at 503-866-8575.

**Business District:** None

**District Coalition:** Southeast Uplift, contact Leah Fisher at 503-232-0010.

**Zoning:** R2 (Multi Family Residential 2,000 square feet)

**Case Type:** LDP (Land Division Partition)

**Procedure:** Type Ix, an administrative decision with appeal to the Oregon Land

Use Board of Appeals (LUBA).

#### Proposal:

The applicant is proposing a 2-parcel partition for attached housing for this 5,000 square foot lot. The existing house on the site was recently removed. Parcels 1 and 2 will be ~2,500 square feet each. Off-street parking is proposed for each house. There are no trees on the site.

This partition is reviewed through a Type 1x land use review because: (1) the site is in a residential zone; (2) fewer than four lots are proposed; (3) none of the lots, utilities, or services are proposed within a Potential Landslide Hazard or Flood Hazard Area, and; (4) no

other concurrent land use reviews (such as an Adjustment, Design Review, or Environmental Review) are requested or required (see 33.660.110).

For purposes of State Law, this land division is considered a partition. To partition land is to divide an area or tract of land into two or three parcels within a calendar year (See ORS 92.010). ORS 92.010 defines "parcel" as a single unit of land created by a partition of land. The applicant's proposal is to create 2 units of land (2 parcels). Therefore this land division is considered a partition.

#### Relevant Approval Criteria:

In order to be approved, this proposal must comply with the approval criteria of Title 33. The relevant approval criteria found in Section 33.660.120, Approval Criteria for Land Divisions in Open Space and Residential Zones.

#### **FACTS**

**Site and Vicinity:** This  $\sim 5,000$  square foot lot is an interior lot that is currently vacant. The existing house on the site was recently removed. The site is generally surrounded by single-family zoning and development. There is a small pocket of commercial development at the intersection of SE Holgate and  $52^{nd}$  to the south, and higher density commercial/residential development along SE Foster Road to the northeast.

#### Infrastructure:

- **Streets** The site has approximately 49.74 feet of frontage on SE Cora Street. At this location, SE Cora Street is classified as a Local Service Street for all modes. The frontage is improved with an approximately 3-ft wide sidewalk with about 12-ft from the face of the curb to the property line. An alley abuts the site to the north. Tri-Met provides transit service approximately 200 feet from the site at SE 52nd Avenue via Bus 71.
- Water Service There is an existing 8-inch CI water main in SE Cora Street.
- **Sanitary Service** There is an existing 30-inch CSP public combination sewer line in SE Cora Street.
- **Stormwater Disposal** There is no public storm-only sewer currently available to this property.

**Zoning:** The R2 zone allows multi-dwelling residential development up to a maximum density of one unit per 2,000 square feet of site area, and requires a minimum density of one unit per 2,500 square feet of site area. Newly created lots in the R2 zone must be at least 4,000 square feet in area for multi-dwelling development, 1,600 square feet for development with attached or detached houses, and 2,000 square feet for development with duplexes. Minimum lot width and depth standards may apply.

Land Use History: City records indicate there are no prior land use reviews for this site.

**Agency Review:** Several Bureaus have responded to this proposal and relevant comments are addressed under the applicable approval criteria. Exhibits "E" contain the complete responses.

**Neighborhood Review:** A Notice of Proposal in Your Neighborhood was mailed on **February 18, 2016**. One written response has been received from a notified property owner in response to the proposal (Ex. F.1). The comment included questions about the lot confirmation procedure that took place at this site in 2015, and the requirements to preserve trees. The lot to the west contained trees, but was created through a lot confirmation procedure in 2015 (PR 15-235400), therefore the existing trees on that lot are not subject to the tree preservation requirements for land divisions (PZC 33.630).

#### **ZONING CODE APPROVAL CRITERIA**

APPROVAL CRITERIA FOR LAND DIVISIONS IN OPEN SPACE AND RESIDENTIAL ZONES

33.660.120 The Preliminary Plan for a land division will be approved if the review body finds that the applicant has shown that all of the following approval criteria have been met.

Due to the specific location of this site, and the nature of the proposal, some of the criteria are not applicable. The following table summarizes the criteria that are not applicable. Applicable criteria are addressed below the table.

Criterion	Code Chapter/Section	Findings: Not applicable because:
	and Topic	
В	33.630 – Tree Preservation	No trees in excess of 6 inches in diameter are located fully or partially on the site, or the trees are nuisance species or exempt due to poor condition.
С	33.631 - Flood Hazard Area	The site is not within the flood hazard area.
D	33.632 - Potential Landslide Hazard Area	The site is not within the potential landslide hazard area.
E	33.633 - Phased Land Division or Staged Final Plat	Not applicable. These standards only apply to land divisions in the RF through R2.5 zones.
F	33.634 - Recreation Area	Not applicable. The minimum required density is less than 40 units.
Н	33.636 - Tracts and Easements	No tracts or easements have been proposed or will be required.
I	33.639 - Solar Access	The proposed development is for something other than single-dwelling detached homes.
J	33.640 - Streams, Springs, and Seeps	No streams, springs, or seeps are evident on the site outside of environmental zones.
L	33.654.110.B.2 - Dead end streets	No dead end streets are proposed.
	33.654.110.B.3 - Pedestrian connections in the I zones	The site is not located within an I zone.
	33.654.110.B.4 - Alleys in all zones	No alleys are proposed or required
	33.654.120.C.3.c - Turnarounds	No turnarounds are proposed or required
	33.654.120.D - Common Greens	No common greens are proposed or required
	33.654.120.E - Pedestrian Connections	There are no pedestrian connections proposed or required
	33.654.120.F - Alleys	No alleys are proposed or required
	33.654.120.G - Shared Courts	No shared courts are proposed or required
	33.654.130.B - Existing public dead-end streets and pedestrian connections	No public dead-end streets or pedestrian connections exist that must be extended onto the site.
	33.654.130.C - Future extension of dead-end streets and pedestrian connections	No dead-end street or pedestrian connections are proposed or required.
	33.654.130.D - Partial rights-of-way	No partial public streets are proposed or required.

#### **Applicable Approval Criteria are:**

### A. Lots. The standards and approval criteria of Chapters 33.605 through 33.612 must be met.

**Findings:** Chapter 33.612 contains the density and lot dimension requirements applicable in the R3 through IR zones. The applicant is proposing 2 single family attached housing parcels.

Single-dwelling or duplex development is proposed for some or the entire site, therefore the proposed lots must meet minimum density and not exceed the maximum density stated in Table 120-3. Maximum density in the R2 zone is one unit per 2,000 square feet and the minimum density is one unit per 2,500 square feet. The total site area shown on the applicant's survey is 4,972 square feet. The site has a minimum required density of 2 units and a maximum density of 2 units.

The lot dimensions required and proposed are shown in the following table:

R2	Minimum lot area (square feet)	Minimum lot width (feet)	Minimum lot depth (feet)	Minimum front lot line (feet)
Attached Houses	1,600	15	none	15
Parcel 1	2,486	24.87	100	24.87
Parcel 2	2,486	24.87	100	24.87

<sup>\*</sup> Width is measured from the midpoints of opposite lot lines.

Because the parcels only meet the standards for attached houses, a condition is required to restrict the housing type. The findings above show that the applicable density and lot dimension standards are met. Therefore this criterion is met.

# G. Clearing, Grading and Land Suitability. The approval criteria of Chapter 33.635, Clearing, Grading and Land Suitability must be met.

#### Findings:

#### Clearing and Grading

The regulations of Chapter 33.635 ensure that the proposed clearing and grading is reasonable given the infrastructure needs, site conditions, tree preservation requirements, and limit the impacts of erosion and sedimentation to help protect water quality and aquatic habitat.

In this case the site is primarily flat, and is not located within the Potential Landslide Hazard Area. Therefore, no significant clearing or grading will be required on the site to make the new lots developable. In addition, there are no trees required to be preserved in the areas where new development on the site is anticipated. This criterion is met.

#### Land Suitability

The site was in residential use until the house was demolished, and there is no record of any other use in the past. As indicated above, the site is relatively flat and contains no known geological hazards. Therefore, there are no anticipated land suitability issues and the new lots can be considered suitable for new development. This criterion is met.

# K. Transportation impacts. The approval criteria of Chapter 33.641, Transportation Impacts, must be met; and,

**Findings:** The transportation system must be capable of safely supporting the proposed development in addition to the existing uses in the area. The Development Review Section of the Portland Bureau of Transportation has reviewed the application for its potential impacts regarding the public right-of-way, traffic impacts and conformance with adopted policies, street designations, and for potential impacts upon transportation services.

PBOT has provided the following findings (see Exhibit E.2):

#### Street Capacity and Levels of Service

The proposal will result in a net increase of 1 single-family residence. This residence can be expected to generate 10 daily vehicle trips with 1 trip occurring in each of the AM and PM Peak Hours. This small increase in peak hour vehicles will not have significant impact on intersection levels of service or street capacity. No mitigation is needed.

#### Vehicle Access/Loading

The new lots will have a driveway to provide access to parking and loading.

#### On-Street Parking Impacts

The new lots will have at least one on-site parking space with an additional space between the garage and the front property line. Impacts to the on-street parking supply should be minimal.

#### Availability of Transit

Tri Met Bus Line #9 is available 1/3 mile away from the site at SE Powell and SE 52nd.

#### Neighborhood Impacts

The site is being developed with new attached single-family residences in compliance with the existing R2 zoning. In addition, standard frontage improvements including sidewalks will reduce the potential for conflicts between pedestrians and vehicles.

#### Safety for All Modes

Sidewalks along both sides of the area streets provide adequate pedestrian facilities. Give the low vehicle speeds and volumes on SE Cora, cyclists can safely share the roadway.

PBOT has reviewed and concurs with the information supplied and available evidence. No mitigation is necessary for the transportation system to be capable of safely supporting the proposed development in addition to the existing uses in the area. These criteria are met.

# L. Services and utilities. The regulations and criteria of Chapters 33.651 through 33.654, which address services and utilities, must be met.

**Findings:** Chapters 33.651 through 33.654 address water service standards, sanitary sewer disposal standards, stormwater management, utilities and rights of way. The criteria and standards are met as shown in the following table:

#### **33.651 Water Service standard** – See Exhibit E.3 for detailed bureau comments.

The Water Bureau has indicated that service is available to the site, as noted on page 2 of this report.

For the proposed parcels 1 and 2, the proposed locations for the water services are too close to the proposed sewer laterals - State of Oregon OAR 333 Rules apply for a minimum of 5' skin to skin horizontal spacing between water service lines and all sanitary laterals in the public right of way. Prior to final plat approval, a supplemental plan will need to be submitted showing the water services located a minimum of 5 feet from the sewer laterals.

With the condition noted above the water service standards have been verified.

#### **33.652 Sanitary Sewer Disposal Service standards** – See Exhibit E.1 for detailed comments.

The Bureau of Environmental Services has indicated that service is available to the site, as noted on page 2 of this report. The sanitary sewer service standards of 33.652 have been verified.

#### 33.653.020 & .030 Stormwater Management criteria and standards - See Exhibits E.1

No stormwater tract is proposed or required. Therefore, criterion A is not applicable.

The applicant has proposed the following stormwater management methods:

• **Parcels 1 and 2:** Stormwater from these lots will be directed to individual drywells that will treat the water and slowly infiltrate it into the ground. Each of these lots has sufficient area for a stormwater facility that can be adequately sized and located to meet setback standards, and accommodate water from a reasonably-sized home. BES has indicated conceptual approval of the drywells.

The standards and criteria are met.

#### 33.654.110.B.1 Through streets and pedestrian connections

Generally, through streets should be provided no more than 530 feet apart and at least 200 feet apart. Pedestrian connections should be provided at least 330 feet apart. The site is located on an east/west connection and 100-ft west of the nearest north/south connection (SE 52nd Avenue).

For the reasons described above, this criterion is met.

#### 33.654.120.B & C Width & elements of the right-of-way - See Exhibit E.2 for bureau comment

In reviewing this land division, Portland Transportation relies on accepted civil and traffic engineering standards and specifications to determine if existing street improvements for motor vehicles, pedestrians and bicyclists can safely and efficiently serve the proposed new development.

At this location, SE Cora Street is classified as a Local Service Street for all modes. The frontage is improved with a ~3-ft wide sidewalk with ~12-ft from the face of the curb to the property line. Based on the zoning and Local Walkway classification, an 11-ft sidewalk corridor with a 4.5-6-0.5 configuration is required at this location.

The applicant appealed the requirement to reconstruct the sidewalk corridor to the Public Works Alternative Review Committee (PW #16-147848). The request was denied. The applicant will need to construct an 11-ft sidewalk corridor with a 4.5-6-0.5 configuration as a condition of building permit approvals.

Portland Transportation has not identified or been made aware of any factors related to this proposal that lead to a conclusion other than that one additional dwelling can be safely served by this existing street with sidewalk improvements without having any significant impact on the level of service provided.

With the conditions of approval described above, this criterion is met.

#### 33.654.130.A - Utilities (defined as telephone, cable, natural gas, electric, etc.)

Any easements that may be needed for private utilities that cannot be accommodated within the adjacent right-of-ways can be provided on the final plat. At this time no specific utility easements adjacent to the right-of-way have been identified as being necessary. Therefore, this criterion is met.

#### **DEVELOPMENT STANDARDS**

Development standards that are not relevant to the land division review, have not been addressed in the review, but will have to be met at the time that each of the proposed lots is developed.

**Existing development that will remain after the land division.** The site is currently vacant so the division of the property will not cause the structures to move out of conformance or further out of conformance with any development standard applicable in the R2 zone. Therefore, this land division proposal can meet the requirements of 33.700.015.

#### OTHER TECHNICAL REQUIREMENTS

Technical decisions have been made as part of this review process. These decisions have been made based on other City Titles, adopted technical manuals, and the technical expertise of appropriate service agencies. These related technical decisions are not considered land use actions. If future technical decisions result in changes that bring the project out of conformance with this land use decision, a new land use review may be required. The following is a summary of technical service standards applicable to this preliminary partition proposal.

Bureau	Code Authority and Topic		
Development Services/503-823-7300	Title 24 – Building Code, Flood plain		
www.portlandonline.com/bds	Title 10 – Erosion Control, Site Development		
	Administrative Rules for Private Rights-of-Way		
Environmental Services/503-823-7740	Title 17 – Sewer Improvements		
www.portlandonline.com/bes	2008 Stormwater Management Manual		
Fire Bureau/503-823-3700	Title 31 Policy B-1 – Emergency Access		
www.portlandonline.com/fire			
Transportation/503-823-5185	Title 17 – Public Right-of-Way Improvements		
www.portlandonline.com/transportation	Transportation System Plan		
Urban Forestry (Parks)/503-823-4489	Title 11 – Trees		
www.portlandonline.com/parks			
Water Bureau/503-823-7404	Title 21 – Water availability		
www.portlandonline.com/water			

As authorized in Section 33.800.070 of the Zoning Code conditions of approval related to these technical standards have been included in the Administrative Decision on this proposal.

• The applicant must meet the requirements of the Fire Bureau in regards to addressing requirements and fire apparatus access, including aerial access. These requirements are based on the technical standards of Title 31 and Fire Bureau Policy B-1.

#### CONCLUSIONS

The applicant has proposed a 2 parcel partition for attached housing, as shown on the attached preliminary plan (Exhibit C.1). As discussed in this report, the relevant standards and approval criteria have been met or can be met with conditions.

With conditions of approval that address these requirements this proposal can be approved.

#### ADMINISTRATIVE DECISION

**Approval** of a Preliminary Plan for a 2-parcel partition, that will result in 2 single dwelling parcels for attached housing, as illustrated with Exhibit C.1, subject to the following conditions:

#### A. The following must occur prior to Final Plat approval:

- 1. The applicant must meet the Water Bureau requirements to submit a supplemental plan showing water services that meet the separation standards of OAR 333, located a minimum of 5 feet from the sewer laterals.
- B. The following conditions are applicable to site preparation and the development of individual lots:
- 1. Parcels 1 and 2 must be developed with attached houses.

- 2. The applicant must reconstruct the sidewalk corridor to the satisfaction of the Bureau of Transportation. Note: Title 17 requires shared driveways for attached houses.
- 3. The applicant must meet the Fire Bureau requirements for addressing and aerial fire department access. Aerial access applies to buildings that exceed 30 feet in height from the fire access as measured to the bottom of the eave of the structure or the top of the parapet for a flat roof.

Staff Planner: Diane Hale

Decision rendered by: \_\_\_\_\_\_ on May 6, 2016

By authority of the Director\of the Bureau of Development Services

#### Decision mailed May 10, 2016

**About this Decision.** This land use decision is **not a permit** for development. A Final Plat must be completed and recorded before the proposed lots can be sold or developed. Permits may be required prior to any work. Contact the Development Services Center at 503-823-7310 for information about permits.

**Procedural Information.** The application for this land use review was submitted on December 29, 2015, and was determined to be complete on February 10, 2016.

Zoning Code Section 33.700.080 states that Land Use Review applications are reviewed under the regulations in effect at the time the application was submitted, provided that the application is complete at the time of submittal, or complete within 180 days. Therefore this application was reviewed against the Zoning Code in effect on December 29, 2015.

ORS 227.178 states the City must issue a final decision on Land Use Review applications within 120-days of the application being deemed complete. The 120-day review period may be waived or extended at the request of the applicant. In this case, the applicant requested that the 120-day review period be extended by 15 days. Unless further extended by the applicant, **the 120 days will expire on June 24, 2016.** 

#### Some of the information contained in this report was provided by the applicant.

As required by Section 33.800.060 of the Portland Zoning Code, the burden of proof is on the applicant to show that the approval criteria are met. The Bureau of Development Services has independently reviewed the information submitted by the applicant and has included this information only where the Bureau of Development Services has determined the information satisfactorily demonstrates compliance with the applicable approval criteria. This report is the decision of the Bureau of Development Services with input from other City and public agencies.

**Conditions of Approval.** If approved, this project may be subject to a number of specific conditions, listed above. Compliance with the applicable conditions of approval must be documented in all related permit applications. Plans and drawings submitted during the permitting process must illustrate how applicable conditions of approval are met. Any project elements that are specifically required by conditions of approval must be shown on the plans, and labeled as such.

These conditions of approval run with the land, unless modified by future land use reviews. As used in the conditions, the term "applicant" includes the applicant for this land use review, any person undertaking development pursuant to this land use review, the proprietor of the use or development approved by this land use review, and the current owner and future owners of the property subject to this land use review.

**This decision, and any conditions associated with it, is final.** It may be appealed to the Oregon Land Use Board of Appeals (LUBA), within 21 days of the date the decision is mailed, as specified in the Oregon Revised Statute (ORS) 197.830. Among other things, ORS

197.830 requires that a petitioner at LUBA must have submitted written testimony during the comment period for this land use review. Contact LUBA at 775 Summer St NE Suite 330, Salem, OR 97301-1283 or phone 1-503-373-1265 for further information.

The file and all evidence on this case are available for your review by appointment only. Please call the Request Line at our office, 1900 SW Fourth Avenue, Suite 5000, phone 503-823-7617, to schedule an appointment. I can provide some information over the phone. Copies of all information in the file can be obtained for a fee equal to the cost of services. Additional information about the City of Portland, city bureaus, and a digital copy of the Portland Zoning Code is available on the internet at <a href="https://www.portlandonline.com">www.portlandonline.com</a>.


Recording the land division. The final land division plat must be submitted to the City within three years of the date of the City's final approval of the preliminary plan. This final plat must be recorded with the County Recorder and Assessors Office after it is signed by the Planning Director or delegate, the City Engineer, and the City Land Use Hearings Officer, and approved by the County Surveyor. The approved preliminary plan will expire unless a final plat is submitted within three years of the date of the City's approval of the preliminary plan.


#### **EXHIBITS**

#### NOT ATTACHED UNLESS INDICATED

- A. Applicant's Statement
  - 1. Applicant's original submittal and plans
  - 2. Applicant's response, February 10, 2016
  - 3. Stormwater Management Manual Simplified Approach Form, February 11, 2016
- B. Zoning Map (attached)
- C. Plans/Drawings:
  - 1. Proposed Plan Map (attached)
  - 2. Existing Conditions Plan
- D. Notification information:
  - 1. Mailing list
  - 2. Mailed notice
- E. Agency Responses:
  - 1. Bureau of Environmental Services
  - 2. Bureau of Transportation Engineering and Development Review
  - 3. Water Bureau
  - 4. Fire Bureau
  - 5. Site Development Review Section of BDS
  - 6. Life Safety Section of BDS
  - 7. Parks Urban Forestry
- F. Correspondence:
  - 1. Chip Horner, 5106 SE Boise St
- G. Other:
  - 1. Original LU Application
  - 2. Incomplete Letter
  - 3. Extension Request

The Bureau of Development Services is committed to providing equal access to information and hearings. Please notify us no less than five business days prior to the event if you need special accommodations. Call 503-823-7300 (TTY 503-823-6868).





CASE NO. 15 - 2825314 EXHIBIT (,)