U.S. Bancorp Tower, 111 SW 5th Avenue, Suite 2500 Portland, OR 97204 (503) 227-3251 FAX (503) 274-4681

MEMORANDUM

DATE: 4/23/2008 **TO**: Phil Sydnor

CC: file

FROM: Matt Johnson

RE: St Andrews Condos - LU 08-106691 AD PROJECT NO.:308040

On-Site

The stormwater management design approach for this project meets the requirements of the Stormwater Management Manual for pollution reduction and flow control. The area of the proposed flow through planters exceeds the minimum required to treat the redeveloped area. In addition to the planter areas, on-site tree credits further enhance the treatment goals. As stated in the Flow Through Planters section of the SWMM, flow control is achieved as part of the design and storage within the topsoil.

On-site infiltration would not be possible for this project and it is not recommended by BES. There are also some hillside stability concerns that would make on-site infiltration undesirable.

Off-Site

The volume and drainage course of the street will not be altered as part of this project. The stormwater runoff volume from the site will be reduced by the additional of 7 trees within the ROW.

(see attached Site Plan)



WILLIAM HAWKINS III
ARCHITECT - FAIA
1425 SOUTHWET 20TH AVENUE
PORTLAND, OREGON 97201
802497-9081
WILLIAMHAWKINSOQWEST-NET ST. ANDREWS CONDOMINIUMS SW 18TH AVE. & MILL ST. TERRACE GOOSE HOLLOW, PORTLAND, OREGON

SITE PLAN Sheet Number

Form SIM: Simplified Approach for Stormwater Management

The city has produced this form to assist with a quick and simple approach to manage stormwater on-site. Facilities sized with this form are presumed to comply with pollution reduction and flow control requirements. Stormwater disposal requirements per Section 1.4 must still be met.

New or Redeveloped Impervious Site Area 4385 Box 1 (do not include roof areas that will be infiltrated on-site with drywells or soakage trenches)

		Column 1	Co	lumn 2	Column 3	
INSTRUCTIONS		Impervious				
Enter square footage of new or redeveloped impervious site area in	Impervious Area	Area Manag	jed =			
Box 1 at the top of this form.	Reduction Technique	Facility Surf	face A	rea		100
	1) Eco-Roof / Roof Garden		sf			
Select impervious area reduction techniques from rows 1-3 to reduce the site's resulting stormwater management requirement. Tree credit can be calculated using the tree credit worksheet on the next page.	2) Contained Planter	100	sf			
	3) Tree Credit (See Next Page)	<u>438.5</u>				
Select desired stormwater	Note: Pervious Pavement areas d	o not need to t	be incl	uded in Bo	x 1	
management facilities from rows 4-10. In Column 1, enter the square footage of impervious area that will flow into each facility type.	Stormwater Management Facility	Impervious Area Managed		Sizing Factor	Facility Surface Area	Unit
4. Multiply each impervious area from	4) Infiltration Planter		sf x	0.06 =		sf
Column 1 by the corresponding sizing factor in Column 2, and enter the result in Column 3. This is the facility surface area needed to manage runoff from the impervious area.	5) Flow-Through Planter	4385	sf x	0.06 =	263	sf
	6) Vegetated Swale		sf x	0.09 =		sf
5. Total Column 1 (Rows 1-10) and enter the resulting "Impervious Area	7) Grassy Swale		sf x	0.12 =		sf
Managed" in Box 2.	8) Vegetated Filter Strip	0	sf x	0.2 =		sf
6. Subtract Box 2 from Box 1 and enter the result in Box 3. When this number reaches 0, stormwater pollution reduction and flow control	9) Vegetated Infil. Basin	0	sf x	0.09 =		sf
requirements have been met. Submi	10) Sand Filter		sf x	0.07 =		sf
this form with the application for permit.	For drywell and soakage trench sizing and design requirements,					
7. If Box 3 is greater than 0 square feet, add square footage or facilities to Column 1 and recalculate, or use additional facilities from Chapter 2.0 of the Stormwater Management Manual to manage stormwater from these remaining impervious surfaces.	see Section 2.9.		***************************************			
	Total Impervious Area Managed	4923.	5	Box 2		
	Box 1 - Box 2	-538-5	Ď	Box 3		

Form SIM (Page 2): Tree Credit Worksheet


See Tree Credits in Section 2.9 for more information regarding the use of trees to meet stormwater management requirements.

Alassa	E		Trees
IACM	EVELU	CC	11662

To receive stormwater management credit, new evergreen trees must be planted within 25 feet of ground-level impervious surfaces. New trees cannot be credited against rooftop surfaces. Minimum tree height (at the time of planting) to receive credit is 6 feet.

Enter number of new evergreen trees that meet qualification requirements in Box A	Box A
Auttiply Box A by 200 and enter result in Box B	Box B
New Deciduous Trees	
To receive stormwater management credit, new deciduous trees must be planted within 25 feet o surfaces. New trees cannot be credited against rooftop surfaces. Minimum tree caliper (at the till eceive credit is 2 inches.	
Enter number of new deciduous trees that meet qualification requirements in Box C	∫ 8 Box C
fultiply Box C by 100 and enter result in Box D	/800 Box D
Existing Tree Canopy	
To receive stormwater management credit, existing tree canopy must be preserved during and af Existing tree canopy must be within 25 feet of ground-level impervious surfaces. Existing trees canopy	
against rooftop surfaces. Minimum tree caliper to receive credit is 4 inches. No credit will be give ree canopy located within environmental zones. Tree canopy is measured around the tree's drip	
Enter square-footage of existing tree canopy that meets qualification requirements in Box E	Box E
fultiply Box E by 0.5 and enter the result in Box F	Box F
Total Tree Credit	
Add boxes B, D, and F and enter the result in Box G	<i>1800</i> Box G
For sites with less than 1,000 square-feet of new or redeveloped impervious area: The amount in Box G is to be entered as "Tree Credit" on Form SIM. ** Stop Here **	
or sites with more than 1,000 square-feet of new or redeveloped impervious area:	- [3 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 - 2 -
Multiply Box 1 of Form SIM by 0.1 and enter the result in Box H	438.5 Box H
Enter the lesser of Box G and H in Box I.	438,5 Box 1
his is the amount to be entered as "Tree Credit" on Form SIM. **Stop Here**	


Contained Planter



Section Not to Scale

St	ormwater Management Goals Achieved	Acceptable Sizing Methodologies	
√	Impervious Area Reduction	SIM	
√	Pollution Reduction	SIM	
√	Flow Control	SIM	
	Destination/ Disposal	. NA	
This facility is not classified as an Underground Injection Control structure (UIC).			
SIM=Simplified Approach, PRES= Presumptive Approach, PERF= Performance Approach			
Notes: 1) This facility is an impervious surface reduction technique. It may be placed over sidewalk, parking lot, flat roof, and plaza areas to reduce the effective impervious area.			

Contained Planter





Description: Contained planters are used for planting trees, shrubs, and ground cover to be placed over impervious surface. The planter may be a prefabricated pot of various dimensions or may be constructed in place and have an infinite variety of shapes and sizes. Contained planters accept precipitation only, not stormwater runoff. Planters are placed on impervious surfaces, such as sidewalks, plazas and rooftops. Drainage is allowed through the bottom of the planter.

Design Considerations: Plants shall be relatively self-sustaining, with little need for fertilizers or pesticides. Irrigation is optional, although plant viability must be maintained. Trees are encouraged and may receive added stormwater management credit on the tree credit section of Form SIM.

Design Requirements:

Soil Suitability: Contained planters are appropriate for all soil types, as they are placed over impervious surface. Topsoil shall be used within the top 12 to 18 inches of the facility.

Setbacks: Not applicable.

Planter Walls: Planter walls shall be made of stone, concrete, brick, clay, plastic, wood, or other stable material. Chemically treated wood that can leach out toxic chemicals and contaminate stormwater shall not be used.

Sizing: Contained planters are given stormwater management credit for the square-footage of impervious surface that they cover, at a 1 to 1 ratio.

Landscaping: Contained planters shall be planted to cover at least 50% of the planter surface.

Contained Planter

*Link to Planter Recommended Plants

Checklist of minimal information to be shown on the permit drawings:

(Additional information may be required on the drawings during permit review, depending on individual site conditions.)

- 1) Facility dimensions and setbacks from property lines and structures
- 2) Profile view of facility, including typical cross-sections with dimensions
- 3) Planter wall material specification
- 4) Growing medium specification
- 5) Landscaping plan

Inspection requirements and schedule: The following table shall be used to determine which stormwater facility components require City inspection, and when the inspection shall be requested:

Facility Component	Inspection Requirement		
Structural planter components			
Growing medium			
Plantings	Call for inspection		

Operations and Maintenance requirements: See Chapter 3.0.

Additional photos and drawings:

- * Link to contained planter photos
- * Link to contained planter drawings

^{*} Link to contained planter O&M form