City of Portland, Oregon

# Preconstruction Task 26

**Guaranteed Maximum Price (GMP)** 

May 4, 2020



### APPENDIX A – SCOPE OF WORK

MWH Constructors, Inc. ("CM/GC") will construct the Corrosion Control Improvements Project as shown and described in the following:

- Project Drawings as prepared by Stantec, Inc. and entitled: Volume 1 Construction Drawings, 90% Design Submittal - November 2019. A listing of project drawings is included as <u>Attachment A-1</u> to this Scope of Work.
- Technical Specifications as prepared by Stantec, Inc. and entitled: 90% Design Submittal Volumes 2, 3, and 4 - November 2019. A listing of technical specifications is included as <u>Attachment A-2</u> to this Scope of Work.
- Request for Information (RFI) numbers 1 thru 12 included as Attachment A-3 to this Scope of Work.
- Items numbers 2 thru 46 excluding item 5 on the 90% Design Clarifications and Changes Log dated 2/25/2020 included as Attachment A-4 to this Scope of Work.

Construction of the Corrosion Control Improvements Project will include twenty-one subcontract work packages (i.e. S-Packages), four equipment procurement packages (i.e. P-Packages), and one self-perform package (i.e. M-Package). A description of each S-Package, P-Package, and M-Package is provided below.

CM/GC's scope of work is subject to the clarifications and exceptions to the requirements of the Project Drawings and Technical Specifications noted in this Scope of Work.

#### 1.0 SUBCONTRACT WORK PACKAGES (S-PACKAGES)

#### Package S-1 - Site Conditions Survey

This bid package generally includes the work described in Specification 02 22 00 (Site Conditions Survey). The following clarifications and exceptions apply:

- It is anticipated that 100% of the work included in the S-1 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Videos documenting existing site conditions will be provided on compact disc or thumb drive. Videos will not be provided on VHS tape.

#### Package S-1A - Survey

This bid package generally includes surveying services to provide verification (i.e. spot checking) of work completed by others. The following clarifications and exceptions apply:

It is anticipated that 100% of the work included in the S-1A bid package will be completed by a firm(s) that
has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned
Business, a Women-Owned Business, or an Emerging Small Business.

 Construction surveying will be provided by Portland Water Bureau. The scope of services provided by the S-1A Subcontractor will be limited to spot checking survey work completed by others.

#### Package S-2 - Site Preparation

This bid package generally includes the work described in Specification 31 10 00 (Site Preparation). This package also generally includes the work shown on the "Erosion and Sediment Control" drawings. The following clarifications and exceptions apply:

- It is anticipated that <u>75%</u> of the work included in the S-2 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Modifications to the Stantec Erosion and Sediment Control drawings, as submitted to Portland Water Bureau
  on December 13, 2019 and included as <u>Attachment A-12</u>, shall govern over the Stantec Erosion and
  Sediment Control drawings.

#### Package S-3C - Site Earthwork and Demolition

This bid package generally includes all work shown on Drawing C-3 (Grading and Drainage Plan). The following clarifications and exceptions apply:

- It is anticipated that <u>75%</u> of the work included in the S-3C bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Temporary chain link fencing will be provided to maintain security along the eastern perimeter of the existing
  Lusted Hill Facility until the permanent fencing is installed. Approximate location of the temporary fencing is
  shown on <u>Attachment A-5</u> to this Scope of Work.

#### Package S-3D – Utility Water Pump Station Earthwork

This bid package generally includes all dewatering, shoring, excavation, and backfill associated with the Utility Water Pump Station. The following clarifications and exceptions apply:

- It is anticipated that <u>10%</u> of the work included in the S-3D bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- A temporary dewatering system will be provided during construction to address the perched groundwater identified in the geotechnical report (i.e. the elevation of the bottom of the utility water pump station is believed to be above the elevation of the groundwater table).
- Collected groundwater will be settled in an on-site Baker tank and discharged into the site stormwater system.
- The temporary dewatering system is expected to generate a limited amount of perched water. Once settled
  in the Baker tank, collected groundwater will be metered (pumped) into the site stormwater system at a rate
  compatible with the capacity of the stormwater system.

#### Package S-3E - Access Road and Staging Area

This bid package generally includes improving the existing emergency access road and constructing a staging and storage area. The following clarifications and exceptions apply:

- It is anticipated that <u>75%</u> of the work included in the S-3E bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Includes \$25,000 of road improvements to the existing roadway (private drive) at Diack's pond.

#### Package S-4 – Utility Water Pump Station Concrete

This bid package generally includes construction of certain cast-in-place concrete structures as shown on the Structural-series drawings and subject to the limits of work identified on the Concrete Key Map (<u>Attachment A-6</u> to this Scope of Work). The following clarifications and exceptions apply:

- It is anticipated that 10% of the work included in the S-4 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Although not called for on the Drawings, Subcontractor will provide a fall protection system (e.g. net system) with the 4'x8' Bilco double leaf hatch.
- Although not called for on the Drawings, Subcontractor will provide a "safety climb system" with the aluminum ladder.
- At the Bureau's direction, MWH will remove the costs for the fall protection system and safety climb system and add the cost of a davit arm receiver.

#### Package S-5 - Site Concrete

This bid package generally includes construction of certain cast-in-place concrete structures as shown on the Structural-series drawings and subject to the limits of work identified on the Concrete Key Map (<u>Attachment A-6</u> to this Scope of Work). The following clarifications and exceptions apply:

 It is anticipated that <u>10%</u> of the work included in the S-5 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

#### Package S-8 – Removal and Disposal of Contaminated Material

This bid package generally includes the work detailed in Specification 02 61 00 (Removal & Disposal of Contaminated Materials). The following clarifications and exceptions apply:

- It is anticipated that 100% of the work included in the S-8 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Work under package S-8 is budgeted at \$10,000 for (2) taps on conduit 4 only.

#### Package S-9 – Pre-Engineered Metal Building and Pre-Engineered Metal Canopies (JH Kelly)

This bid package generally includes design, supply, and construction of the Pre-Engineered Metal Building (total of 1) and Pre-Engineered Metal Canopies (total of 3). The following clarifications and exceptions apply:

 It is anticipated that <u>5%</u> of the work included in the S-9 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

- CM/GC's GMP pricing includes award of this work to JH Kelly at a price of \$319,000.
  - CM/GC's GMP pricing includes \$300,981 for supply and installation of the pre-engineered metal building and pre-engineered metal canopies. The remaining \$18,019 (shop drawings) is included in Amendment 2 to the Pre-Construction Services agreement.
- CM/GC's GMP pricing for the S-9 bid package is based on the draft 90% design documents including the draft 90% Project Drawings listed in <u>Attachment A-10</u> and the draft 90% Technical Specifications listed in <u>Attachment A-11</u>.
- CM/GC's GMP pricing specifically includes changes made via Specification 01 33 17 Structural Design Criteria dated 11/18/19 and changes made via Drawings GS-1 – Structural Notes, Revision C dated 11/18/19.

#### Package S-10 - Tensile Membrane Structure

This bid package generally includes the work detailed in Specification 13 31 00 (Tensile Membrane Structure). The following clarifications and exceptions apply:

 It is anticipated that <u>5%</u> of the work included in the S-10 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

#### Package S-12 – Painting and Coatings

This bid package generally includes the work detailed in Specification 09 96 00 (Protective Coatings). The following clarifications and exceptions apply:

- It is anticipated that 100% of the work included in the S-12 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- CM/GC's GMP excludes painting and/or coating of plastic piping.

#### Package S-14 – Heating, Ventilating, and Air Conditioning (HVAC)

This bid package generally includes the work shown on the HVAC-series drawings and detailed in Division 23 of the Specifications. The following clarifications and exceptions apply:

 It is anticipated that <u>75%</u> of the work included in the S-14 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

#### Package S-15 - Electrical

This bid package generally includes the work shown on the Electrical-series drawings. The following clarifications and exceptions apply:

- It is anticipated that 10% of the work included in the S-15 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Electrical package S-15 is budgeted at \$2,056,269 per contract documents as modified by 90% Design Clarifications and Changes Log and attachments dated 2/25/2020.
- The standby generator (a.k.a. portable electrical generator) will be provided by Portland Water Bureau.

- Portland Water Bureau will operate the portable electrical generator during switchover from the existing power service to the new power service.
- GMP includes 4% contingency on S-15 & S-15A package for market risks associated with this scope. Unused amounts after successful negotiations with low bidder shall be returned to PWB.

#### Package S-15A – Instrumentation and Controls

This bid package generally includes the work shown on the Instrumentation-series drawings. The following clarifications and exceptions apply:

- It is anticipated that <u>5%</u> of the work included in the S-15A bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- Instrumentation and Controls package S-15A is budgeted at \$188,500. Any remaining or additionally needed funds when the S-15A package is awarded will be returned to or provided from project contingency.
- All programming modifications to the existing Lusted Hill Treatment Facility SCADA/HMI system will be provided by Portland Water Bureau.
- All screen modifications to the existing Lusted Hill Treatment Facility SCADA/HMI system will be provided by Portland Water Bureau.

#### Package S-16 - Utilities Piping

This bid package generally includes supply and installation of certain piping subject to the limits of work identified on the Piping Key Map (<u>Attachment A-7</u> to this Scope of Work). The following clarifications and exceptions apply:

 It is anticipated that 30% of the work included in the S-16 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

#### Package S-17 - Process Piping

This bid package generally includes supply and installation of certain piping subject to the limits of work identified on the Piping Key Map (Attachment A-7 to this Scope of Work). The following clarifications and exceptions apply:

- It is anticipated that <u>15%</u> of the work included in the S-17 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- For purposes of installing the diffusers within Conduits 2, 3, and 4, MWH will excavate (and backfill) the
  existing manways shown on Drawing C-8. Portland Water Bureau will remove and replace the manways
  (hatches) themselves.
- It is assumed that no obstructions exist within Conduits 2, 3, and 4 between the point of entry (i.e. existing manways) and the point of diffuser installation.
- For purposes of installing the diffusers within Conduits 2, 3, and 4, Portland Water Bureau will shut down, drain, and clean (if necessary) Conduits 2, 3, and 4. Contractor will perform work and contact spray work areas for disinfection. Following installation of the new diffusers, Portland Water Bureau will fill and place Conduits 2, 3, and 4 back into service.

- Installation of the diffusers will require a single shutdown of each Conduit 2, 3, and 4.
- This package includes a 60 ft receiving pit at the UWPS associated with the horizontal directional drilling (provided under package S-18 below).
- Package includes a 36' x 16' Bore pit at Lusted Road to launch HDD under conduit 3.
- Includes downed tree removal on slope below Lusted road that was not able to be removed as part of the early work.
- An owner-controlled allowance of \$850,000 has been included for the utility corridor work between STA 6+10 and 10+25 in package S-17. It is anticipated that a change order for the actual amount of the work will be processed for the actual price of the work when the design is complete.

#### Package S-18 - Horizontal Directional Drilling

This bid package generally includes supply and installation (via horizontal direction drilling) certain piping subject to the limits of work identified on the Piping Key Map (<u>Attachment A-7</u> to this Scope of Work). The following clarifications and exceptions apply:

- It is anticipated that <u>10%</u> of the work included in the S-18 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- The GMP pricing is predicated upon use of the horizontal directional drilling (HDD) technology as follows:
  - (1) 12" HDD from Station 6+10 to UW Valve Vault. This HDD excludes an outer casing.
  - Where outer casings are provided, grouting of the annular spacing is excluded. The annular space will be filled by the drilling mud.
- Use of the HDD technology is based on geotechnical borings provided showing uniform clay at bore elevation without obstructions or cobbles.

#### Package S-19 – AC Pavement and Base

This bid package generally includes the work detailed in Specification 32 11 13 (A.C. Pavement and Base). The following clarifications and exceptions apply:

 It is anticipated that <u>75%</u> of the work included in the S-19 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

#### Package S-20 - Chain Link Fencing

This bid package generally includes the work detailed in Specification 32 31 13 (Chain Link Fencing). The following clarifications and exceptions apply:

 It is anticipated that 100% of the work included in the S-20 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.

#### Package S-21 - Landscaping

This bid package generally includes the work shown on the Landscape-series drawings. The following clarifications and exceptions apply:

- It is anticipated that 100% of the work included in the S-21 bid package will be completed by a firm(s) that has been certified by the State of Oregon as a Disadvantaged Business Enterprise, a Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business.
- CM/GC's GMP pricing includes \$51,689 for the secondary fire safety zone referenced in Keynote 2 on Drawing
   I -1

#### 2.0 EQUIPMENT PROCUREMENT PACKAGES (P-Packages)

#### Package P-1 – Carbon Dioxide Feed System (TOMCO2)

This procurement package includes supply of the equipment detailed in Specification 41 35 60 (Carbon Dioxide Feed System). The following clarifications and exceptions apply:

- CM/GC's GMP pricing includes award of this work to TOMCO2 at a price of \$685,000. A copy of the TOMCO2 proposal is included as <u>Attachment A-8</u> to this Scope of Work.
- CM/GC's GMP pricing is predicated upon TOMCO and Portland Water Bureau's acceptance of the following payment terms for P-1:
  - 3% of purchase price upon submittal of shop drawings
  - 7% of purchase price upon engineer's approval of shop drawings
  - 15% of purchase price at 8 weeks into fabrication
  - 60% of purchase price upon delivery of equipment
  - 10% of purchase price upon successful installation
  - 5% of purchase price upon successful completion of commissioning and start-up
- CM/GC's GMP pricing for the P-1 bid package is based on the draft 90% design documents including the draft 90% Project Drawings listed in <u>Attachment A-10</u> and the draft 90% Technical Specifications listed in <u>Attachment A-11.</u>
- CM/GC's GMP pricing specifically includes changes made via Specification 01 33 17 Structural Design Criteria dated 11/18/19 and changes made via Drawings GS-1 – Structural Notes, Revision C dated 11/18/19.

#### Package P-2 - Pumps

This procurement package includes supply of the equipment detailed in Specification 43 22 93 (Submersible Sump Pumps) and Specification 43 24 03 (Submersible Deep Well Turbine Pumps).

#### Package P-3 – Chemical Feed System

This procurement package includes supply of the equipment detailed in Specification 43 23 02 (Horizontal ANSI End Suction Pumps).

#### Package P-4 – Soda Ash Storage and Feed System (Chemco Systems)

This procurement package includes supply of the equipment detailed in Specification 46 32 40 (Soda Ash Storage and Feed System). The following clarifications and exceptions apply:

 CM/GC's GMP pricing includes award of this work to Chemco Systems at a price of \$1,012,100. A copy of the Chemco Systems proposal is included as <u>Attachment A-9</u> to this Scope of Work.

- CM/GC's GMP pricing includes \$917,053 for supply of the soda ash storage and feed system. The remaining \$95,047 (shop drawings) is included in Amendment 1 & 2 to the Pre-Construction Services agreement.
- CM/GC's GMP pricing includes \$10,000 for design and supply of galvanized grating to function as an extended
  access platform working surface as depicted in the revised general arrangement plan P103019 REV01.pdf.
- CM/GC's GMP pricing includes \$4,800 for suppling a beam and manual hoist and trolley system for each silo.
   The structural beam will be finish painted and installed above head level while on top of the tank for each silo.
   The beam would be welded structurally integral to the silo and installed perpendicular to the safety railing at the top of the tank. The manual chain fall hoist & trolley system will have a capacity rating of 1,000lb.
- CM/GC's GMP pricing is predicated upon Chemco Systems and Portland Water Bureau's acceptance of the following payment terms for P-4:
  - 3% of purchase price upon submittal of shop drawings
  - 7% of purchase price upon engineer's approval of shop drawings
  - 15% of purchase price at 8 weeks into fabrication
  - 60% of purchase price upon delivery of equipment
  - 10% of purchase price upon successful installation
  - 5% of purchase price upon successful completion of commissioning and start-up
- CM/GC's GMP pricing for the P-4 bid package is based on the draft 90% design documents including the draft 90% Project Drawings listed in <u>Attachment A-10</u> and the draft 90% Technical Specifications listed in Attachment A-11.
- CM/GC's GMP pricing specifically includes changes made via Specification 01 33 17 Structural Design Criteria dated 11/18/19 and changes made via Drawings GS-1 – Structural Notes, Revision C dated 11/18/19.
- Chemco Systems warranty excludes on-site labor and repairs (i.e. defective equipment must be returned to Chemco Systems factory for repair and/or replacement).

#### 3.0 MWH SELF-PERFORM WORK

#### General Conditions Labor and Other Direct Costs

Provisions of labor and services required to execute the aforementioned work including the Specified General Conditions as detailed in <u>Attachment B-3</u> to Appendix B.

#### Package M-1 - Process Mechanical

This bid package generally includes supply and installation of certain piping subject to the limits of work identified on the Piping Key Map (<u>Attachment A-7</u> to this Scope of Work).

M-1 scope also includes \$8,000 (total) for CM/GC and PWB inspection travel costs of P-1 (Carbon Dioxide Feed System) and P-4 (Soda Ash Storage and Feed System) equipment during the fabrication process.

#### Commissioning and Start-up

Provisions of labor and services required to complete commissioning and start-up services as detailed in <u>Attachment</u> <u>B-4</u> to Appendix B (Guaranteed Maximum Price).

#### Digital Delivery Services

- Digital delivery services including:
  - 4D sequencing for facility construction schedule, cost, and operations review
    - Model 1 Based on current construction schedule and current 90% design models from Stantec
    - Model 2 Add cost/Earned Value Analysis to above model
    - Model 3 Simulated construction rehearsal. We propose to utilize the delivery and installation
      of the Soda Ash silos as demonstration of the spatial coordination clash detection.
  - Design model clash detection based on 90% design review
  - BIM for fabrication workflow
    - Create Level of Design (LOD) 350-400 3D BIM models
    - Export 2D shop drawings
    - Export fabrication-ready models
  - BIM for Asset Management workflow using mobile BIM applications (BIM 360)
    - Laser scan components of the existing Lusted Hill Facility
    - Convert as-built data to 3D BIM
    - Add asset information (tags, specs, etc.) provided by PWB (input into BIM 360)
    - Demonstrate Use of tools for accessing data in the field (including iPad and mixed reality for accessing model)
    - Optional draft a guideline for CMMS integration
  - BIM with VR "Walkthrough" using Unity for O&M example for new facility
    - Use above model to demonstrate use of VR Walkthrough to simulate work within the new preengineered metal building (i.e. within the new treatment building)
    - Demonstrate using a headset device e.g., Hololens
  - The digital delivery scope excludes all below ground/buried features of the work.

#### 4.0 ADDITIONAL CLARIFICATIONS and EXCLUSIONS

In addition to the package-specific clarifications and exclusions shown above, the following clarifications and exclusions apply:

- CM/GC is closely monitoring the changing circumstances surrounding the Coronavirus Disease ("COVID 19") to avoid losses, mitigate the impacts, and prepare for what is to come. CM/GC is currently assessing
  and evaluating the Project schedule, the supply chain for the Project, as well as the Project labor force. At this
  juncture, the ultimate impact resulting from the COVID-19 pandemic remains unknown. CM/GC reserves the
  right to submit for adjustment to completion deadlines and costs as a result of COVID-19.
- Subcontracted work for packages S-9 (Pre-Engineered Metal Building and Pre-Engineered Metal Canopies) and S-22 (Tree Removal) will be provided by the parties identified above.
- Process equipment for packages P-1 (Carbon Dioxide Feed System) and P-4 (Soda Ash Storage and Feed System) will be provided by the parties identified above.
- CM/GC will have free and clear access to easement and right-of-way to work. MWH understands the existing
  facility needs to remain in operation and will work with plant staff to guarantee plant staff have necessary
  access.
- CM/GC will have use of the existing emergency access roadway.
- No re-routing of utilities has been included unless specifically shown on the contract documents.

- CM/GC's submittals will be provided in electronic format only. Hard copies will not be required.
- CM/GC's Operation and Maintenance manuals (O&M manuals) will be provided in electronic format only.
   Hard copies will not be required.
- CM/GC will be provided a with a copy of the Masterworks database at project completion specifically including electronic copies of all submittals, RFIs, design clarifications, etc.
- 10. Where detailed schedules have been provided in the Specifications and/or Drawings (e.g. gate schedule, conduit schedule, I/O list, etc.) these detailed schedules shall govern over information shown elsewhere in the contract documents.
- Record drawings will not require a civil engineer's or professional land surveyor's signature and registration number
- Concrete basins and/or structures will not require disinfection.
- Revisions to specification 01 72 00 General Conditions are incorporated into contract per attachment A-10 (Pending final negotiations)
- CM/GC's Scope of Work excludes:
  - All third-party inspection fees
  - All special inspection fees
  - All on-site material testing fees.
  - Part-time and/or full-time on-site security guard. MWH will be responsible for maintaining site security in relation to existing security fence removal & temporary fencing throughout construction activities.
  - Application for, and securing of, all permits required for construction specifically including the land use permit, building permits (excluding trade permits), demolition permit, grading/fill permit, and Oregon Department of Environmental Quality 1200-C permit.
  - Changes made to the Project Drawings and Technical Specifications following issuance of the 90% document set (as detailed in Attachments A-1 and A-2).
  - The cost of electricity, natural gas, and water (potable and non-potable), which are to be provided by Owner at no cost to CM/GC.
  - All third-party utility hook-up fees and/or meter fees.
  - The cost of chemicals needed for commissioning and start-up activities.
  - All Stantec engineering fees specifically including Stantec engineering inspections and/or re-inspections.
  - All fees for Stantec engineering services during construction
  - Material escalation.
  - Hydraulic testing of the Utility Water Pump Station concrete structure.
  - Pigging of pipelines as called for in Part 3.2 of Specification 01 74 30
  - Provision of an Owner/Engineer trailer as called for in Specification 00 72 00
  - Provision of landline phone service.
  - Weekly wetting and sweeping of the entry drive, roadways, and all other streets and walkways affected by the Work and where adjacent to the work. Cleaning and sweeping will be provided as needed.
  - Fire Suppression System: Scope not defined (Carried in Owner Allowance)
  - Utility Corridor Work STA 6+10 to 10+25 (Carried in Owner Allowance)
    - This scope generally includes all work from STA 6+10 to STA 10+25 including but not limited to Lusted road closure, road crossing, road stabilization, road re-building, exposed

section of piping on downhill slope of Lusted road, and all pipe work associated with stations listed above.

#### Attachments to Appendix A

- A-1 List of 90% Project Drawings
- A-2 List of 90% Technical Specifications
- A-3 Request for Information Nos. 1 thru 12
- A-4 90% to 100% Change Log with attachments
  - Attachment A Cable and Conduit Schedule Revision NOT ATTACHED CONFIDENTIAL
  - Attachment B Erosion and Sedimentation Control Drawings ESC-1 through ESC-5 plotted 2/3/2020 NOT ATTACHED CONFIDENTIAL
  - Attachment C Security Plan Drawing E-53 & E-55 markups NOT ATTACHED CONFIDENTIAL
  - Attachment D Example Wiring Diagram dated 11/23/2009 NOT ATTACHED CONFIDENTIAL
  - Attachment E MCC Information (including pricing) from Schneider Electric printed 2/6/2020 NOT ATTACHED CONFIDENTIAL
  - Attachment F PWB Guidelines for Utility Protection dated October 2012 NOT ATTACHED REFERENCED ONLY
  - Attachment G Drawing E-7 revision NOT ATTACHED CONFIDENTIAL
  - Attachment H PWB Integrated Vegetation Management Plan dated November 2017 NOT ATTACHED CONFIDENTIAL
  - Attachment I Section 007316 Insurance Requirements revisions NOT ATTACHED CONFIDENTIAL
  - Attachment J Electrical Conduit Requirements e-mail from Jon Johnson dated 3/4/2020 including revised Specification 26 05 33 Table A NOT ATTACHED CONFIDENTIAL
- A-5 CM/GCs Site Layout Plan
- A-6 Concrete Key Map NOT ATTACHED CONFIDENTIAL
- A-7 Piping Key Map NOT ATTACHED CONFIDENTIAL
- A-8 TOMCO2 Proposal dated November 7, 2019 NOT ATTACHED CONFIDENTIAL
- A-9 Chemco Systems Proposal dated December 4, 2019 NOT ATTACHED CONFIDENTIAL
- A-10 Revisions to 007200 General Conditions NOT ATTACHED CONFIDENTIAL
- A-11 Risk Matrix

--- End of Appendix A ---

## APPENDIX B – GUARANTEED MAXIMUM PRICE

CM/GC's guaranteed maximum price is \$16,139,637 as detailed below:

Subcontracted Bid Packages		
S-1 – Site Conditions Survey		\$15,000
S-1A – Survey		\$15,000
S-2 – Site Preparation		\$337,469
S-3C – Site Earthwork and Demolition		\$368,283
S-3D - Utility Water Pump Station Earthwor	k	\$570,934
S-3E – Access Road and Staging Area		\$301,178
S-4 – Utility Water Pump Station Concrete		\$364,497
S-5 – Site Concrete		\$683,673
S-8 - Removal and Disposal of Contaminate	ed Materials	\$10,000
S-9 - Pre-Engineered Metal Building and Pr		\$300,981
S-10 – Tensile Membrane Structure		\$225,000
S-12 – Painting and Coatings		\$134,560
S-14 – HVAC		\$205,000
S-15 – Electrical		\$2,056,269
S-15A – Instrumentation and Controls		\$188,500
S-16 – Utilities Piping		\$395,967
S-17 – Process Piping		\$2,516,758
S-18 – Horizontal Directional Drilling		\$136,188
S-19 – AC Pavement and Base		\$158,030
S-20 - Chain Link Fencing		\$34,300
S-21 – Landscaping		\$237,295
Equipment Procurement Packages		
P-1 – Carbon Dioxide Feed System **		\$685,000
P-2 – Pumps		\$121,086
P-3 – Chemical Feed Systems		\$46,825
P-4 - Soda Ash Storage and Feed Systems	**	\$917,053
MWH Self-Perform Services		
General Conditions		\$1,481,369
M-1 - Self-Perform Process Mechanical		\$1,481,980
Commissioning and Start-up		\$100,751
Digital Delivery Services		\$30,000
	SUBTOTAL =	\$14,118,944
Contingency		\$494,163
CM/GC Fee (9.61% of Subtotal)		\$1,356,831
Payment and Performance Bonds		\$106,999
Oregon Corporate Tax (effective 1/1/2020)		\$62,700
,		
	GUARANTEED MAXIMUM PRICE =	\$16,139,637
Owner Controlled Allowance		\$1,850,000
		<b>A.3.65</b>
	ANTICIPATED CONTRACT VALUE =	\$17,989,637

<sup>\*\*</sup> indicates a portion of cost for this bid package is carried in Amendment 2 to the Pre-Construction Services Agreement

This Guaranteed Maximum Price (GMP) is predicated upon the following:

- 1 CM/GC's scope of work shall be as presented in Appendix A.
- 2 CM/GC's schedule shall be as presented in Appendix C.
- 3 Inclusion of the Oregon Corporate Tax (effective 1/1/2020).
- 4 Except for the four bid packages identified in Items 3 thru 6 above, pricing for the remaining bid packages are based on CM/GC's 90% estimate included as Attachment B-1.
- 5 Labor rates used in the CM/GC's 90% estimate reflect the higher of 1) Oregon's Bureau of Labor and Industries (BOLI) wage rates issued 7/1/19 and updated 10/1/19 or 2) and the Davis Bacon wage rate Building Decision #OR20190029 Modification 7 dated 11/14/19.
- 6 Inclusion of the Specified General Conditions costs identified in <u>Attachment B-2</u>.
- 7 Inclusion of the Commissioning & Start-up costs identified in <u>Attachment B-3</u>.

#### Attachments to Appendix B

- B-1 90% Estimates NOT ATTACHED CONFIDENTIAL
- B-2 General Conditions Estimate NOT ATTACHED CONFIDENTIAL
- B-3 Commissioning and Start-up Estimate NOT ATTACHED CONFIDENTIAL

--- End of Appendix B ---

## APPENDIX C – SCHEDULE

A copy of the CM/GC's baseline schedule is included as <u>Attachment C-1</u>. Contractual dates for this GMP shall be as follows:

- Substantial Completion February 28, 2022
- Final Completion April 30, 2022

This schedule and completion dates are predicated upon the following:

- CM/GC's scope of work shall be as detailed in Appendix A.
- CM/GC and Portland Water Bureau recognize that certain details regarding the status of 100% Drawings and Specifications as well as construction sequencing of the tie-ins to the three existing conduits (i.e. Conduit 4, Conduit 3, and Conduit 2) are not fully known at this time. CM/GC and Portland Water Bureau agree to work together to identify a mutually acceptable sequence of events that allows for completion of construction in accordance with the regulatory deadline date of April 30, 2022.
- Portland Water Bureau will provide permits as required to support the project schedule.

#### Attachments to Appendix C

C-1 90% Schedule (run date 4-May-20)

---- End of Appendix C ----

#### Attachment A-1 -List of 90% Project Drawings

<u>Drawing Number</u>	<u>Drawing Title</u>	Revision	<u>Date</u>
General			
G-1	Cover		44.40.0040
G-2	Location Map and Vicinity Map	C	11/19/2019
G-3	List of Drawings	С	11/18/2019
G-4	Standard Symbols	C	11/18/2019
G-5	Abbreviations	С	11/18/2019
G-6	Conduit Connections and UW Pump Process Flow Diagram	С	11/19/2019
G-7	Carbon Dioxide (CO2) System Process Flow Diagram	С	11/19/2019
G-8	Soda Ash and Ammonia Systems Process Flow Diagram	С	11/18/2019
G-9	Existing Utility Water Pump Station Process Flow Diagram	С	11/19/2019
G-10	Design Criteria	С	11/19/2019
G-11	Pipe and Material Schedule	С	11/18/2019
G-12	3D Model	С	11/18/2019
G-13	CWS Hydraulic Profile - I	С	11/19/2019
G-14	CWS Hydraulic Profile - II	С	11/19/2019
Erosion and Sediment Co	ontrol		
ESC-1	Notes - I	С	11/19/2019
ESC-2	Notes - II	С	11/19/2019
ESC-3	Site Plan	С	11/18/2019
ESC-4	Details - I	С	11/18/2019
ESC-5	Details - II	С	11/18/2019
Civil			
GC-1	Notes and Symbols	С	11/18/2019
GC-2	Standard Details - I	С	11/18/2019
GC-3	Standard Details - II	С	11/18/2019
GC-4	Standard Details - III	С	11/18/2019
GC-5	Standard Details - IV	С	11/18/2019
GC-6	Standard Details - V	С	11/18/2019
GC-7	Standard Details - VI	С	11/18/2019
GC-8	Standard Details VII	С	11/18/2019
C-1	Overall Site Plan and Pipeline Key Plan	С	11/18/2019
C-2	Horizontal Control and Paving Plan	С	11/18/2019
C-3	Grading and Drainage Plan	С	11/18/2019
C-4	Yard Piping Plan - I	С	11/18/2019
C-5	Chlorinated Water Supply Piping Plan and Profile	С	11/19/2019
C-5 C-6 C-7 C-8	Chemical Utility Trench Plan and Profile - I	С	11/19/2019
C-7	Chemical Utility Trench Plan and Profile - II	С	11/19/2019
C-8	Chemical Utility Trench Plan and Profile - III	С	11/19/2019
C-9	Enlarged Plans - I & II	C	11/18/2019
C-10	Enlarged Plans - III & IV	C	11/18/2019
C-11	Conduit Chemical Injection Vault Detail	C	11/18/2019
C-12	Utility Trench Cross Sections	C	11/18/2019
C-13	CWS Conduit Pipe Tap Details	С	11/19/2019
Instrumentation			
GI-1	Symbols and Abbreviation	С	11/18/2019
GI-2	Installation Details - I	С	11/18/2019
GI-3	Installation Details - II	С	11/18/2019
GI-4	Installation Details - III	С	11/18/2019

GI-5	Installation Details - IV	С	11/18/2019
GI-6	Installation Details - V	С	11/18/2019
GI-7	Installation Details - VI	С	11/18/2019
I-1	Conduit Connections	С	11/18/2019
I-2	CO2 Utility Water Pumps P&ID	С	11/18/2019
I-3	Soda Ash Utility Water Pumps P&ID	С	11/18/2019
I-4	Lusted Hill Carbon Dioxide Storage Tank P&ID	С	11/18/2019
I-5	Conduit 2 and 3 CO2 Feeder Panels P&ID	С	11/18/2019
I-6	Conduit 4 and Spare CO2 Feeder Panels P&ID	С	11/18/2019
1-7	Lusted Hill Soda Ash Silo 1 P&ID	С	11/18/2019
I-8	Lusted Hill Soda Ash Silo 2 P&ID	C	11/18/2019
1-9	Soda Ash Solution Pumps No. 1, 2, 3, 4, & 5 P&ID	С	11/18/2019
I-10	Existing Conduit 2 Chemical Feed P&ID	C	11/18/2019
I-11	Existing Conduit 3 & 4 Chemical Feed P&ID	C	11/18/2019
I-12	Power Monitor, ATS, & Generator P&ID	C	11/18/2019
	removiment, rive, a company range		11/10/2010
Landscape		_	
GI-1	Standard Details - I	С	11/18/2019
GL-2	Standard Details - II	С	11/18/2019
L-1	Tree Removal Plan - I	С	11/18/2019
L-2	Tree Removal Plan - II	С	11/18/2019
L-3	Mitigation Plan	С	11/18/2019
L-4	Seeding Plan	С	11/18/2019
Architectural			
GA-1	Legend and Assemblies	С	11/18/2019
GA-2	Door Types + Schedules and Opening Details	C	11/18/2019
GA-3	Details - I	C	11/18/2019
GA-4	Details - II	C	11/18/2019
GA-5	Details - III	C	11/18/2019
A-1	Code Plan & Building Data	C	11/18/2019
A-2	Enlarged Floor Plans - I	C	11/18/2019
A-3	Enlarged Floor Plans - II	C	11/18/2019
A-4	Roof Plan	C	11/18/2019
A-5	Elevations - I	C	11/18/2019
A-6	Elevations - II	C	11/18/2019
A-7	Sections - I	С	11/18/2019
Stuctural			
GS-1	Structural Notes - I	C	11/18/2019
GS-2	Structural Notes - II	С	11/18/2019
GS-3	Standard Details	С	11/18/2019
S-1	Overall Structure/Roof Pla	С	11/18/2019
S-2	Chemical Bldg & Canopy Foundation Plan	С	11/18/2019
S-3	North Walkway Plan & Sections	С	11/18/2019
S-4	Silo Foundation Plan	С	11/18/2019
S-5	Sections and Details - I	С	11/18/2019
S-6	Sections and Details - II	С	11/18/2019
S-7	Sections and Details - III	С	11/18/2019
S-8	Sections and Details - IV	C	11/18/2019
S-9	Valve Vault Plans	C	11/18/2019
S-10	Valve Vault Sections and Details - I	C	11/18/2019
S-11	Valve Vault Sections and Details - II	C	11/18/2019
S-12	Misc Foundation Plans and Details	C	11/18/2019
O IL	Allow I Communicate Figure Details	v	11/10/2013

Mechanical			
GM-1	Standard Details - I	С	11/18/2019
GM-2	Standard Details - II	С	11/18/2019
GM-3	Standard Details - III	С	11/18/2019
GM-4	Standard Details - IV	С	11/18/2019
GM-5	Standard Details - V	С	11/18/2019
GM-6	Standard Details - VI	С	11/18/2019
GM-7	Standard Details - VII	С	11/18/2019
M-1	Valve Vault and Pump Station Plans - I	С	11/18/2019
M-2	Valve Vault and Pump Station Plans - II	С	11/18/2019
M-3	Valve Vault and Pump Station Sections - I	С	11/18/2019
M-4	Soda Ash Silos Plans	С	11/18/2019
M-5	Soda Ash Silos Sections	С	11/18/2019
м-6	Chemical Building Lower Plan	С	11/18/2019
M-7	Chemical Building Upper Plan	С	11/18/2019
м-8	Chemical Building Sections - I	С	11/18/2019
м-9	Chemical Building Sections - II	С	11/18/2019
M-10	Chemical Building Sections - III	С	11/18/2019
M-11	Chemical Building Sections - IV	С	11/18/2019
M-12	Existing Chemical Building Plan	С	11/18/2019
HVAC			
GH-1	Symbols, Notes and Abbreviations	С	11/18/2019
GH-2	Standard Details - I	С	11/18/2019
GH-3	Equipment Schedules	С	11/18/2019
GH-4	Sequence of Operation	С	11/18/2019
H-1	Chemical Building Lower Plan	С	11/18/2019
H-2	Chemical Building Sections - I	С	11/18/2019
H-3	Chemical Building Sections - II	С	11/18/2019
Plumbing	0.11.00		44402040
GP-1	Symbols, Notes, and Abbreviation	C	11/18/2019
GP-2	Standard Details - I	C	11/18/2019
GP-3	Standard Details - II	C	11/18/2019
P-1	Chemical Building Lower Plan	C	11/18/2019
P-2	Isometric	С	11/18/2019
Electrical			
GE-1	General Legend - 1	0	11/18/2019
DE-1	Site Plan Demolition	C C	11/18/2019
E-1	Site Plan Demolition	C	11/18/2019
E-2	Trench Plan	C	11/18/2019
E-3	Utility Power Plan	C	11/18/2019
E-3	MCCA One-Line Diagram	C	
E-4	MCCB One-Line Diagram MCCB One-Line Diagram	C	11/18/2019 11/18/2019
E-6	MCCA & MCCB Elevation	C	11/18/2019
E-7	Enclosure Power Plan	C	11/18/2019
E-8	Enclosure Power Plan Enclosure Lighting Plan	C	11/18/2019
E-9	Enclosure Lighting Plan Enclosure Control Plan	C	11/18/2019
E-10			
E-10 E-11	Chemical Building Power Plan	C	11/18/2019
E-11	Chemical Building Lighting Plan	C C	11/18/2019
E-12 E-13	Chemical Building Control Plan		11/18/2019
	Soda Ash Silo Storage Power & Control Plan	C C	11/18/2019
E-14	Soda Ash Silo Storage Lighting Plan		11/18/2019
E-15	Soda Ash Silo Storage Elevation	С	11/18/2019

E-16	Utility Water Pump Vault Power Control Plan	С	11/18/2019
E-17	Utility Water Pump Vault Lighting Plan	С	11/18/2019
E-18	CO2 Tank Storage Power & Control Plan	С	11/18/2019
E-19	CO2 Tank Storage Lighting Plan	С	11/18/2019
E-20	Details - I	С	11/18/2019
E-21	Details - II	С	11/18/2019
E-22	Details - III	С	11/18/2019
E-23	Details - IV	С	11/18/2019
E-24	Panel Schedules	С	11/18/2019
E-25	Power Conduit Schedule	С	11/18/2019
E-26	Control Conduit Schedule - I	С	11/18/2019
E-27	Control Conduit Schedule - II	С	11/18/2019
E-28	Trench With Power Conduit Schedule	С	11/18/2019
E-29	Equipment Schedule	С	11/18/2019
E-30	Typical Motor With VFD Wiring Diagram	С	11/18/2019
E-31	Typical Motor Across the Line Wiring Diagram	С	11/18/2019
E-32	Typical Pump LCP	С	11/18/2019
E-33	Lusted Hill Network Diagram	С	11/18/2019
E-34	Typical Flow Loop Diagram	С	11/18/2019
E-35	Typical Pressure Loop Diagram	С	11/18/2019
E-36	Typical Temperature Loop Diagram	С	11/18/2019
E-37	Typical Level Loop Diagram	С	11/18/2019
E-38	Typical Weight Loop Diagram	С	11/18/2019
E-39	Typical Conductivity Loop Diagra	С	11/18/2019
E-40	Control Panel Layout	С	11/18/2019
E-41	PLC Power Schematic & Discrete Input Wiring - I	С	11/18/2019
E-42	Discrete Input Wiring - II	С	11/18/2019
E-43	Discrete Input Wiring - III	С	11/18/2019
E-44	Discrete Input Wiring - IV	С	11/18/2019
E-45	Discrete Outpu Wiring - I	С	11/18/2019
E-46	Discrete Output Wiring - II	С	11/18/2019
E-47	Analog Input Wiring - I	С	11/18/2019
E-48	Analog Input Wiring - II	С	11/18/2019
E-49	Analog Input Wiring - III	С	11/18/2019
E-50	Analog Input Wiring - IV	С	11/18/2019
E-51	Analog Output Wiring - I	С	11/18/2019
E-52	Analog Output Wiring - II	С	11/18/2019
E-53	Security Plan Camera and Gates	С	11/18/2019
E-54	Security Plan Doors	С	11/18/2019
E-55	Security Plan Conduit Utility Water Taps	С	11/18/2019
E-56	Security Plan Diack's Pond - Chemical Injection Vaults	С	11/18/2019
E-57	Security Schedule	С	11/18/2019

#### ATTACHMENT A-2 -LISTING OF 90% SPECIFICATIONS

<u>Specification Number</u> <u>Specification Title</u> DIVISION 00-Procurement and Contracting Requirements (ALL)		Revision	<u>Date</u>
00 72 00	rement and Contracting Requirements (ALL) General Conditions		Dec-18
00 73 00			Dec-18
00 13 00	Supplementary Conditions		Dec-10
DIVISION 01-Gener	ral Requirements (ALL)		
01 10 00	Summary of Work	90% Design	11/18/2019
01 16 00	Owner-Furnished Products and Services	90% Design	11/18/2019
01 29 00	Schedule of Values and Measurement	90% Design	11/18/2019
01 31 13	Project Coordination	90% Design	11/18/2019
01 32 25	Construction Management Software	90% Design	11/18/2019
01 33 00	Submittal Procedures	90% Design	11/18/2019
01 33 17	Structural Design Criteria	90% Design	11/18/2019
01 35 43	Environmental Protection	90% Design	11/18/2019
01 35 53	Site Security	90% Design	11/18/2019
	Attachment A - Confidentiality Statement Form		
	Attachment B – Site Security Access Form		
01 43 33	Manufacturers' Field Services	90% Design	11/18/2019
01 50 00	Temporary Facilities and Controls	90% Design	11/18/2019
	Supplements:		
	Project Construction Signs		
01 55 00	Site Access and Storage	90% Design	11/18/2019
01 55 26	Temporary Traffic Control	90% Design	11/18/2019
01 55 26.13	Accommodations for Public Traffic	90% Design	11/18/2019
01 56 39	Tree and Plant Protection	90% Design	11/18/2019
01 57 13	Temporary Erosion and Sediment Control	90% Design	11/18/2019
	Supplements:	-	
	DEQ Construction Site BMP Inspection Report, Form 1 & 2		
01 74 20	Gravity Pipeline Testing	90% Design	11/18/2019
01 74 30	Pressure Pipe Testing and Disinfection	90% Design	11/18/2019
01 78 23	Operation and Maintenance Data	90% Design	11/18/2019
	Supplements:		
	Maintenance Summary For		
01 78 25	Testing, Equipment Startup and Commissioning	90% Design	11/18/2019
DIVISON 02-Existin	ng Conditions		
02 22 00	Site Condition Surveys	90% Design	11/18/2019
02 22 13	Settlement Monitoring	90% Design	11/18/2019
02 41 00	Removal, Salvage and Disposal	90% Design	11/18/2019
02 61 00	Removal & disposal of Contaminated Media	90% Design	11/18/2019
DIVISON 03-Condit	tions		
03 01 30	Concrete Repair and Rehabilitation	90% Design	11/18/2019
03 11 00	Concrete Forming	90% Design	11/18/2019
03 21 00	Reinforcement Steel	90% Design	11/18/2019
03 31 00	Cast-In-Place Concrete	90% Design	11/18/2019
03 32 00	Joints in Concrete	90% Design	11/18/2019
03 60 00	Grouting	90% Design	11/18/2019
DRAGION OF M.	do.		
<b>DIVISION 05 – Met</b> a 05 05 19		Q00/ D:	11/10/2011
	Post Installed Anchors in Concrete	90% Design	11/18/2019
05 12 00	Structural Steel Framing	90% Design	11/18/2019
05 40 00	Cold Formed Metal Framing	90% Design	11/18/2019

	Miscellaneous Metalwork	90% Design	11/18/2019
05 52 00	Aluminum Railings	90% Design	11/18/2019
OIVISION 06 – Wo	od, Plastics, and Composites		
06 10 00	Rough Carpentry	90% Design	11/18/2019
6 60 00	Fiberglass Fabrication	90% Design	11/18/2019
DIVISION 07 – The	rmal and Moisture Protection		
07 10 00	Dampproofing	90% Design	11/18/2019
7 92 13	Sealants and Caulking	90% Design	11/18/2019
DIVISION 08 - Ope	_		44.40.0040
8 11 13	Steel Doors and Frames	90% Design	11/18/2019
8 33 00	Overhead Coiling Doors	90% Design	11/18/2019
8 62 00	Unit Skylights	90% Design	11/18/2019
8 71 00	Door Hardware	90% Design	11/18/2019
8 74 00	Locking Hardware	90% Design	11/18/2019
8 81 00	Glazing	90% Design	11/18/2019
8 91 00	Louvers	90% Design	11/18/2019
nanotori ee E			
NVISION 09 – Fin		00w p	4440-0040
9 96 00	Protective Coating	90% Design	11/18/2019
IVISION 10 – Spe	uni altino		
nvision 10 – spe 0 14 00		000/ D:	11/18/2019
0 44 00	Building Signage	90% Design 90% Design	11/18/2019
0 44 00	Fire Extinguishers	90% Design	11/16/2019
-	cial Construction	000.	44.40.0040
3 31 00	Tensile Membrane Structure	90% Design	11/18/2019
3 34 19	Pre-Engineered Metal Buildings	90% Design	11/18/2019
3 34 21	Pre-Engineered Metal Canopies	90% Design	11/18/2019
	•	00w D :	11/10/2010
2 10 10	Plumbing, Piping, and Specialties	90% Design	11/18/2019
2 10 10 2 30 00	Plumbing, Piping, and Specialties Plumbing Equipment	90% Design	11/18/2019
22 10 10 22 30 00	Plumbing, Piping, and Specialties		
2 10 10 2 30 00 2 42 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures	90% Design	11/18/2019
2 10 10 2 30 00 2 42 00 DIVISION 23 – Hea	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  sting, Ventilating, and Air Conditioning	90% Design 90% Design	11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 DIVISION 23 – Hea 3 00 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  tting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning	90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 DIVISION 23 – Hea 3 00 00 3 05 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing	90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>IVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment	90% Design 90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>IVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29 3 05 48	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment	90% Design 90% Design 90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>DIVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>DIVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 DIVISION 23 – Hea 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>IVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13 3 34 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 IVISION 23 – Hea 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13 3 34 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>DIVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13 3 34 00 3 52 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Inting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 <b>DIVISION 23 – Hea</b> 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13 3 34 00 3 52 00	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Inting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 IVISION 23 – Head 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13 3 34 00 3 52 00 IVISION 26 – Elector	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Inting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units  Etrical Electrical Work, General	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 DIVISION 23 – Hea 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 09 23 3 31 13 3 34 00 3 52 00 DIVISION 26 – Election 10 10 10 10 10 10 10 10 10 10 10 10 10	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units  Electrical Electrical Work, General Electric Motors	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 IVISION 23 – Hea 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 39 23 3 31 13 3 34 00 3 52 00 IVISION 26 – Electory 10 10 10 10 10 10 10 10 10 10 10 10 10	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Inting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units  Etrical Electrical Work, General	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 IVISION 23 – Hea 3 00 00 3 05 00 3 05 29 3 05 48 3 07 13 3 39 23 3 31 13 3 34 00 3 52 00 IVISION 26 – Elector 10 6 05 10 6 05 19 6 05 26	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units  Electrical Electrical Work, General Electric Motors	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
2 10 10 2 30 00 2 42 00 2 42 00 2 42 00 2 42 00 3 05 00 3 05 29 3 05 48 3 07 13 3 39 23 3 31 13 3 34 00 3 52 00 2 50 00 2 6 05 10 6 05 19 6 05 26 6 05 33	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Iting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units  Electrical Electrical Work, General Electric Motors Low-Voltage Electrical Power Conductors and Cables	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
DIVISION 22 – Plu 12 10 10 12 30 00 12 42 00 DIVISION 23 – Hea 13 00 00 13 05 00 13 05 29 13 05 48 13 07 13 13 34 00 13 34 00 13 52 00 DIVISION 26 – Ele 16 00 00 16 05 10 16 05 19 16 05 26 16 05 33 16 05 43	Plumbing, Piping, and Specialties Plumbing Equipment Plumbing Fixtures  Inting, Ventilating, and Air Conditioning Heating, Ventilating, and Air Conditioning HVAC Testing and Balancing Hangers and Supports for HVAC Piping and Equipment Vibration and Seismic Controls for HVAC Piping and Equipment Duct Insulation HVAC Instrumentation and Controls Metal Ductwork Systems Fan Equipment Air Handling Units  Ctrical Electrical Work, General Electric Motors Low-Voltage Electrical Power Conductors and Cables Grounding and Bonding for Electrical Systems	90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019

26 05 53	Identification for Electrical Systems	90% Design	11/18/2019
26 05 73	Electrical Power Distribution System Studies	90% Design	11/18/2019
26 08 00	Commissioning of Electrical Systems	90% Design	11/18/2019
26 09 16	Electrical Controls and Relays	90% Design	11/18/2019
26 22 00	Low Voltage Transformers and Switchgear	90% Design	11/18/2019
26 24 16	Panelboards	90% Design	11/18/2019
26 24 19	Motor Control Centers	90% Design	11/18/2019
26 27 26	Wiring Devices	90% Design	11/18/2019
26 28 00	Low-Voltage Circuit Protective Devices	90% Design	11/18/2019
26 28 17	Motor and Circuit Disconnects	90% Design	11/18/2019
26 29 23	Variable Frequency Drive Units	90% Design	11/18/2019
26 36 23	Transfer Switches	90% Design	11/18/2019
26 50 00	Lighting	90% Design	11/18/2019
26 56 13	Lighting Poles and Standards	90% Design	11/18/2019
26 56 19	Exterior Lighting	90% Design	11/18/2019
<b>DIVISION 31 – Eart</b> i 31 10 00	hwork Site Preparation	90% Design	11/18/2019
31 12 00	Excavation Support Systems	90% Design	11/18/2019
31 23 19	Dewatering	90% Design	11/18/2019
31 23 33	Trench Excavation, Bedding and Backfil	90% Design	11/18/2019
31 30 00	Farthwork	90% Design	11/18/2019
31 34 19	Geotextiles	90% Design	11/18/2019
31 35 26	Erosion Control Barrier	90% Design	11/18/2019
32 11 13 32 11 14 32 11 23	A.C. Pavement and Base Pavement Markings - Legends and Bars (Thermoplastics) Aggregate Base and Subbase Courses	90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019
32 31 13	Aggregate Base and Subbase Courses Chain Link Fencing	90% Design	11/18/2019
32 84 00	Irrigation	90% Design	11/18/2019
32 91 13	Soil Preparation	90% Design	11/18/2019
32 92 00	Seeding	90% Design	11/18/2019
32 93 00	Plants	90% Design	11/18/2019
32 95 00	Plant Establishment and Maintenance	90% Design	11/18/2019
<b>DIVISION 33 – Utili</b> 33 05 16			11/18/2019
33 05 23	Horizontal Directional Drilling	90% Design 90% Design	11/18/2019
33 92 10	Steel Pipe, Specials, and Fittings	90% Design	11/18/2019
33 92 20	Ductile Iron Piping	90% Design	11/18/2019
33 95 34	Large Polyethylene Pressure Piping	90% Design	11/18/2019
33 95 40	Small Poly Vinyl Chloride Non Pressure Piping Rubber Joints	90% Design	11/18/2019
33 95 50	PVC Pressure Pipe, Rubber Joints	90% Design	11/18/2019
33 30	ryorressure ripe, Number Joints	50% Design	11/10/2019
<b>DIVISION 40 – Instr</b> 40 05 00	rumentation and Control for Process Systems Piping General	90% Design	11/18/2019
40 05 00	Piping General Piping Identification	90% Design	11/18/2019
40 05 02	Pipe Supports	90% Design	11/18/2019
	Copper Water Tube	90% Design	11/18/2019
AN NS 17	Copper vvaler Tube		11/18/2019
	Continue Coll Disc		11/18/7019
40 05 18	Cast Iron Soil Pipe	90% Design	
40 05 18 40 05 23	Stainless Steel Pipe	90% Design	11/18/2019
40 05 18 40 05 23 40 05 24	Stainless Steel Pipe Steel Pipe	90% Design 90% Design	11/18/2019 11/18/2019
40 05 18 40 05 23 40 05 24 40 05 30	Stainless Steel Pipe Steel Pipe PVC Pressure Pipe	90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019
40 05 17 40 05 18 40 05 23 40 05 24 40 05 30 40 05 31 40 10 64	Stainless Steel Pipe Steel Pipe	90% Design 90% Design	11/18/2019 11/18/2019

40 66 00 *	Network Communications Equipment	90% Design	11/18/2019
40 66 33 *	Metallic and Fiber Optic Communications Cabling and Connectors	90% Design	11/8/2019
40 90 10	Control Strategies	90% Design	11/8/2019
40 91 00	Process Control and Instrumentation	90% Design	11/18/2019
40 91 02	In-Line Liquid Flow Measuring	90% Design	11/8/2019
40 91 06	Level Measuring	90% Design	11/18/2019
40 91 08	Pressure Measuring	90% Design	11/18/2019
10 91 12	Process Monitoring	90% Design	11/18/2019
10 95 10	Programmable Logic Controllers	90% Design	11/18/2019
40 95 13	Control Panels	90% Design	11/18/2019
40 95 15	Panel Mounted Instruments	90% Design	11/18/2019
	erial Processing and Handling Equipment		
41 35 60	Carbon Dioxide Feed System	90% Design	11/18/2019
43 07 00	cess Gas and Liquid Handling, Purification, and Storage Equipment Pipe and Equipment Insulation	90% Design	11/18/2019
43 20 00	Pumps, General	90% Design	11/18/2019
43 22 93	Submersible Sump Pumps	90% Design	11/18/2019
13 23 02	Horizontal ANSI End Suction Pumps	90% Design	11/18/2019
13 24 03	Submersible Deep Well Turbine Pumps	90% Design	11/18/2019
13 30 00	Valves, General	90% Design	11/18/2019
3 30 12	Valves and Gate Actuators		44400040
10 00 12	valves and Gate Actuators	90% Design	11/18/2019
	Valves and Gate Actuators  Butterfly Valves	90% Design 90% Design	11/18/2019
13 30 14		_	
13 30 14 13 30 16	Butterfly Valves	90% Design	11/18/2019
13 30 14 13 30 16 13 30 18	Butterfly Valves Check Valves	90% Design 90% Design	11/18/2019 11/18/2019
43 30 14 43 30 16 43 30 18 43 30 22	Butterfly Valves Check Valves Ball Valves	90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019
43 30 14 43 30 16 43 30 18 43 30 22 43 30 40	Butterfly Valves Check Valves Ball Valves Gate Valves	90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019
43 30 14 43 30 16 43 30 18 43 30 22 43 30 40 43 30 52	Butterfly Valves Check Valves Ball Valves Gate Valves Pressure Sustaining Valves	90% Design 90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
43 30 14 43 30 16 43 30 18 43 30 22 43 30 40 43 30 52 DIVISIONS 46 - Wa	Butterfly Valves Check Valves Ball Valves Gate Valves Pressure Sustaining Valves Miscellaneous Valves	90% Design 90% Design 90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019
43 30 14 43 30 16 43 30 18 43 30 22 43 30 40 43 30 52	Butterfly Valves Check Valves Ball Valves Gate Valves Pressure Sustaining Valves Miscellaneous Valves	90% Design 90% Design 90% Design 90% Design 90% Design 90% Design	11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019 11/18/2019



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Project Name:	Corrosion Conti	rol Improvements P	roject	
Date:	October 25, 201	9	RFI Number:	001
Contractor:	MWH Construc	tors, Inc.	P.O. / Contract Number:	30006839
Address:	370 Interlocken	Blvd. Suite 400	Ordinance Number:	188621
City, State, Zip	Broomfield, CO	80021	Contract Date:	April 23, 2019
Attn:	Ben McGeachy		Project Number:	W02190
Contractor requests info	rmation for the rea	son checked below: (	Check one box only)	
Clarification of Design	gn Intent	Differing Site Cond	litions Other:	
Change for Contracto	or Convenience	Possible Bettermen		
A response to this infor	_	guested by:	(16 d D V )	
Tresponse to this infor	indicon request is re	quested by:	(Month Day, Year)	
Subject:	P-04 Soda Ash S	torage and Feed Sy	stem Bid Package	
Specification Section:	46 32 40 Soda Ash S	Storage and Feed Syste	m	
Drawing No:		]	Detail No:	
Request: (Limit or	ne issue per RFI)	Cost Impact:	Schedule Impact.	
Response:				



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Response 1A: Soda Ash equipment coatings should be FM 16	5.
Response 1B: The interior of the solution tanks should be FM	112.
Response 2A: Please follow the P&ID drawings and provide	1 guided wave radar and 3 level switches (on each silo).
Response 3A: The pump suction isolation valving (manual bathe soda ash equipment vendor. These valves will be supplied the signal between the pump suction isolation valving and the	ed by others. The P&ID drawings will be revised to remove
  -	
Owner's Representative	Date
The response to this request by the Owner's representative shall not be construed a contract. The Owner's response does not relieve the Contractor of any of the risks pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Special Construction Construction Special Construction Special Construction Construct	or obligations under the Contract. The Owner's response constitutes a Field Order
cc: File,CM,Sr. Inspector,Site Inspector,	



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Project Name:	Corrosion Control improvements Project		
Date:	October 25, 2019	RFI Number:	002
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019
Attn:	Ben McGeachy	Project Number:	W02190
Contractor requests info	ormation for the reason checked below: (Check	one box only)	
⊠Clarification of Desi	gn Intent Differing Site Conditions	Other:	
Change for Contract	or Convenience Possible Betterment		
A response to this infor	mation request is requested by:	(Month Day, Year)	
Subject:	P-04 Soda Ash Storage and Feed System E	Bid Package	
Specification Section:	46 32 40 Soda Ash Storage and Feed System		
Drawing No:	Detail N	0:	
Request: (Limit of	ne issue per RFI) Cost Impact:	Schedule Impact.	
_	enterline-to-centerline dimensional distance bet		s dimension
influences the crosswal	k design and if a support structure would be req	uired for the crosswalk.	
Contractor's Represe	entative Date		
Despenses			
Response:			
The centerline to center	rline distance between the silos is 25'8"		
The centerine to center	inic distance octween the shos is 25 o		



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Owner's Representative	Date
The response to this request by the Owner's representative shall not be construed a contract. The Owner's response does not relieve the Contractor of any of the risks pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Special Construction Cons	s or obligations under the Contract. The Owner's response constitutes a Field Order
cc: File,CM,Sr. Inspector,Site Inspector,	



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

D-4		cı	
Date:	October 25, 2019	RFI Number:	003
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019
Attn:	Ben McGeachy	Project Number:	W02190
Contractor requests info	ormation for the reason checked below: (Che	ck one box only)	
⊠Clarification of Desi	gn Intent Differing Site Condition	ns Other:	
Change for Contract	or Convenience Possible Betterment		
A response to this infor	mation request is requested by:	(Month Day, Year)	
-			
Subject:	P-04 Soda Ash Storage and Feed System	ı Bid Package	
Specification Section:	46 32 40 Soda Ash Storage and Feed System		
Drawing No:	Detai	l No:	
Request: (Limit o	ne issue per RFI) Cost Impact:	Schedule Impact.	
<ol> <li>The specification mentions only a single crosswalk (i.e. the crosswalk from the roof of one silo to the roof of the other silo); however, the drawings show what appears to be a second "intermediate level" crosswalk. Please clarify how many crosswalk(s) are required as well as where the crosswalk(s) are to be located.</li> <li>The contract drawings show that the mixing tank shares one wall with the silo. Due to the size of the mixing tank, we (i.e. equipment manufacturer) will not be able to insulate this wall, which we (i.e. equipment manufacturer) feel can be problematic. We (i.e. equipment manufacturer) feel the tank should be a completely separate item, so that the entire thing can reside inside an insulated, heated silo. Please clarify the intent of the design.</li> <li>We (i.e. equipment manufacturer) will need to mount a pneumatic slide gate between the silo discharge and the delumper. The reason for doing this is that the delumper needs to be isolated in order for it to function properly. Please confirm this approach is acceptable to the Owner and Engineer.</li> <li>There are many components typically provided in the silo skirt that are not mentioned iFAn the silo specification (e.g. lights, receptacles, heater, fans, thermostats, etc.). Please clarify the exact components that are needed in the skirt.</li> </ol>			
2. The contract drawin (i.e. equipment manufa problematic. We (i.e. e can reside inside an ins.)  3. We (i.e. equipment redelumper. The reason confirm this approach in the confirmation that is a confirmation to the confirmation that is a confirmation that is a confirmation that is a confirmation to the confirmation that is a confir	igs show that the mixing tank shares one wall octurer) will not be able to insulate this wall, we equipment manufacturer) feel the tank should rulated, heated silo. Please clarify the intent of manufacturer) will need to mount a pneumation of doing this is that the delumper needs to be acceptable to the Owner and Engineer.  In ponents typically provided in the silo skirt the ter, fans, thermostats, etc.). Please clarify the	with the silo. Due to the size of the which we (i.e. equipment manufacture) be a completely separate item, so the design.  It is slide gate between the silo discharter isolated in order for it to function gate are not mentioned iFAn the silo separate react components that are needed in the silo separate isolated in order for it to function gate.	e mixing tank, we arer) feel can be hat the entire thing ge and the properly. Please
2. The contract drawin (i.e. equipment manufa problematic. We (i.e. ecan reside inside an ins.)  3. We (i.e. equipment redelumper. The reason confirm this approach in the confirmation that the confirmation is approach in the confirmation that the confirmation is approach in the confirmation that the confirmation is a confirmation to the confirmation that the confirmation is a confirmation to the confirmation that the confirmation is a confirmation to the confirmation that the confirmation is a confirmation to the confirmation that the confirmation is a confirmation to the confirmation that	igs show that the mixing tank shares one wall octurer) will not be able to insulate this wall, we equipment manufacturer) feel the tank should rulated, heated silo. Please clarify the intent of manufacturer) will need to mount a pneumation of doing this is that the delumper needs to be acceptable to the Owner and Engineer.  In ponents typically provided in the silo skirt the ter, fans, thermostats, etc.). Please clarify the	with the silo. Due to the size of the which we (i.e. equipment manufacture) be a completely separate item, so the design.  It is slide gate between the silo discharter isolated in order for it to function gate are not mentioned iFAn the silo separate react components that are needed in the silo separate isolated in order for it to function gate.	e mixing tank, we arer) feel can be hat the entire thing ge and the properly. Please



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

- The intermediate crosswalk indicted on the drawings would be part of internal skirt equipment access, if required.
  The specification requires that each silo provide an equipment maintenance system. This system will provide access
  to all equipment inside the silo skirt without exposure to confined spaces or working at heights. For some
  manufacturers the best approach to this may be to provide a secondary access by crosswalk to a mezzanine level
  inside the silo above the soda ash mixing tank.
- 2. The mixing tank is not required to be constructed exactly as shown on the 90% drawings. The manufacturer may configure the mixing tank to best suit their silo, within the limits of section 2.8 Soda Ash Solution Feed System.
- 3. It is acceptable to mount a pneumatic slide gate between the silo discharge and the delumper. The existing facility has an existing air compressor for use. The air compressor is rated at 5 hp and delivers 17.3 cfm at 175 psi. The manufacturer should confirm that the silo air requirement can be met by this air compressor.
- 4. The silo should be suitable for operation and maintenance 24 hours per day, 7 days a week in the Northwest Oregon climate. The equipment and applicable appurtenances required at a minimum shall include:
  - Indoor and outdoor lighting, including lighting of the exterior spiral staircase and roof
  - Skirting insulation
  - Skirt interior exhaust fan
  - Skirt interior heater
  - 2 duplex receptacles

cc: File,CM,Sr. Inspector,Site Inspector,

Skirt interior thermostat

Owner's Representative	Date
	as direction or advice on the method or manner of performing any work under the s or obligations under the Contract. The Owner's response constitutes a Field Order pecifications.
•	•



3. Yes 2.3.D.2 should also be 20 lbs/hr

#### Amanda Fritz, Commissioner Michael Stuhr, P.E., Administrator

1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

## REQUEST FOR INFORMATION

Project Name:	Corrosion Control Improvements Pro-	ect	
Date:	October 28, 2019	RFI Number:	004
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019
Attn:	Ben McGeachy	Project Number:	W02190
Contractor requests info	ormation for the reason checked below: (Ch	eck one box only)	
Clarification of Desi	gn Intent Differing Site Condition	ons Other:	
Change for Contracto	or Convenience Possible Betterment		
A response to this inform	mation request is requested by:	(Month Day, Year)	
Subject:	P-01 Carbon Dioxide Feed System Bid	Package	
Specification Section:			
Drawing No:	Det	ail No:	
Request: (Limit one issue per RFI) Cost Impact: Schedule Impact.			
Request: (Limit or	ne issue per RFI) Cost Impact:	Schedule Impact.	
Request: (Limit of	ne issue per RFI) Cost Impact:	Schedule Impact.	_
•		Schedule Impact.	_
Regarding Specification	n 41 35 60 – Carbon Dioxide Feed System:		
Regarding Specification			correct?
Regarding Specification  1. 41 35 60, Part 1	n 41 35 60 – Carbon Dioxide Feed System:	maximum delivery rate (worst case),	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2	n 41 35 60 – Carbon Dioxide Feed System:  1.1.E – This is the dissolution efficiency at a control of the contro	maximum delivery rate (worst case), ature at time of maximum req'd deli	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2	n 41 35 60 – Carbon Dioxide Feed System:	maximum delivery rate (worst case), ature at time of maximum req'd deli	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2	n 41 35 60 – Carbon Dioxide Feed System:  1.1.E – This is the dissolution efficiency at a control of the contro	maximum delivery rate (worst case), ature at time of maximum req'd deli	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2  3. 41 35 60, Parts	n 41 35 60 – Carbon Dioxide Feed System:  1.1.E – This is the dissolution efficiency at a control of the contro	maximum delivery rate (worst case), ature at time of maximum req'd deliv 20 lb/hr instead of 10 lb/hr?	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2  3. 41 35 60, Parts  Contractor's Represe	n 41 35 60 – Carbon Dioxide Feed System:  1.1.E – This is the dissolution efficiency at a control of the contro	maximum delivery rate (worst case), ature at time of maximum req'd deliv 20 lb/hr instead of 10 lb/hr?	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2  3. 41 35 60, Parts	n 41 35 60 – Carbon Dioxide Feed System:  1.1.E – This is the dissolution efficiency at a control of the contro	maximum delivery rate (worst case), ature at time of maximum req'd deliv 20 lb/hr instead of 10 lb/hr?	
Regarding Specification  1. 41 35 60, Part 1  2. 41 35 60, Part 2  3. 41 35 60, Parts  Contractor's Represe  Response:	n 41 35 60 – Carbon Dioxide Feed System:  1.1.E – This is the dissolution efficiency at a control of the contro	maximum delivery rate (worst case), ature at time of maximum req'd deliv 20 lb/hr instead of 10 lb/hr?	

## An Equal Opportunity Employer



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



Owner's Representative	Date

The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.

cc: File,CM,Sr. Inspector,Site Inspector,



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Project Name:	Corrosion Control Improvements Project				
Date:	October 28, 2019	RFI Number:	005		
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839		
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621		
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019		
Attn:	Ben McGeachy	Project Number:	W02190		
Contractor requests info	ormation for the reason checked below: (Check	one box only)			
☐Clarification of Desi	☐ Clarification of Design Intent ☐ Differing Site Conditions ☐ Other:				
Change for Contract	or Convenience Possible Betterment				
A response to this infor	mation request is requested by:	(Month Day, Year)			
Subject:	P-04 Soda Ash Storage and Feed System	Bid Package			
Specification Section:	46 32 40 Soda Ash Storage and Feed System				
Drawing No:	rawing No: Detail No:				
Request: (Limit one issue per RFI) Cost Impact: Schedule Impact.  1. The Specifications SECTION 46 32 40 does not contain information on the silo skirt heater, we (i.e. the equipment manufacturer) are requesting acceptance for use of the Dayton 2YU70 product.  2. The Specifications SECTION 46 32 40 does not contain information on the silo skirt exhaust fan, we (i.e. the equipment manufacturer) are requesting acceptance for use of the Dayton 10D985 product.  3. The Specifications SECTION 46 32 40 does not contain information on the silo jib crane, we (i.e. the equipment manufacturer) are requesting acceptance for use of the Thern 5PT10-E4-P product.  4. The Specifications SECTION 46 32 40 does not contain information on the slurry tank heater, we (i.e. the equipment manufacturer) are requesting acceptance for use of the Durex MTL4A-840680W-210C8 product. We want to keep the slurry temperature higher than 60°F, in order to avoid soda ash slurry crystallization.					
manufacturer) are required.  2. The Specifications sequipment manufacturer  3. The Specifications sequipment manufacturer  4. The Specifications sequipment manufacturer are required.	SECTION 46 32 40 does not contain information are requesting acceptance for use of the Day SECTION 46 32 40 does not contain information acceptance for use of the Day esting acceptance for use of the Thern 5PT10-FECTION 46 32 40 does not contain information acceptance for use of the Durex MTL4A	on on the silo skirt exhaust fan, we ston 10D985 product. On on the silo jib crane, we (i.e. the E4-P product. On on the slurry tank heater, we (i.e. 440680W-210C8 product. We w	e (i.e. the e equipment e. the equipment		
manufacturer) are required.  2. The Specifications sequipment manufacturer  3. The Specifications sequipment manufacturer  4. The Specifications sequipment manufacturer are required.	SECTION 46 32 40 does not contain information are requesting acceptance for use of the Day SECTION 46 32 40 does not contain information esting acceptance for use of the Thern 5PT10-F SECTION 46 32 40 does not contain information acceptance for use of the Thern 5PT10-F SECTION 46 32 40 does not contain information esting acceptance for use of the Durex MTL4A ner than 60°F, in order to avoid soda ash slurry	on on the silo skirt exhaust fan, we ston 10D985 product. On on the silo jib crane, we (i.e. the E4-P product. On on the slurry tank heater, we (i.e. 440680W-210C8 product. We w	e (i.e. the e equipment e. the equipment		



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

1.	A heater for the silo skirt has been added to the specification. The heater shall maintain a minimum temperature of
	50°F inside the silo skirt to be acceptable.

- 2. An exhaust fan has been added to the specification. The exhaust fan should be sized to suit the space under the skirt
- 3. The silo jib crane is found in section 46 32 40 .2.1.D Silo Roof Davit Crane.
- 4. The soda ash will be batched to a solution, not a slurry. The solution shall be maintained below 2.5% and should not require a tank heater.

Owner's Representative	Date

The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.

cc: File,CM,Sr. Inspector,Site Inspector,



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Corrosion Control Improvements Proje	ect			
October 31, 2019	RFI Number:	006		
MWH Constructors, Inc.	P.O. / Contract Number:	30006839		
370 Interlocken Blvd. Suite 400	Ordinance Number:	188621		
Broomfield, CO 80021	Contract Date:	April 23, 2019		
Ben McGeachy	Project Number:	W02190		
ormation for the reason checked below: (Che	ck one box only)			
Clarification of Design Intent				
or Convenience Possible Betterment				
mation request is requested by:	(Month Day, Year)			
P-04 Soda Ash Storage and Feed System	n Bid Package			
46 32 40 Soda Ash Storage and Feed System				
Deta	il No:			
ne issue per RFI) Cost Impact:	Schedule Impact.			
ash silo). Specifically, is handrailing required along both sides of the spiral staircase? Or is handrailing just required along the exterior of the spiral staircase (i.e. just along the side of the stairs that is NOT adjacent to the tank)?				
include handrailing along the interior of the sp	piral staircase (i.e. shall <u>not</u> include h	andrailing adjacent		
	October 31, 2019  MWH Constructors, Inc.  370 Interlocken Blvd. Suite 400  Broomfield, CO 80021  Ben McGeachy  Ormation for the reason checked below: (Checked gn Intent	MWH Constructors, Inc.  370 Interlocken Blvd. Suite 400 Broomfield, CO 80021 Ben McGeachy  Domination for the reason checked below: (Check one box only) gn Intent Differing Site Conditions Ordinance Number:  Project Number:  Ordinance Number:  Contract Date: Project Number:  Ordinance Number:  Onthract Date: Project Number:  Other:  Other:		



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Owner's Representative	Date		
The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.			
cc: File,CM,Sr. Inspector,Site Inspector,			



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

Project Name:	Corrosion Control Improvements Project			
Date:	November 1, 2019	RFI Number:	007	
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839	
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621	
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019	
Attn:	Ben McGeachy	Project Number:	W02190	
Contractor requests inf	formation for the reason checked below: (Check	one box only)		
☐Clarification of Des	ign Intent Differing Site Conditions	Other:		
Change for Contract	tor Convenience Possible Betterment			
A response to this infor	rmation request is requested by: 11/7/19	(Month Day, Year)		
Subject:	S-09 Pre-Engineered Metal Building and	Pre-Engineered Metal Canopie	S	
Specification Section:	13 34 19 and 01 33 17			
Drawing No:	Detail 1	No:		
Detail No:   Detail No:     Schedule Impact.				
Response:				



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

- 1. IAS AC472 certification is an acceptable alternate to MBMA membership
- This should be Risk Category II
- 3. Collateral Loads shall be considered be as follows:
  - a. Piping and ductwork a uniform load of 20 PSF shall be assumed throughout the building
  - b. Mechanical equipment Point loads for AHI-01, EF-01 and EF-02 shall be as shown in the schedules on GH-3, at the locations shown on the HVAC drawings.
  - c. Connections and supports for the above are the responsibility of the contractor and shall be included as a deferred submittal.
- 4. Yes, the project is required to comply with the American Iron and Steel provisions (a.k.a. Buy American).

Owner's Representative	Date
The response to this request by the Owner's representative shall not be construed a contract. The Owner's response does not relieve the Contractor of any of the risks pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Sp.	or obligations under the Contract. The Owner's response constitutes a Field Order
cc: File,CM,Sr. Inspector,Site Inspector,	



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

# REQUEST FOR INFORMATION

Troject Name.	Corrosion Control improvements Project			
Date:	November 5, 2019	RFI Number:	008	
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839	
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621	
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019	
Attn:	Ben McGeachy	Project Number:	W02190	
Contractor requests info	rmation for the reason checked below: (Check o	ne box only)		
Clarification of Design	en Intent Differing Site Conditions	Other:		
Change for Contracto				
_	mation request is requested by: 11/8/19			
A response to this inform	nation request is requested by.	(Month Day, Year)		
Subject:	Bid Package S-22 - Tree Removal			
Specification Section:	01 56 39 (Tree and Plant Protection)			
Drawing No:	Detail No	o:		
Request: (Limit or	ne issue per RFI) Cost Impact:	Schedule Impact.		
request: (2)		stream Impact		
1. Specification 01 56 3 package?	39, Part 1.7, Item A - Is a certified arborist requi	red to complete the early-out tre	e removal	
package? If erected nov beginning construction	39, Part 1.7, Item B - Is tree protection fencing row, the specified orange plastic construction fencion work next summer. As an alternate, for the earliefy the limits of the "construction limit fencing".	ing will likely need to be replace y-out tree removal package, cou	ed prior to	
_	39, Part 1.8, Item B - Is construction limit fencin tive, for the early-out tree removal package, cou on limit fencing"?			
4. Specification 01 56 39, Part 3.1, Item A - Is flagging of existing trees required to complete the early-out tree removal package? Portland Water Bureau will flag "trees to be removed". It appears that all trees within the "construction limit fencing" are scheduled to be removed. There doesn't appear to be any "trees to remain" within the "construction limit fencing".				
package? It appears tha	39, Part 3.2, Item B - Is a certified arborist require all trees within the construction limits are schezone" for existing trees?	-		
Please confirm that veh	39, Part 3.3, Item C - This item prohibits vehicle icle traffic is not allowed within the "construction removed? Is the intent of this item to prohibit	on limit fencing". If vehicle traff	fic is not allowed,	



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



Contractor's Representative Date

#### Response:

- A certified arborist is not required for the early out tree package.
- Tree protection fencing should be erected prior to tree removal.
- 3. Tree protection fencing can be used as construction limits fencing for the early out packages.
- 4. Trees have been marked for removal by PWB with orange paint.
- A certified arborist is not required for the early out tree package.
- Vehicle traffic is allowed inside of the construction limits fencing and not beyond the limits or into tree preservation/protection areas.

Owner's Representative 12/09/2019

Date

The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.

cc: File,CM,Sr. Inspector,Site Inspector,



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

### REQUEST FOR INFORMATION

Project Name:	Corrosion Control	Improvements Project		
Date:	November 5, 2019	)	RFI Number:	009
Contractor:	MWH Constructor	rs, Inc.	P.O. / Contract Number:	30006839
Address:	370 Interlocken B	lvd. Suite 400	Ordinance Number:	188621
City, State, Zip	Broomfield, CO 8	0021	Contract Date:	April 23, 2019
Attn:	Ben McGeachy		Project Number:	W02190
Contractor requests info	ormation for the reason	n checked below: (Check o	one box only)	
⊠Clarification of Desi	gn Intent 🔲 🗆	Differing Site Conditions	Other:	
Change for Contract	or Convenience	Possible Betterment		
A response to this infor	mation request is requ	ested by: 11/8/19	(Month Day, Year)	
			(Monin Day, Tear)	
Subject:	Bid Package S-22 -			
Specification Section:	31 10 00 (Site Preparate	ion)		
Drawing No:		Detail N	0.	
Drawing 110.		Detail it	···	
	ne issue per RFI)	Cost Impact:	Schedule Impact.	
	ne issue per RFI) (			
Request: (Limit of	•	Cost Impact:	Schedule Impact.	ires, as necessary.
Request: (Limit of	00, Part 1.1, Item B - I	Cost Impact:  It is our intent to place ero		
Request: (Limit of 1. Specification 31 10 to support the early-out	00, Part 1.1, Item B - I tree removal work. P	Cost Impact:  It is our intent to place ero	Schedule Impact.	
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing w	00, Part 1.1, Item B - I tree removal work. P ill NOT be required fo	Cost Impact:  It is our intent to place ero Please confirm that site wice or the tree removal work.	Schedule Impact.  esion and sediment control measured erosion and sediment control in	measures as well
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing w 2. Specification 31 10 0	00, Part 1.1, Item B - I tree removal work. P rill NOT be required fo 00, Part 3.1, Item A - F	Cost Impact:  It is our intent to place ero Please confirm that site wic or the tree removal work.  Please confirm that the tree	Schedule Impact.  ssion and sediment control measured erosion and sediment control to the removal subcontractor will have	measures as well re access BOTH
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing w 2. Specification 31 10 0	00, Part 1.1, Item B - I tree removal work. P rill NOT be required fo 00, Part 3.1, Item A - F	Cost Impact:  It is our intent to place ero Please confirm that site wic or the tree removal work.  Please confirm that the tree	Schedule Impact.  esion and sediment control measured erosion and sediment control in	measures as well re access BOTH
Request: (Limit of  1. Specification 31 10 to support the early-out as temporary fencing w  2. Specification 31 10 0 via the existing Lusted	00, Part 1.1, Item B - I tree removal work. P rill NOT be required fo 00, Part 3.1, Item A - F Hill Treatment Facilit	Cost Impact:  It is our intent to place ero Please confirm that site wich or the tree removal work.  Please confirm that the tree y as well as via the private	Schedule Impact.  osion and sediment control measured erosion and sediment control is eremoval subcontractor will have access road to the Diack's Ponder	measures as well re access BOTH l area.
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing where 2. Specification 31 10 to via the existing Lusted 3. Specification 31 10	00, Part 1.1, Item B - I tree removal work. P rill NOT be required fo 00, Part 3.1, Item A - F Hill Treatment Facilit	Cost Impact:  It is our intent to place ero Please confirm that site wic or the tree removal work.  Please confirm that the tree y as well as via the private	Schedule Impact.  Schedule Imp	measures as well re access BOTH l area. s to be removed".
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing where 2. Specification 31 10 to via the existing Lusted 3. Specification 31 10 Is the intent that the entitle of the control of	00, Part 1.1, Item B - I tree removal work. P rill NOT be required for 00, Part 3.1, Item A - F Hill Treatment Facility 00 (general) - This spe tire tree including all b	Cost Impact:  It is our intent to place ero Please confirm that site wice or the tree removal work.  Please confirm that the tree by as well as via the private ecification does not identify branches, stump material, e	Schedule Impact.  osion and sediment control measured erosion and sediment control is eremoval subcontractor will have access road to the Diack's Ponder	measures as well re access BOTH l area. s to be removed".
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing where 2. Specification 31 10 to via the existing Lusted 3. Specification 31 10	00, Part 1.1, Item B - I tree removal work. P rill NOT be required for 00, Part 3.1, Item A - F Hill Treatment Facility 00 (general) - This spe tire tree including all b	Cost Impact:  It is our intent to place ero Please confirm that site wice or the tree removal work.  Please confirm that the tree by as well as via the private ecification does not identify branches, stump material, e	Schedule Impact.  Schedule Imp	measures as well re access BOTH l area. s to be removed".
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing where 2. Specification 31 10 to via the existing Lusted 3. Specification 31 10 Is the intent that the entitle of the control of	00, Part 1.1, Item B - I tree removal work. P rill NOT be required for 00, Part 3.1, Item A - F Hill Treatment Facility 00 (general) - This spe tire tree including all b	Cost Impact:  It is our intent to place ero Please confirm that site wice or the tree removal work.  Please confirm that the tree by as well as via the private ecification does not identify branches, stump material, e	Schedule Impact.  Schedule Imp	measures as well re access BOTH l area. s to be removed".
Request: (Limit of 1. Specification 31 10 to support the early-out as temporary fencing where 2. Specification 31 10 to via the existing Lusted 3. Specification 31 10 Is the intent that the entitle of the control of	00, Part 1.1, Item B - I tree removal work. P rill NOT be required for 00, Part 3.1, Item A - F Hill Treatment Facility 00 (general) - This spective tree including all b is allowed, can the chip	Cost Impact:  It is our intent to place ero Please confirm that site wice or the tree removal work.  Please confirm that the tree by as well as via the private ecification does not identify branches, stump material, e	Schedule Impact.  Schedule Imp	measures as well re access BOTH l area. s to be removed".

#### Response:

- Site-wide erosion control is not required for the tree removal effort. Care should be taken to ensure the no visible
  or measurable sediment leaves the site and that all soil that is exposed through this work is covered and protected.
- The tree removal contractor will have access to both the existing Lusted Hill Facility and the private access road across the Diak property.
- Chipping is allowed and chips that the prime contractor feels may have beneficial use may remain on site but become the sole property and responsibility of the prime contractor and stockpiles shall be appropriately maintained during construction and removed prior to final project completion.



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

A.	
//~	

11/26/2019

Date

#### Owner's Representative

The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.

cc: File,CM,Sr. Inspector,Site Inspector,



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

# REQUEST FOR INFORMATION

Troject Name.	Corrosion Control Improvements Fro	,				
Date:	November 12, 2019	RFI Number:	010			
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839			
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621			
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019			
Attn:	Ben McGeachy	Project Number:	W02190			
Contractor requests info	ormation for the reason checked below: (C	heck one box only)				
	Clarification of Design Intent					
Change for Contract	or Convenience Possible Betterment					
A response to this infor	mation request is requested by: 11/15/19	(Month Day, Year)				
Subject:	Bid Package S-09 - Pre-Engineered M		Metal Canonies			
Specification Section:	13 34 21 (Pre-Engineered Metal Canopies)	letal Building and Fre-Elignicered	wiciai Canopies			
Drawing No:	, ,	etail No:				
Request: (Limit of	ne issue per RFI) Cost Impact:	Schedule Impact.				
<ol> <li>Specification 13 34 21, Part 2.1, Item C (page 6) lists Pacific Building Systems (PBS) as an approved manufacture for the pre-engineered metal canopies. Unfortunately, PBS does not meet the requirements of the specification as they do not use HSS tubing in their process. Could the canopies be built using hot rolled W sections for the columns and rafters (in lieu of the specified HSS)?</li> <li>The S-09 Scope of Work document, Item 4.1.12 states " Subcontractor's Scope of Work includes furnish and installation of building appurtenances, including but not limited to, man-doors, overhead coiling doors, windows, skylights, and louvers." We see the skylights on the drawings but cannot find a specification. Please provide a specification for the skylights.</li> </ol> Contractor's Representative Date						
Response:						
1. The canopies can be			•			



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandgregon.gov/water



www.portlandoregon.gov/water An Equal Opportunity Employer

- -	
Owner's Representative	Date
·	Date  Instrued as direction or advice on the method or manner of performing any work under the
The response to this request by the Owner's representative shall not be con	
The response to this request by the Owner's representative shall not be con	astrued as direction or advice on the method or manner of performing any work under the he risks or obligations under the Contract. The Owner's response constitutes a Field Order
The response to this request by the Owner's representative shall not be con contract. The Owner's response does not relieve the Contractor of any of the	astrued as direction or advice on the method or manner of performing any work under the he risks or obligations under the Contract. The Owner's response constitutes a Field Order
The response to this request by the Owner's representative shall not be con contract. The Owner's response does not relieve the Contractor of any of the	astrued as direction or advice on the method or manner of performing any work under the he risks or obligations under the Contract. The Owner's response constitutes a Field Order



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



#### REQUEST FOR INFORMATION

Project Name:	Corrosion Control Improvements Project				
Date:	November 22, 2019	011			
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839		
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621		
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019		
Attn:	Ben McGeachy	Project Number:	W02190		
Contractor requests info	ormation for the reason checked below: (Check of	one box only)			
Clarification of Design	gn Intent Differing Site Conditions	Other:			
Change for Contracto		_			
	mation request is requested by: 12/3/19				
A response to this infor	mation request is requested by.	(Month Day, Year)			
Subject: Bid Package S-22 - Tree Removal					
Subject.	Did I ackage 5-22 - Tree Removar				
Specification Section:	Did Lackage 5-22 - Tree Tellioval				
· .	Detail N	0:			
Specification Section: Drawing No:	•	o: Schedule Impact.			
Specification Section: Drawing No:  Request: (Limit or	Detail N ne issue per RFI) Cost Impact:	Schedule Impact.	sting season?		
Specification Section: Drawing No:  Request: (Limit of 1. Removal is tentative)	Detail N	Schedule Impact. duled to avoid migratory bird ne			
Specification Section: Drawing No:  Request: (Limit of 1. Removal is tentative) 2. Some trees slated for damage/disturbance is a	Detail Note issue per RFI) Cost Impact:  ly scheduled for 3/30-5/1. Can the work be scheduled removal are within the RPZ of trees designated acceptable in these situations?	Schedule Impact. duled to avoid migratory bird ne			
Specification Section: Drawing No:  Request: (Limit of 1. Removal is tentative) 2. Some trees slated for damage/disturbance is a 3. Is erosion/expected to	Detail Note issue per RFI) Cost Impact:  ly scheduled for 3/30-5/1. Can the work be scheduled are within the RPZ of trees designated acceptable in these situations?  To be inspected until the next phase of developments.	Schedule Impact.  duled to avoid migratory bird need for preservation. What amount onent?			
Specification Section: Drawing No:  Request: (Limit or 1. Removal is tentativel 2. Some trees slated for damage/disturbance is a 3. Is erosion/expected to 4. Is standing water in or	Detail Note issue per RFI) Cost Impact:  ly scheduled for 3/30-5/1. Can the work be scheduced are within the RPZ of trees designated acceptable in these situations?  To be inspected until the next phase of development clearing area expected to be managed until the next phase.	Schedule Impact.  duled to avoid migratory bird new for preservation. What amount of ent? ext phase of development?			
Specification Section: Drawing No:  Request: (Limit or 1. Removal is tentativel 2. Some trees slated for damage/disturbance is a 3. Is erosion/expected to 4. Is standing water in or	Detail Note issue per RFI) Cost Impact:  ly scheduled for 3/30-5/1. Can the work be scheduled are within the RPZ of trees designated acceptable in these situations?  To be inspected until the next phase of developments.	Schedule Impact.  duled to avoid migratory bird new for preservation. What amount of ent? ext phase of development?			
Specification Section: Drawing No:  Request: (Limit or 1. Removal is tentativel 2. Some trees slated for damage/disturbance is a 3. Is erosion/expected to 4. Is standing water in or	Detail Note issue per RFI) Cost Impact:  ly scheduled for 3/30-5/1. Can the work be scheduced are within the RPZ of trees designated acceptable in these situations?  To be inspected until the next phase of development clearing area expected to be managed until the next phase.	Schedule Impact.  duled to avoid migratory bird new for preservation. What amount of ent? ext phase of development?			
Specification Section: Drawing No:  Request: (Limit or 1. Removal is tentativel 2. Some trees slated for damage/disturbance is a 3. Is erosion/expected to 4. Is standing water in or	Detail Note issue per RFI) Cost Impact:  ly scheduled for 3/30-5/1. Can the work be scheduced are within the RPZ of trees designated acceptable in these situations?  To be inspected until the next phase of development clearing area expected to be managed until the number of this portion of work from the Project expected.	Schedule Impact.  duled to avoid migratory bird new for preservation. What amount of ent? ext phase of development?			

#### Response:

- Yes, the project schedule is somewhat flexible as it pertains to the S-22 Tree Removal work. MWH Constructors
  is open to beginning and completing the tree removal work prior to the migratory bird nesting season.
- Project work is limited by the disturbance limits and tree protection fencing. As long as the work occurs inside of those boundaries it is acceptable.
- It is the contractor's responsibility to ensure that no visible or measurable sediment leaves the project site regardless of the duration between phases.
- Standing water exists from time to time in the disturbance area. It is the contractor's responsibility to ensure that no
  visible or measurable sediment leaves the project site.
- MWH Constructors' estimate of the S-22 Tree Removal work is between \$100,000 to \$200,000.



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

A	
	12/09/2019
Owner's Representative	Date

The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.

cc: File,CM,Sr. Inspector,Site Inspector,



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

# REQUEST FOR INFORMATION

Project Name:	Corrosion Control Improvements Proj	ect	
Date:	December 3, 2019	RFI Number:	012
Contractor:	MWH Constructors, Inc.	P.O. / Contract Number:	30006839
Address:	370 Interlocken Blvd. Suite 400	Ordinance Number:	188621
City, State, Zip	Broomfield, CO 80021	Contract Date:	April 23, 2019
Attn:	Ben McGeachy	Project Number:	W02190
	•	-	
Contractor requests info	rmation for the reason checked below: (Che	ock one box only)	
Clarification of Design			
Change for Contracto			
_			
A response to this inform	mation request is requested by: 12/9/19	(Month Day, Year)	
Subject:	Intent of 90% Documents		
Specification Section:	90% Documents		
Drawing No:	90% Documents Deta	il No:	
Request: (Limit or	ne issue per RFI) Cost Impact:	Schedule Impact.	
O1: Part 3.2 of Specific	cation 02 22 00 (Site Conditions Survey) rec	nuires significant pre and post topogr	aphic surveying of
	glands. Please confirm this is the intent of t		apine surveying or
	,		
	ication 02 61 00 (Removal and Disposal of		
	asbestos. The notes on the drawings indica		
asbestos. Is asbestos ex	spected on the coatings of Conduit 3 only? (	Conduit 4 only? Both Conduits 3 and	4?
O2: Dort 1 1 Itam A of	Specification 22 00 22 (LDVAC Instrument	stion and Controls) makes reference	to an "anistina fire
	Specification 23 09 23 (HVAC Instruments on firm if there is, or is not, an existing fire a		to an existing life
alariii palici . I icase co	minim it dicte is, or is not, an existing fire a	ain that we are to the into.	
O4: Part 1.2. Item A of	Specification 23 09 23 (HVAC Instrument	ation and Controls) states that Contra	ctor is to design
-	alarm system as indicated. We find no detail	•	_
Please clarify.	-		,
	VAC Sequence of Operation) references a "	Carbon Dioxide Monitoring System	by I&C". Please
provide a specification i	for the desired CO2 monitoring system.		
O6: Detail C-132 calls	for the use of base aggregate for the gravel	areas on Drawing C-2 (Horizontal C	ontrol and Paving
	lies more of a cobble material. Please confi		
ramy. The drawing map	nes more of a cocole manerial. I reaso com	im ouse aggregate is the michael in	
Q7: Note 2 on Drawing	g L-4 (Seeding Plan) states Owner will prov	ide seed. Please confirm PWB will j	provide all
required seed mixes.			
Contractor's Represen	ntative Date	•	



1120 SW 5th Avenue, Room 600 Portland, Oregon 97204-1926 Information: 503-823-7404 www.portlandoregon.gov/water



An Equal Opportunity Employer

#### Response:

Q1: Significant pre and post topographic surveying of the site and surrounding lands is not required.

Q2: The coating on only Conduit 4 is expected to contain asbestos.

Q3: Item A of Specification 23 09 23 has been deleted. There are no duct smoke detectors required in this project's HVAC systems.

Q4: Section 23 09 23 is being modified to incorporate a fire sprinkler system. A new specification for the alarm and sprinklers is being developed.

Q5: Provide ATI model #D121R.

Q6: Base aggregate is the intended material- see specification 32 11 23. The area around the existing antenna was erroneously hatched and this area will not be re-graded.

Q7: The Owner will provide seed mixes as indicated.

Owner's Representative	Date
Jan 1	12/18/2019

The response to this request by the Owner's representative shall not be construed as direction or advice on the method or manner of performing any work under the contract. The Owner's response does not relieve the Contractor of any of the risks or obligations under the Contract. The Owner's response constitutes a Field Order pursuant to Section 00140.30 of the 2010 City of Portland Standard Construction Specifications.

cc: File,CM,Sr. Inspector,Site Inspector,

No.	Originator	Document Reference	Description	Reference Infomation	Notes	
no	origin	docs	desc	refs	Notes	
01		E-9, E10, E-13, E-16 and E-18.	E-9 - Delete all the "J" labeled vaults E-10- Delete all the "J" labeled vaults E-13 - Delete all the "J" labeled vaults E-16 – increase size of "J" vaults they are incorrectly shown diagrammatically on scaled sheet. They are actually 36" long E18 – Delete all the "J" labeled vaults	N/A		
02	IRFILITZOI	02 22 00 Site Conditions Survey	Pre- and post- construction topographic surveying is not required	RFI 012 Response (12/18/2019)		
03	RFI 012 Q2	02 60 00 Removal and Disposal of Contaminated Media	Only Conduit 4 coating is expected to contain asbestos	RFI 012 Response (12/18/2019)		
04	RFI 012 Q3	23 09 23 HVAC I&C	No duct smoke detectors required	RFI 012 Response (12/18/2019)		
05		23 09 23 HVAC I&C Fire alarm specification tbd Fire sprinkler specification tbd	Provide fire sprinkler system	RFI 012 Response (12/18/2019)	Excluded, in o	wners allowance
06		GH-4 HVAC Sequence of Operation I&C spec TBD	Provide CO2 monitor ATI modle #D12R	RFI 012 Response (12/18/2019)		
07		Detail C-132 C-2 Horizontal Control and Paving Plan	Base aggregate is the intended material- see specification 32 11 23. The area around the existing antenna was erroneously hatched and this area will not be re-graded.	RFI 012 Response (12/18/2019)		
08	RFI 012 Q7	L-4 Seeding Plan	The Owner will provide seed mixes as indicated.	RFI 012 Response (12/18/2019)		
09		26 05 43 - Underground Ducts and Raceways for Electrical Systems	Revise Section 26 05 43 as follows: DELETE requirement in 2.3A that ducts and conduits shall not be less than 4-inch trade size. Duct banks shall utilize direct-buired rigid non-metallic conduit			
10	Designer	E-2	Provide separate power and control handholes for H1, H3, H4 & H5			

90% Design Clarifications and Changes

2/3


No.	Originator	Document Reference	Description	Reference Infomation	Notes
11	Designer	09 96 00 - Protective Coating	Revise section 09 96 00 as follows: DELETE requirement in 3.21.A to coat non-ferrous piping (e.g. PVC piping).		
12		09 96 00 - Protective Coating	Change requirement for coating valve vault (System 211 - Buried concrete coating) to "a.Apply two coats of CO-MA-Seal CM exterior vault coating to walls at a rate of 175 sq ft/gallon or equivalent"		
13		09 96 00 - Protective Coating	ADD to 3.18 Coating System Schedule, Ferrous Metal - Not Galvanized: FM-2: All Pipes and appurtenances inside vaults: Surface Prep shall be commercial blast cleaning SSPC SP 6/NACE 3, System No. 5 - Epoxy Mastic. System 5 - Epoxy Mastic shall be aluminum pigmented, high-solids mastic. VOC Content limit - 88 g/L. Prime and finish coat shall be Carboline Carbomastic 15, total system shall build to 7 to 10 mils DFT.		
14	Designer	26 29 23 Variable Frequency Drives	Variable Frequency Drives shall be Schneider/Square -D ATV 630, with 6-pulse width modulation. VFDs shall be mounted inside the MCC.		
15	Designer	26 24 19 Motor Control Centers, E-7	MCC shall be generally as shown in the attached quotation, with general arrangement as shown in revised drawing E-7.	MCC Information, PWB_CCIP-E7.pdf	
16	Designer	40 91 00 Process Control and Instrumentation	Point-to-Point diagrams prepared by the System Integrator, as required under 40 91 00 shall follow the example attached to this document	Example Wiring Diagram	
17	Designer	26 05 33 Raceways and Boxes for Electrical Systems	Conduit requirements shown in 26 05 33 3.1B.1 Table A shall be replaced with a requirement to meet NEC.		
18	Designer	E-25, E-26, E-27, E-28, E- 57	Teniare nower conditii schedilles wiin revised speels	Cable and Conduit Schedules (E-25, E-26, E-27, E-28, E-57)	
19	Designer	ESC-1, -2, -3, -4, -5	Replace erosion and sediment control sheets with revised drawings.	CCIP_ESC-15.pdf	
20	PWB	Section 00 73 16	ADD new Section 00 73 16 - Insurance Requirements	Section 00 73 16	
21	PWB	Various	This project will include Water Infrastructure Finance and Innovation Act (WIFIA) funding. The Contractor is required to comply with all applicable WIFIA statutes and regulations and any additional terms and conditions imposed by EPA in connection with WIFIA funding for the Project.		
22		Various	All communications are to be between the Contractor and the Owner's Representative. This overrides any references in the Specifications that the Contractor is to communicate directly with the Engineer.		
23		Various	All QC inspections are to be by owner. This overrides any references in the specifications about QC inspection by the Contractor		
24		E-57, E-59	Revise conduit routing for owner-provided security cameras as shown on revisions to Sheets E-57 and E-59	Drawing Revisions - Security.pdf	
25		G-6, C-4	Add a buried gate valve and check valve at the connection of the utility water supply pipng to Conduit 3, similar to the valve shown at the connections to Conduits 2 and 4.		
26		GC-5	Chain link fence (Standard Detail W-700) shall have top and bottom rail as required by Specification 32 31 13.		

90% Design Clarifications and Changes

# 2/25/2020

No.	Originator	Document Reference	Description	Reference Infomation	Notes
27		GL-1	Planting Note 7: Change to "Mitigation Planting areas shall have invasive species management and removal throughout the entire mitigation area, in particular clear within 10' of all new tree and shrub planting."		
28		M-4	Add note to 1/2" AIR piping continuity break on left side of page: "Route air piping through existing building to existing air compressor in existing truck unloading room, and connect to existing discharge piping."		
29		C-4	Rerouting of exisitng C3 sample vault sample 1.5" sample line ("SL") no longer required. This vault does not exist, nor does the piping.		
30		C-13	Add installation of an Oldcastle Infrastructure 504-LA vault at the connection of the 12" CWS line on Conduit 2.		
31		C-10	Replace butterfly valves with gate valves at the CWS connection to C2 and C4.		
32		M-3	The Combination air/vac valves are size 1".		
33		C-4	4" SEW (drain line from chemical building sink) to be PVC type PV02. Add CLSM backfill for cross contamination prevention where it crosses other pipe (10' in either direction).		
34		C-4	Use a catch basin instead of MH at location A2 for the SDR line heading north.		
35		C-2	Add four "no parking" signs.		
36		C-2	Reduce width of access gates to 14' (instead of 20').		
37		C-4	Delete the fire hydrant shown south of the paved area add a 6" replacement backflow preventor.		
38		C-6 and C-7	Add 2 trench plugs above Lusted Rd., and 3 Below Lusted Road. 5 total.		
39	PWB		Contractor to provide information requested in the PWB Equipment Schedule Template for each piece of equipment installed.	Equipment Schedule Template	
40		C-4	Swich PEX AA pipe to braided PVC tubing.		
41	PWB	P-1	Underslab SEW and CDR piping shall be PVC type PV02.		
42	PWB	00 73 00	Incorporate PWB Guidelines for Utility Protection into contract documents.	PWB Guidelines for Utility Protection	
43	PWB	M-drawings	All Underslab CWS, CDS and NAC piping shall be type PE05.		
44	PWB	31 30 00	Earthwork Compaction Requirements - Add decompaction of undeveloped areas once the infrastructure is developed. Anywhere that is not covered with concrete and is going to be vegetated should be decompacted to a minimum depth of 18" to assist in establishment of vegetation. In addition, these areas should be comprised of no more than 10% rock, branches or other non-soils.		
45	PWB	M-8, M-9, M-10, M-11	All penetrations through Chemical Building floor to be in accordance with Detail M- 130.		
46	PWB	32 91 13	Incorporate PWB Intergrated Vegetation Management Plan into the contract documents.	PWB Integrated Vegetation Management Plan	

90% Design Clarifications and Changes





# Attachment 1 Portland Water Bureau Corrosion Control Improvements Project - RISK REGISTER



	Sees Sees	land for	Manual Salar	Orac Orac	David David	See See	Sua Sua	See See	Dana Dana		Date:	13-Apr-20	Manual Faire	Manual Fator			Ome Ome	U
Manual Ency	Urap Down	Marcia Litry	Manual Entry	Urop uown	Drop Down	brop bown	brop bown	Drop Down	Drop Down	Auto	Auto	Manual Lifery	Manual Entry	Manual Entry	Auto	Auto	Urop Down	Manual Lifety
		Risk Identification Information						Qualitative Analy	sis (Pre-miti	gation)			Quant	itative Analy:	sis (Pre-Mitig	ation)		Risk Response
Risk ID	Status	Risk Description	Date Identified	Risk Owner	Risk Category	Funding Category	Probability of Occurrence (Pre)	Cost Impact	Schedule Impact	Risk Score	Risk Rating	Probability % (Pre)	Cost Impact Most Likely	Schedule Impact Most Likely (Weeks)	Schedule Impact Minimum (Weeks)	Schedule Impact Maximum (Weeks)	Impacts Critical Path?	Proposed Response/Mitigation
1	Mitigated	Project Site involves working within a constrained site. Which means construction must avoid unplanned	Aug 29, 2019	MWH	Construction	Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	0wk	Owk	1wk	Yes	Manage Construction Site and Logistics. Using just in time delivery method
2		Impacts to adjacent habitat. Thus Possible cost impacts could occur due to logistics  Do to smaller sized subcontracts and the volume of work in the area. It may be difficult to achieve completion of each subcontractors scope of work through the punch list and final acceptance of the work.	Aug 29, 2019	MWH	External	Enhancements Management Reserve	36%-65%	\$25,001 - \$50,000	>1-2 weeks	6	Moderate	50%	\$ 45,000	2wk	1wk	2wk	No	Monitor the progress of the work subcontractors work. Also provide cost incentives to complete work.
3	Mitigated	Complexity Associated with the switch over from existing chemicals to new chemicals transition.	Aug 29, 2019	Shared	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	0wk	Owk	1wk	No	Close coordination with the owner to best achieve a smooth transition from the old Chemical treatment to the new chemical treatment
4	Mitigated	Characteristics of existing geotechnical conditions on steep hill/Lusted Road Crossing possible soil stability Issues.	Aug 29, 2019	Shared	Environmental	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	Yes	Perform additional Geotechnical investigation, Review means and methods for Utilidor Line installation
5	Mitigated	Dewatering requirements for the CCIP Chemical Utilidor Piping Conduit require dewatering over and above those costs included in the MWH cost estimate.	Aug 29, 2019	MWH	Environmental	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$	Owk	Owk	1wk	No	Perform Utilidor Line installation in dry season as much as possible. Price Dewatering system conservatively. Provide an Allowance
6		Dewatering requirements for the CCIP Utility Water Pump Station excavation require dewatering over and above those costs included in the MWH cost estimate.	Aug 29, 2019		Environmental		0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ .	0wk	Owk	1wk		Perform Utility Pump Station excavation in dry season as much as possible. Price Dewatering system conservatively. Provide an Allowance
7	Mitigated	Contract Documents do not contain any requirements for Cathodic Protection for piping and equipment. It required additional cost could be incurred.	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	φ.	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
8	Active	The field of qualified contractors is limited due to the volume of construction work and the location of the project site, effectively limiting competition, and increasing project costs"	Aug 29, 2019	Shared	Procurement	Market Conditions Adjustments	36%-65%	\$50,001 - \$100,000	>2 - 4 weeks	9	Significant	65%	\$ 100,000	4wk	2wk	4wk	Yes	Proactively manage the bid packaging and procurement process
9	Mitigated	Asbestos removal is referenced in Conduit 4 (see Specification 026100). This Scope of Work is not well defined and not included in the 60% Cost Estimate.	Aug 29, 2019	MWH	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	·	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
10	Mitigated	As the design is at 60%. There is a potential for Design Progression/Scope Creep as the design moves forward to 90% and 100% design completion.	Aug 29, 2019	Shared	Design	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
11	Mitigated	Receipt of the Land Use Permit delays construction by an indeterminate number of days.	Aug 29, 2019	PWB	Regulatory	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Monitor the Progress of the Land Use Permit
12	Mitigated	Unexpected Sub-surface conditions are discovered	Aug 29, 2019	PWB	Environmental	Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	·	0wk	Owk	1wk	Yes	Perform additional Geotechnical evaluations and testing. And/or provide an allowance item to budget for costs incurred
13	Active	Concerns regarding the ability to find qualified and capable I&C Integrators to perform the Scope of Work required for the project.	Aug 29, 2019	Shared	Procurement	Market Conditions Adjustments	11%-35%	\$10,001 - \$25,000	>2 - 4 weeks	4	Moderate	25%	\$ 25,000	3wk	2wk	4wk	No	Proactively manage the bid packaging and procurement process
14	Mitigated	Delays to the completion of pipelines required to fully commission the CCIP impacts the Substantial Completion Milestone creating a need to treat water for compliance via alternate means to fulfill the requirements for Substantial Completion dates.	Aug 29, 2019	MWH	Environmental	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$	0wk	Owk	1wk	Yes	Proactively monitor and manage the progress of the pipelines
15	Mitigated	Early work packages are delayed due to permitting and or deferred submittal requirements imposed by City of Portland, PWB, Multnomah County, or other permitting agencies	Aug 29, 2019	PWB	Organization	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	· •	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
16		As indicated in MWH's Construction Schedule, it will be necessary for the PWB operations team to work in and around an active construction site to accomplish the goal of operating facilities by the contractual Milestone date. Given that this is an active construction site, there is an increased risk for injury to the PWB operators (compared to normal working conditions).	Aug 29, 2019	Shared	External	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$	Owk	Owk	1wk	No	Open and productive communications between operators and CM/GC to make the project team aware of ongoing coordination needed on the project site.
17	Mitigated	The security system has not been defined for the CCIP. Therefore the requirements for security elements was (and is unknown). There is a risk that the scope (and associated costs and schedule) for the desired Improvements exceeds what was included in the MWH Cost Estimate.	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	>2 - 4 weeks	2	Minimal	0%	\$ -	Owk	2wk	4wk	No	Provide project documents that define the required Scope of Work
18	Active	Conduits cannot be completely isolated and shut off. Requiring that flow be managed while work is performed on the Conduits	Aug 29, 2019	PWB	External	Risk	36%-65%	\$10,001 - \$25,000	>2 - 4 weeks	6	Moderate	50%	\$ 25,000	3wk	2wk	4wk	Yes	identify issues related to isolation early in construction. So if required alternative means to isolate the lines can be discussed, evaluated and determined.
19	Mitigated	Disinfection of Conduits requires more then local spray disinfection at conduit tap locations	Aug 29, 2019	Shared	Regulatory	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
20		Additional geotechnical investigations to be conducted along the utility corridor to identify conditions not anticipated in the Cost Estimate. This may creating changes to the Utility Corridor pipe installation.	Aug 29, 2019	PWB	Environmental	Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	us	Owk	Owk	1wk	No	Perform additional Geotechnical evaluations and testing. And/or provide an allowance item to budget for costs incurred
21	Active	The bid packaging requirements of this project, have the potential for failure or poor performance of a subcontractors. While it is difficult to estimate the magnitude of impact, some allowance should be created for the predictable occurrence of this risk.	Aug 29, 2019	Shared	Procurement	Market Conditions Adjustments	36%-65%	\$50,001 - \$100,000		9	Significant	50%	\$ 100,000	5wk	4wk	6wk	Yes	Provide an Allowance to budget for costs incurred
22	Active	Risk to meeting schedule milestones due to lack of availability of contractors, labor and resources.	Aug 29, 2019	Shared	Procurement	Risk	36%-65%	\$25,001 - \$50,000	>4 - 6 weeks	9	Significant	50%	\$ 40,000	5wk	4wk	6wk	Yes	Proactively manage the bid packaging and procurement process
23	Mitigated	Risk of unforeseen environmental site conditions that could range from new presence of threatened and endangered species, contaminated soil, or archeological finds. The risk response or remediation would depend on the character of the actual occurrence.	Aug 29, 2019	PWB	Environmental	Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	N	Enter Impact Values	0%	vs	Owk	Owk	1wk	No	Provide an Allowance in the Cost Estimate/GMP to budget for costs incurred
24	Mitigated	Risk that Escalation of labor, equipment, and materials may exceed the 3 percent allowance, and could increase the actual cost of construction.	Aug 29, 2019	PWB	Procurement	Market Conditions Adjustments	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	· Ф	Owk	Owk	1wk	No	Provide an Allowance to budget for costs incurred
25	Mitigated	Architectural design development could change design assumptions made in 60% design documents.	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
26	Mitigated	Utility Trench Cut-off walls are not defined in the design. MWH Cost Estimate includes cut-off walls at 100 foot intervals	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
27	Mitigated	Weather delays, delay progress of construction and require exercising the coverage of the Builder's Risk Policy to cover delays and damaged works.	Aug 29, 2019	Shared	Environmental	Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	Yes	Provide an Allowance in the Cost Estimate/GMP to budget for costs incurred
28	Mitigated	Risk that equipment pricing could change due to procurement policies, terms and conditions and specific requirements of the project (general conditions which have not been provided).	Aug 29, 2019	PWB	Procurement	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
29	Mitigated	Utility Trench pipe zone material is not defined. MWH Cost Estimate includes sand. If sand is not acceptable additional cost will be incurred.	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
30	Active	The Lusted Road Pipe Crossing Scope of Work is not defined.	Aug 29, 2019	PWB	Design	Facility Enhancements	36%-65%	\$50,001 - \$100,000	>4 - 6 weeks	9	Significant	50%	\$ 50,001	5wk	4wk	6wk	Yes	Provide project documents that define the required Scope of Work
31	Active	Construction in and adjacent to residential areas could create a need for benefits for the adjoining residual properties, to sustain public support for the project. The City should consider budgeting an allowance for this potential added cost	Aug 29, 2019	Shared	Environmental	Allowance Item	36%-65%	\$10,001 - \$25,000	<=1 week	3	Minimal	40%	\$ 10,001	1wk	1wk	1wk	No	Provide an Allowance in the Cost Estimate/GMP to budget for costs incurred
32	Active	Observation access Unknown existing utilities or facilities, there is some risk of additional costs for relocation or repair of existing utilities:	Aug 29, 2019	PWB	External	Allowance Item	36%-65%	\$25,001 - \$50,000	>2 - 4 weeks	6	Moderate	40%	\$ 25,001	3wk	2wk	4wk	No	Provide an Allowance in the Cost Estimate/GMP to budget for costs incurred
33	Mitigated	Coating Specification 09 96 00 does not appear to be specific to the CCIP Project. If MWH's cost estimate assumptions are not correct additional costs could be incurred.	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
34	Mitigated	Ductbank sections shown on E-38 are included in the MWH's cost estimate as minimum code required	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
35	Mitigated	trench's and depths.  MWH's Cost estimate includes Reasonably Anticipated Scope (RAS). These items need to be further defined	Aug 29, 2019	PWB		Facility Enhancements	0%-10%	\$0 - \$10,000 Page 1 of 3	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work



# Attachment 1 Portland Water Bureau Corrosion Control Improvements Project - RISK REGISTER



											Date:	13-Apr-20						
Manual Entry	Orap Down	Manual Citry	Manual Entry	Drop Down	Drop Down	Drop Down	Drop Down	Drop Down	Orop Down	Auto	Auto	Manual Entry	Manual Entry	Manual Entry	Auto	Auto	Drop Down	Manual Entry
		Risk Identification Information						Qualitative Analy	sis (Pre-miti	gation)			Quant	tative Analy	sis (Pre-Mitig	ation)		Risk Response
Risk ID	Status	Risk Description	Date Identified	Risk Owner	Risk Category	Funding Category	Probability of Occurrence (Pre)	Cost Impact	Schedule Impact	Risk Score	Risk Rating	Probability % (Pre)	Cost Impact Most Likely	Schedule Impact Most Likely (Weeks)	Schedule Impact Minimum (Weeks)	Schedule Impact Maximum (Weeks)	Impacts Critical Path?	Proposed Response/Mitigation
36	Mitigated	Requirements and locations for injection and sample vaults not clearly defined. Requirements for valve vaults need to be refined.	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
37	Mitigated	MWH cost estimate includes a auxiliary building for controls and compressor. The cost estimate includes installing the building, but assumes foundation is accounted for with the silo slab	Aug 29, 2019	PWB	Design	Facility Enhancements	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
38	Active	Electrical and I&C requirements are not clearly defined.	Aug 29, 2019	PWB	Design	Facility Enhancements	66%-90%	100,001 - \$250,000	>6 - 8 weeks	16	Severe	67%	\$ 115,001	8wk	6wk	8wk	Yes	Provide project documents that define the required Scope of Work
39	Mitigated	MWH's cost estimate and contingency excludes tariffs that are related to materials	Aug 29, 2019	PWB	Procurement	Market Conditions Adjustments	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	Owk	1wk	1wk	No	Provide an Allowance to budget for costs incurred
40	Active	The existing water conduits are old and are installed utilizing Lock-Bar pipe with riveted joints. Making potential damage to the existing conduits more challenging and difficult.	Aug 29, 2019	Shared	Construction	Risk	36%-65%	\$0 - \$10,000	>1-2 weeks	3	Minimal	33%	\$ 10,000	2wk	1wk	2wk	Yes	Pre Plan the work and perform due diligence to ensure damage does not occur to the existing conduits.
41	Mitigated	Quality inspections and testing is not defined by the project documents inspection.	Aug 29, 2019	PWB	Design	Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact	0%	\$ -	0wk	Owk	1wk	No	Provide an Allowance in the Cost Estimate/GMP to budget for costs incurred
42	Mitigated	Work hours are restricted due to noise ordinances or other public issues that constrain working hours.	Aug 29, 2019	MWH	Construction	Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ -	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
43	Mitigated	MWH's Cost Estimate assumed 7 AM to 5 PM.  Submittal review is delayed beyond the 20-to 30 day period assumed in MWH's schedule and cost estimate.	Aug 29, 2019	Shared	Design	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact	0%	\$ -	0wk	Owk	1wk	Yes	Project Team to coordinate and schedule timely submittal review
44	Mitigated	Functional Acceptance and Performance Test duration exceeds 40 days, assumed by the MWH cost estimate.	Aug 29, 2019	Shared	Construction	Enhancements Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact	0%	\$ -	0wk	Owk	1wk	Yes	Provide project documents that define the required Scope of Work
45	Mitigated	Chemical costs have not been included in the MWH Cost Estimate.	Aug 29, 2019	PWB	Design	Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact	0%	\$ -	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
46	Mitigated	Commissioning requires over-time, and/or exceeds the assumed commissioning time in the cost estimate.	Aug 29, 2019	MWH	Construction	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	Owk	Owk	1wk	Yes	Provide project documents that define the required Scope of Work
47	Mitigated	Formal training needs by the PWB extends beyond Substantial Completion.	Aug 29, 2019	PWB	Organization	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	0wk	Owk	1wk	No	Provide project documents that define the required Scope of Work
48	Mitigated	Equipment training may be required beyond Substantial Completion.	Aug 29, 2019	PWB	Organization	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ .	0wk	Owk	1wk	Yes	Provide project documents that define the required Scope of Work
49	Mitigated	Training requires training more than two shifts of operators. MWH's cost estimate assumes all process and	Aug 29, 2019	PWB	Organization	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
50	Mitigated	vendor training can occur in a single operator shift. PWB requires professional videography of training and commissioning, which is not included in the MWH	Aug 29, 2019	PWB	Organization	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
51	Mitigated	cost estimate.  Reinforcing steel densities exceed the assumptions of the MWH Cost Estimate (275lbs/CY).	Aug 29, 2019	PWB	Design	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
52	Mitigated	Rock excavation is required (and none is included in baseline estimate).	Aug 29, 2019	PWB	Environmental	Enhancements Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	Owk	Owk	1wk	Yes	Provide an Allowance in the Cost Estimate/GMP to budget for costs
53	Mitigated	MWH's cost estimate assumed minimal impacts for extended weather delays that are not covered by	Aug 29, 2019	Shared	Environmental	Allowance Item	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ -	Owk	Owk	1wk	Yes	incurred Provide an Allowance in the Cost Estimate/GMP to budget for costs
54		builder's risk insurance policy. PGE Power requirements are not clearly defined at this time to accurately estimate the cost.	Aug 29, 2019	PWB	Design	Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	\$ .	Owk	Owk	1wk	No	incurred Provide project documents that define the required Scope of Work
55	Mitigated	Heat tracing on piping and chemical tanks exceeds what is included in the Cost Estimate.	Aug 29, 2019	PWB	Design	Enhancements Facility	0%-10%	\$0 - \$10,000	<=1 week	NIL	Values Enter Impact	0%	s .	Owk	Owk	1wk	No	Provide project documents that define the required Scope of Work
56	Active	Maintaining operations of the existing facilities at all times while construction is ongoing.	Aug 29, 2019		Regulatory	Enhancements Facility	11%-35%	\$0 - \$10,000	>1-2 weeks	2	Values Minimal	35%	\$ 11,395	1wk	1wk	2wk	No	Open and productive communications between operators and
						Enhancements												CM/GC to make the project team aware of ongoing coordination needed on the project site. Develop Maintenance of Plant Operations (MOPO) procedures that minimize impacts to the plant
57		Current cost for offsite warehouse and employee transportation and parking may be inadequate	Aug 29, 2019	мwн	External	Risk	0%-10%	\$0 - \$10,000	<=1 week	NIL	Enter Impact Values	0%	\$ .	Owk	Owk	1wk	No	include in the Cost Estimate a value for offsite warehouse, transportation and parking that is negotiated and reasonable.
58	Active	Managing and Administration of Multiple Small Business and Minority Enterprise Contracts	Aug 29, 2019	MWH	Project Management	Market Conditions Adjustments	36%-65%	\$10,001 - \$25,000	<=1 week	3	Minimal	50%	\$ 25,000	1wk	1wk	1wk	Yes	Proactively manage the bid packaging and procurement process
64	Active	Coronavirus - Employee Health and Safety - Physical and Mental well being and its affects on the labor force. Anxiety, absenteeism, quarantine, lack of specialty work force and decline in production. Due to lost access to the anticipated workforce caused by mandatory quarantines, lack of childcare or eldercare, or sickness.	Mar 16, 2020		Regulatory	Risk	66%-90%	\$25,001 - \$50,000			Worst Case	67%	\$ 50,000	Swk	Swk	40wk	Yes	Communicate and educate employees on the current CDC requirements and recommendations. Institute shift work to reduce men per required per shift and promote social distancing. Pre-shift planning meeting conducted to ensure safety and compliance with current COVID recommendations to promote "Flattening the Curve". Developed Covid 19 response team that meets daily to ensure compliance with covid 19 mitigation efforts and evaluates steps forward to ensure employee safety.
65	Active	Coronavirus - Potential delay in production due to social distancing of split or multiple shifts causing a strain on resources.	April 10,2020	MWH	Regulatory	Risk	36%-65%	\$10,001 - \$25,000	>4 - 6 weeks	9	Significant	50%	\$ 15,000	4wk	4wk	6wk	Yes	MWH may evaluate possible incentives to pay or extend hours of work. Flexible crew sizing and start times/hours to reduce
66	Active	Coronavirus Additional Safety Plan Requirements due to State or Federal Rqmts.	April 10,2020	MWH	Regulatory	Risk	36%-65%	\$10,001 - \$25,000	>4 - 6 weeks	9	Significant	50%	\$ 20,000	4wk	4wk	6wk	Yes	personnel on site at one time. Project Team to have active and clear communication and monitoring of dynamic situations associated with COVID-19 as it relates to potential State and Federal requirement changes
67	Active	Coronavirus - General and overall impacts to the project	Apr 10, 2020	Shared	External	Risk	36%-65%	\$25,001 - \$50,000	>6 - 8 weeks	12	Significant	67%	\$ 40,000	6wk	6wk	8wk	Yes	requirement charges  Working together as a team to review ALL the Covid 19 associated  impacts to the project. Weekly we will review any and all possible  impacts. Monthly review the Risk potential and mitigations efforts.
68	Active	Coronavirus - Direct impacts to Owner/Engineer Key Personnel where key players become ill or are unable to work due to FMLA or other	April 8 2020	PWB	External	Risk	36%-65%	\$10,001 - \$25,000	>4 - 6 weeks	9	Significant	50%	\$ 10,000	4wk	4wk	6wk	Yes	Implement PWB/Stantec checks for employees before reporting for work. PWW/Stantec working to ensure social distancing measures are followed. PWB/Stantec to provide additional PPE. Implement social distancing measures for those working closely together in tasks. PWB/Stantec to adjust staff sizing and durations as need to achieve the Covid 19 mitigation measures.
69	Active	Coronavirus - Direct Impacts to MWH Key Personnel where key players become ill or are unable to work due to FMLA or other	April 8 2020	MWH	External	Risk	36%-65%	\$10,001 - \$25,000	>4 = 6 weeks	9	Significant	50%	\$ 10,000	4wk	4wk	6wk	Yes	implement MWH temperature checks for employees before reporting for work. MWH working to ensure social distancing measures are followed. MWH is providing additional PPE. Implement social distancing measures for those working closely together in tasks such as pipe fit and forming concrete concrete. MWH also working to adjust crew sizing and durations as need to achieve the Covid 19 mitigation measures.



# Attachment 1 Portland Water Bureau Corrosion Control Improvements Project - RISK REGISTER



Cost Impact TOTAL \$869,399


Risk Description  Risk Description  Oats Identified  Oats Open Description  Oats Impact Sink Rating Impact Sink Rating Impact Sink Imp								13-Apr-20	Date											
Risk ID Status Risk Description  Date identified Risk Punding Category Coursence (Pro)  Active Connection in the pool of available apprenticeship and/or journeyman level workers. Potential spyllation may determine that the risk of becoming effected is not worth the pay scale.  April 2, 2220 Mini Status Risk Description (Weeks)  April 2, 2220 Shared External Risk Status Risk Rating Status Risk Rating Probability of Cost Impact Simplest Risk Rating Probability Sort (Weeks)  April 2, 2220 Mini Status Risk Rating Probability of Cost Impact Simplest Risk Rating Probability Sort (Weeks)  April 2, 2220 Mini Status Risk Rating Risk Rating Probability Sort (Weeks)  April 2, 2220 Mini Status Risk Rating Risk Rating Risk Rating Probability Sort (Weeks)  April 2, 2220 Mini Status Risk Rating Ris	Manual Entry	,	Drop Down	Auto	Auto	Manual Entry	Manual Entry	Manual Entry	Auto	Auto	Drop Down	Drop Down	Drop Down	Drop Down	Drop Down	Drop Down	Manual Entry	Manual Entry	Drop Down	Manual Entry
Risk Description  Date Identified  Gwner  Category  Category  Category  Category  Category  Category  Cournence (Pre)  Active  Active  Conconavirus - Reduction in the pool of available apprenticeship and/or journeyman level workers. Potential applicants may determine that the risk of becoming infected in not worth the pay scale.  April 2, 2020  Minnt  April 2, 2020  Minnt  April 2, 2020  Minnt  April 2, 2020  Minnt  April 2, 2020  Shared  General Risk  364-65%  S10,001-\$25,0000  A-6 weeks  9 Significant  50%  S10,001-\$25,0000  A-6 weeks  9 Significant  50%  S10,001-\$25,0000  A-6 weeks  9 Significant  50%  S10,001-\$25,0000  Auk  Awk  Gwk  Yes  Minnt  Mi	Risk Response	Ris		ation)	sis (Pre-Mitig	itative Analy:	Quant			gation)	ysis (Pre-miti	Qualitative Analy						Risk Identification Information		
Coronavirus - Reduction in the pool of available apprenticethip and/or journeyman level workers. Potential applicants may determine that the risk of becoming infected is not worth the pay scale.  April 8 2020 Shared External Risk 36%-65% \$10,003 - \$25,000 N-4 6 weeks 9 Significant 50% \$ 5,000 4wk 4wk 6wk 7 session PWB best paratices for one Construction of Coronavirus - Changes in the law for what is considered Critical Infrastructure or Stoppages of work orders  72 Active Coronavirus - Termination by PWB due to Economic Hardridge which may lead to the Insulinity to Perform.  April 8 2020 PWB External Risk 56%-65% \$10,003 - \$25,000 N-4 6 weeks 9 Significant 50% \$ 13,000 4wk 4wk 6wk 7 ses Team to collaborate funding that may be for substitution to material pupily shortages - Due to reductions in work force or factory shutdowns. Leading to material supply shortages and higher cost. And slower project completion. Impacts to smaller subcontracting company defaults in the proof of available properties of the proof of available proof	oposed Response/Mitigation	Proposed R	Critical	Impact Maximum	Impact Minimum	Impact Most Likely			Risk Rating			Cost Impact					Date Identified	s Risk Description	Status	Risk ID
best practices for a Maria Score Majes  Coronavirus - Changes in the law for what is considered Critical infrastructure or Stoppages of work orders  72 Active Coronavirus - Termination by PWB due to Economic Hardship which may lead to the Inability to Perform.  73 Active Coronavirus - Material Joseph Score Majes  74 Coronavirus - Material Joseph Score Majes  75 Indian to color or Stoppages of work orders  76 Active Coronavirus - Material Joseph Score  77 Active Coronavirus - Material Joseph Score  78 Active Coronavirus - Material Joseph Score  79 Significant SOM \$ 13,000 4wk 4wk 6wk Ves Indians Indi	e to practice safe distancing measures that are in jects. Educating and working with local building he health and safety of the employees. Ensure tand no safety shortcuts will be tolerated as it stancing and other covid 19 mitigations efforts.	place on other projects. Educ trades to ensure the health a employees understand no saf		8wk	6wk	6wk	\$ 30,000	67%	Severe	16	>6 - 8 weeks	\$25,001 - \$50,000	66%-90%	Risk	External	MWH	Apr 10, 2020	Coronavirus - Reduction in the pool of available apprenticeship and/or journeyman level workers. Potentia	Active	70
Active Coronavirus - Material Delays and Shortages - Due to reductions in work force or factory shutdowns. Leading fittings.  Active Coronavirus - Material Delays and Shortages - Due to reductions in work force or factory shutdowns. Leading fittings.  Mar 16, 2020 MWH Regulatory  Risk 66%-90% \$10,001 - \$25,000 98 weeks 20 Worst Case 67% \$ 15,000 8wk 40wk Yes Whith to work closing the supply of material supply shortages and higher cost. And slower project completion. Impacts to steel, pipe valves and place in the pool of available place in the pool of available businesses are being driven out of work, causing company defaults  Active Coronavirus - Impacts to smaller subcontracting companies such as the reduction in the pool of available work through econom necessary. Administration of the coronavirus - Potential NTP Delay beyond June 15, 2020 Apr 8, 2020 PWB Procurement Risk 66%-90% \$10,001 - \$25,000 6-8 weeks 16 Severe 67% \$ 25,000 6wk 6wk 8wk Yes If project is delayed hadditional/electended project.	B by attending meetings to share nation wide construction craft employees measures related ajeure contract requirements are enacted. Enac	best practices for construction Covid 19. Force Majeure cont		6wk	4wk	4wk	\$ 5,000	50%	Significant	9	>4 - 6 weeks	\$10,001 - \$25,000	36%-65%	Risk	External	Shared	April 8 2020			71
to material supply shortages and higher cost. And slower project completion. Impacts to steel, pipe valves and fittings.  The supply of material phase true production in the pool of available to ensure production status of material del phase true	te for possible solutions to alter the schedule or se need to mitigate the impacts to the project	funding that may be need to delivery		6wk	4wk	4wk	\$ 13,000	50%	Significant	9	>4 - 6 weeks	\$10,001 - \$25,000	36%-65%	Risk	External	PWB	April 8 2020	Coronavirus - Termination by PWB due to Economic Hardship which may lead to the inability to Perform.	Active	72
D/M/W/ESB firms as many small businesses are being driven out of work, causing company defaults  work through econoministra financistra financial health ( run  75 Active Coronavirus - Potential NTP Delay beyond June 15, 2020 Apr 8, 2020 PWB Procurement Risk 66%-90% \$10,001 - \$25,000 >6 - 8 weeks 16 Severe 67% \$ 25,000 6wk 6wk 8wk Yes if project additional/extended project.	ing with suppliers to monitor and be proactive invalid supplies and manage from the submittal if procurement. MWH may increase factoritist ion and will report weekly and/or monthly the delivery to the team.	the supply of materials expect phase through final procurem		40wk	8wk	8wk	\$ 15,000	67%	Worst Case	20	>8 weeks	\$10,001 - \$25,000	66%-90%	Risk	Regulatory	МWН		to material supply shortages and higher cost. And slower project completion. Impacts to steel, pipe valves an		73
additional/extended project.	tractors to facilitate diminished work force and nomic hardships. Tailor work packages as strate duel payment checks. Also monitor un a D&B) of potential subcontracting firms.	work through economic hard: necessary. Administrate duel		40wk	8wk	8wk	\$ 30,000	67%	Worst Case	20	>8 weeks	\$25,001 - \$50,000	66%-90%	Risk	Regulatory	Shared	Mar 16, 2020			74
76 Active Companions Additional opposition from polishbors citing the gathering of construction workers as an Apr 10, 2020 Shared Regulatory Risk 36%-65% \$0.\$10,000 >4.6 weeks 9 Significant 50% \$ 5,000 4wk 4wk 6wk Yes Work to achieve appr	d MWH may reduce impact by working ed hours as allowed to reduce impacts to the	additional/extended hours as project.		8wk	6wk	6wk	\$ 25,000	67%	Severe	16	>6 - 8 weeks		66%-90%	Risk	Procurement	PWB	Apr 8, 2020	Coronavirus - Potential NTP Delay beyond June 15, 2020	Active	75
unnecessary risk to their own health;	pproval of flex hours or multiple shifts or reduce the number of personnel on the project	extended hours to reduce the		6wk	4wk	4wk	\$ 5,000	50%	Significant				36%-65%	Risk	Regulatory	Shared	Apr 10, 2020	Coronavirus - Additional opposition from neighbors citing the gathering of construction workers as an	Active	76
Coronavirus - Longer review penous from authorities having junisdiction (APU) such as state or uregon.	mmunications to expediting review deliverables is involved understand the deadlines required for	to ensure all parties involved		8wk	6wk	6wk	\$ 20,000	67%	Severe	16	>6 - 8 weeks	\$10,001 - \$25,000	66%-90%	Risk	Regulatory	PWB	Apr 10, 2020	Coronavirus - congen review periods from authorities maving jurisdiction (Arti) such as state or oregon,	Active	77

DICK DAT	TIME LECT	MD DICK	SCORE/	RISK RATING
KISK KAI		·MD = KISK	SCURF	KISK KATING


				,			
	PORTLAND				Impact		
	BUREAU		Minimal	Moderate	Significant	Severe	Worst Case
		Ratings	1	2	3	4	5
	Most likely won't happen	1	1	2	3	4	5
¥	Likely won't happen	2	2	4	6	8	10
Probability	May happen	3	3	6	9	12	15
ď	Very likely to happen	4	4	8	12	16	20
	Will most likely happen	5	5	10	15	20	25

Project-	Specific F	Risk Coding
From	То	Rating
0	3	Minimal
4	6	Moderate
8	12	Significant
15	16	Severe
20	25	Worst Case

obability of Occurrer	Probability %
Will not happen	0%
Most likely won't	0%-10%
happen	
Likely won't happen	11%-35%
May happen	36%-65%
Very likely to	66%-90%
happen	
Will most likely	90%-100%
happen	



Run Date: 04-May-20 Data Date: 30-Apr-20 Project ID: PWB 90% Page 1 of 6







	Orig Dur	Start	Finish	Total Float				202				2021
				1 IOGI	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct Nov Dec Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec
Valves and Fittings - Submittal MWH (S-16)	10	09-Oct-20	22-Oct-20	0								Pipe Valves and Fittings - Submittal MWH (S-16)
Valves and Fittings - Submittal MWH (M1)	10	09-Oct-20	22-Oct-20	0								Pipe Valves and Fittings - Supmittal MWH (M1)
trical MCC - Submittal MWH	10	23-Oct-20	05-Nov-20	80	ļi				i			Electrical MCC - Submittal MWH
sformer - Submittal MWH	10	23-Oct-20	05-Nov-20	60								Transformer - Submittal MWH
nersible Pumps (Utility Water) - Submittal MWH	10	23-Oct-20	05-Nov-20	38								Submersible Pumps (Utility Water) - Submittal MWH
a As h Metering Pumps - Submittal MWH	10	23-Oct-20	05-Nov-20	40	1							Soda Ash Metering Pumps - Submittal MWH
p Pumps - Submittal MWH	10	23-Oct-20	05-Nov-20	58	1							Sump Pumps - Submittal MWH
	86	06-Aug-20	07-Dec-20	95								
ast Vaults - Engineer Review	14	06-Aug-20	25-Aug-20	0								Vaults - Engineer Review
Valves and Fittings - Engineer Review (S-17)	14	07-Aug-20	26-Aug-20	9	1							lves and Fittings - Engineer Review (S-17)
crete - Engineer Review	21	23-Oct-20	20-Nov-20	82	1		i		i		ipe valv	Concrete - Engineer Review
-				405			- 1	- 1	- 1			· · · · · · · · · · · · · · · · · ·
trical Enclosure (Building) - Engineer Review	21	23-Oct-20	20-Nov-20	105								Electrical Enclosure (Building) - Engineer Review
Valves and Fittings - Engineer Review (S-16)	21	23-Oct-20	20-Nov-20	0	ļ						 	
Valves and Fittings - Engineer Review (M1)	21	23-Oct-20	20-Nov-20	0								Fipe Valves and Fittings - Engineer Review (M1)
trical MCC - Engineer Review	21	06-Nov-20	07-Dec-20	80								Electrical MCC - Engineer Review
sformer - Engineer Review	21	06-Nov-20	07-Dec-20	60								Transformer - Engineer Review
nersible Pumps (Utility Water) - Engineer Review	21	06-Nov-20	07-Dec-20	38	1							Submersible Pumps (Utility Water) - Engineer Review
a Ash Metering Pumps - Engineer Review	21	06-Nov-20	07-Dec-20	40	1		i	į	i			Soda/Ash Metering Purhps - Engineer Review
p Pumps - Engineer Review	21	06-Nov-20	07-Dec-20	58	t		·		<del> </del>			Sump Pumps - Engineer Review
sterials Fabrication & Delivery	182	12-Aug-20	27-Apr-21	60								
System - Fab/Del	80	12-Aug-20	03-Dec-20	05	1							CO2 System - Fab/Del
-				85	1							<del>, , ,</del> , , , , , , , , , , , , ,
ast Vaults - Fab/Del	35	26-Aug-20	14-Oct-20	0					- 1	_		Precast Vaults - Fab/Del
Valves and Fittings - Fab/Del (S-17)	35	27-Aug-20	15-Oct-20	9	ļ							Piple Valves land Fittings - Fab/IDel (S-17)
al Building/Canopies - Fab/Del	60	08-Sep-20	01-Dec-20	60	1							Metal Building/Canopies - Fab/Del
a Ash System - Fab/Del	110	24-Sep-20	26-Feb-21	50							_	Soda Ash System - Fab/Del
crete - Fab/Del	1	23-Nov-20	23-Nov-20	63	1 :							I Concrete Fab/Det
trical Enclosure (Building) - Fab/Del	60	23-Nov-20	16-Feb-21	105	1							Electrical Enclosure (Building) - Fab/Del
Valves and Fittings - Fab/Del (S-16)	40	23-Nov-20	19-Jan-21	0	1							Pipe Valves and Fittings - Fab/Del (S-18)
Valves and Fittings - Fab/Del (M1)	40	23-Nov-20	19-Jan-21	0	·							Pipe Valves and Fittings - Fab/Del (M1)
trical MCC - Fab/Del	80	08-Dec-20	30-Mar-21	80	1							Electrical MCC - Fab/Del
	60		-	en	1							Transformer - Fab/Del
isformer - Fab/Del		08-Dec-20	02-Mar-21	00			İ					! ! ! <del> </del>
mersible Pumps (Utility Water) - Fab/Del	80	08-Dec-20	30-Mar-21	38				- 1	- 1			Submersible Pumps (Utility Water) - Fab/Del
a Ash Metering Pumps - Fab/Del	100	08-Dec-20	27-Apr-21	40	ļi		j.	<u> </u> -	i			Soda Ash Metering Pumps - Fab/Del
p Pumps - Fab/Del	60	08-Dec-20	02-Mar-21	58								Sump Pumps - Fab/Del
	358	02-Jul-20	24-Nov-21	0	:		!	!				
k	358	02-Jul-20	24-Nov-21	0								
nit Erosion Control Plan - Site Work	1	02-Jul-20	02-Jul-20	4	1		i	j.	Submit	Erosion (	Control Pl	An - Site Work
all Erosion Control Site- Site Work	5	06-Jul-20	10-Jul-20	4	1 :			- 1	■ Instal	II Erosion	Control	Site-Site Work
tain Erosion Control - Site Work	357	06-Jul-20	24-Nov-21	0	·							Maintain E
all Temp Construction Utilities (Water, Sewer and Power)	5	13-Jul-20	17-Jul-20	74	1				□ Int	tall Temp	Constru	ubtion Utilities (Water, Sewer and Power)
Il Construction Entrance & Wheelwash	_			64	1		i		- 1	-	: :	
	5	13-Jul-20	17-Jul-20					-	□ IN\$	į	į	Entrance & Wheelwash
ove Tree Stumps	10	20-Aug-20	02-Sep-20	31			-					vie Tree Stumps
elop Onsite Staging Area - Site Work	10	27-Aug-20	10-Sep-20	26					<u></u>		<del>-</del>	velop Onsite Staging Area - Site Work
ab Existing Filter Strip	4	27-Aug-20	01-Sep-20	210	1			i		<b>-</b>	Rehab	b Existing Filter Strip
ove Curbs, Gutters, Sidewalk and Paving	3	11-Sep-20	15-Sep-20	23			- 1	-			■ Re	demove Curbs, Gutters, Sidewalk and Paving
r and Grub Site - Site Work	10	16-Sep-20	29-Sep-20	23								Clear and Grub Site - Site Work
ove Existing Fence - Site Work	5	30-Sep-20	06-Oct-20	23	]						Ċ	Remove Existing Fence - Site Work
ide Temporary Security Fence & Gates - Site Work	10	30-Sep-20	13-Oct-20	23	1		i		i		İ	Provide Temporary Security Fence & Gates - Site Work
cate Propane Tank & 1" PO - Site Work	3	14-Oct-20	16-Oct-20	130	<del> </del>							Relocate Propane Tank & 1" P.D Site Work
-					1			!				Install Electrical Ductbanks Main Power Feeds - Site Work
NI CIECUNAL PUGLIARIAS INIAITI FOWEL FEEDS - THE WORK				-	1 :							Electrical Ductbank Branches - Site Work
									İ			
trical Ductbank Branches - Site Work				_			i	į				Final Grade Site - Site Work
trical Ductbank Branches - Site Work  I Grade Site - Site Work		07-Apr-21	09-Apr-21		ļ						 	
trical Ductbank Branches - Site Work  Grade Site - Site Work  Backflow Pad			23-Apr-21	60		Ī						Paving Subsurface Prep
trical Ductbank Branches - Site Work  I Grade Site - Site Work	10	12-Apr-21			. :							
trical Ductbank Branches - Site Work  Grade Site - Site Work  Backflow Pad		12-Apr-21 26-Apr-21	30-Apr-21	60	:			i	i			□ Place Aggregate Base coarse
trical Ductbank Branches - Site Work  I Grade Site - Site Work  Backflow Pad  ng Subsurface Prep	10		-	60								☐ Place Aggregate Base coarse ☐ Place Curb and Gutter - Site Work
trical Ductbank Branches - Site Work  I Grade Site - Site Work  Backflow Pad  ng Subsurface Prep e Aggregate Base coarse	10 5	26-Apr-21	30-Apr-21									
	Ductbanks Main Power Feeds - Site Work nk Branches - Site Work - Site Work	Ductbanks Main Power Feeds - Site Work         20           Ink Branches - Site Work         20           - Site Work         15           ad         3	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21       Ink Branches - Site Work     20     01-Feb-21       - Site Work     15     11-Mar-21       ad     3     07-Apr-21	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21       - Site Work     15     11-Mar-21     31-Mar-21       ad     3     07-Apr-21     09-Apr-21	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     28-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60       be Prep     10     12-Apr-21     23-Apr-21     60	Ductbanks Main Power Feeds - Site Work     20     04-Jan-21     29-Jan-21     105       Ink Branches - Site Work     20     01-Feb-21     26-Feb-21     137       - Site Work     15     11-Mar-21     31-Mar-21     77       ad     3     07-Apr-21     09-Apr-21     60

Run Date: 04-May-20 Data Date: 30-Apr-20 Project ID: PWB 90% Page 2 of 6





		Orig Dur	Start	Finish	Total Float		-			020		-					T =					2021					1 -	2022
	During Objection 9 Circums City Worth		24 May 24	44 1 24	60	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun			_		_	Dec	Jan
AUU00	Paving, Stripping & Signage - Site Work	15	24-May-21	14-Jun-21	75															•	1		77 -	7 -	e - Site Wo - Site Wo			
APRICE	Install Bollards Site (7ea) - Site Work	5	15-Jun-21	21-Jun-21	/5																i	i	i		- 1	and¦Stagin	_	
	Clean Up/Remove Access Roads and Staging	_	15-Jun-21	21-Jun-21	00					-								-		1	"_	Clean U	* i	i	i	i -	i	
	Landscaping and Restoration - Site Work	30	22-Jun-21	03-Aug-21	75																	<u> </u>	i		- i	toration -	Site Work	
	Install Security Fence - Site Work	15	22-Jun-21	13-Jul-21	/5				¦	<b>}</b> -	<del> </del>							<del></del>		. <del> </del>	- <del> </del>		nstall Sec	unty Fer	nce - Site	work ment Syste		·
	Temp Water Management Systems (Testing, Flushing, Disinfection)	15	16-Jul-21	05-Aug-21	33					į												-	ler	np wate	r Manage	!	!	!
	Installation of Security Systems - Site Work	20	25-Oct-21	19-Nov-21	3																					<u> </u>	Installatio	on of Sec
Yard Pipe		213	02-Jul-20	30-Apr-21	95																							
	Pothole Existing Utilities - Site Work (S-17)	5	02-Jul-20	09-Jul-20	20					☐ Poth	ple Existin	- :	;															
	Pothole Existing Utilities (S-16)	5	11-Sep-20	17-Sep-20	151		; }		i	ļ	ii	Pb	thole Exi	sting Utilit														
	Relocate 4" & 6" SDR - YP	8	08-Dec-20	17-Dec-20	95											elocate 4	i	i										
	Install 1" PW to New Chem Bldg	2	15-Dec-20	16-Dec-20	0					į						:	:	Chem Bi	ig									
	Install 1.5" CO2	3	17-Dec-20	21-Dec-20	0											กรtall 1.5' !	!											
	Remove and Replace Sample Line Vault - YP	5	18-Dec-20	24-Dec-20	95					į						i		lace Sam	le Line \	/ault - YP		İ		İ	İ	į	İ	
A6925	Install 4" PDR	3	22-Dec-20	24-Dec-20	0				<u> </u>	<u> </u>	<u> </u>				•	install 4"		<u> </u>		ļ	<u>.</u>							
A6160	Install 1.5" SL - YP	5	25-Dec-20	31-Dec-20	95					-					_	Install	1,5" SL -	ÝΡ		1	-					İ		
A6175	Install Precast utility Vault ( 3ea 1/2" AA) - YP	5	25-Dec-20	31-Dec-20	105										. –	}	:	itility Vault	•		:							
A6150	Install 1" SPD (Reroute Sump Pump Discharge) - YP	5	04-Jan-21	08-Jan-21	95											1		(Reroute		1 7		Ϋ́P						
A6105	Install 8" SDR w/ Soak Age Trench- YP	10	11-Jan-21	22-Jan-21	95					1							install 8"	SDR w/ S	oak Age	Trench-	ΥP			1				
A6100	Install 4" SEW - YP	5	25-Jan-21	29-Jan-21	95				<u> </u>	<u> </u>	<u>i</u>						Install	4" SEW -	ΥP	<u>.</u>	. i	_i		i_		İ	i	i
A6110	Install 3" CWS (3ea) - YP	5	25-Jan-21	29-Jan-21	127												Install	3" CWS (	lea) - YF	)								
A6115	Install 12" CWS PS to Tie in w/ S-18	2	01-Feb-21	02-Feb-21	127					į			İ				Instal	12" CWS	PS to T	ie in w/S	18	İ		İ	İ	į	İ	
A6900	Install 6" PW- YP	7	01-Feb-21	09-Feb-21	95												Ins	tall 6" PW	YP									
A6130	Install 2" SPD UWPS Sump Drain- YP	4	03-Feb-21	08-Feb-21	127					:	1 1						☐ Inst	all 2" SPC	UWPS	Sump Dr.	ain-YP			-				
A6135	Install 4" CWS (2ea) - YP	10	09-Feb-21	22-Feb-21	127													Install 4"	CWS (2	ea) - YP								
A6910	1" Irrigation	3	10-Feb-21	12-Feb-21	95				i	ļ	†i	<del>-</del>				i		Irrigation		†								
A6140	Install 12" CWS PS to Conduit 3 (Near UWPS) - YP	5	23-Feb-21	01-Mar-21	127					!								Install	2" CWS	PS to Co	nduit 3 (	Near UV	NPS) - YF	P				
A6145	Tie in 12" CWS to Conduit 3 (Near UWPS) - YP	2	02-Mar-21	03-Mar-21	127					į								I Tie in	12" CWS	to Cond	ult 3 (Ned	ar UWPS	5) +YP			i		
Utilidor Pipi	oing	119	13-Jul-20	28-Dec-20	183																							
A6021	Install Erosion Control - Chem Utility Pipeline	10	13-Jul-20	24-Jul-20	4						Install Ero																	
A6026	Clear and Grub - Chem Utility Pipeline	5	27-Jul-20	31-Jul-20	4				!			nd Grub				ļ	†	†		†								
A6225	Install Utility Trench Piping 11+40 to end of Utility Trench - YP (C-8)	15	03-Aug-20	21-Aug-20	4							nstall Utilit	y Trench	Fiping 11	+40 to en	d of Utilit	Trench	YP (C-8	)									
A6950	Install 12" CWS UWPS to 6+10	15	05-Aug-20	25-Aug-20	7					į		Install 12	cwsu	WPS to 6	+10											İ	İ	
A6230	Install Chemical Lines from 9+50 to 11+40 - YP (C-8)	10	24-Aug-20	04-Sep-20	4						. =	Instal	Chemica	Lines fro	m 9+50 tr	o 11+40 -	YP (C-8	,										
A6955	Install 12" CWS & 2" SL 9+50 to 6+10	25	26-Aug-20	30-Sep-20	7								i	i i	8 2" SL 9	i	i							-		İ		
A6180	Install Utility Trench Piping Chem Bldg. to 2+00 - YP (C-8)	5	08-Sep-20	14-Sep-20	4				!	<del> </del>	<u> </u>	Inst	tall Utility	Trench P	ping Cher	m Bldg. to	2+00 -	YP (C-6)		†	· <del> </del>							
A6185	Install Utility Trench Piping 2+00 C-4 to 4+75 - YP (C-8)	20	15-Sep-20	12-Oct-20	4					İ							•	+75 - YP	C-6)		İ	i		İ		i	i	
	Install 2" SL (Existing PS) - YP (C-9)	5	01-Oct-20	07-Oct-20	7					!		1	Instal			i	i		-									
	Install Utility Trench Piping - End of Trench to Vaults	20	13-Oct-20	09-Nov-20	4					ļ					_		1 *	ofTrenc	n to Vaul	is.								
	Install 12" CWS from Utility Trench to Utility Water Taps - YP (C-7)	5	10-Nov-20	16-Nov-20	207													ench to U		!	YP (C-7	, !						
	Flush and Head Test CO2 Dffuser	5	10-Nov-20	16-Nov-20	4		¦		·	t	ti	<del> </del>			ush and H	<del></del>		<del>+</del>	,	+	-	÷			·	<u></u>		
	Final Grade - Chem Utility Pipeline	5	17-Nov-20	23-Nov-20	207					į				i i	Final Grad	i	i	i						İ	ĺ	ĺ		į
	Fab CO2 Diffuser	15	17-Nov-20	08-Dec-20	4										Fab	:												
	Install Chem Trench 9+50 to 4+75	25	23-Nov-20	28-Dec-20	173					-						!	!	nch 9+50	to 4+75					İ				İ
	ults at Conduits	184	13-Aug-20	30-Apr-21	.,,					į														i				
	Install Conduit 2, 3 and 4 Chemical Injection Vaults - YP (C-7)	15	11-Sep-20	01-Oct-20	0	<del> </del>	<del> </del>	ļ	ļ	<del> </del>	<del> </del>	<u></u>	Install (	Conduit 2	3 and 4 6	Chemical	niection	Vaults - \	P (C-7)	╁	-}		<del></del> -					
Conduit 4	make souther E, o and it strenmed injection values - 11 (0-1)	101	13-Aug-20	05-Jan-21	0					!			stall C	Z wat Z	J GIRG T	- remodi	ingeouo!	Tuurs -	. (0-1)					!		!		
	Written Request to PWB to Shutdown Conduit 4	40	-	08-Oct-20	4					į			166		st to PWI	1/6//			//////	2								į
	PWB Isolate, Dewater, complete shutdown Operation Conduit 4	5	13-Aug-20 15-Oct-20*	21-Oct-20	- 4					1			1////	17/////		ソノノアノノ	8//////	tibown Op		Andus 4				-				
				28-Oct-20	17					į			7777	141141	Asbesto	シリリナリリ	シリリナリ			A COURT		į		į	İ	į	į	į
	Remove Asbestos - Conduit 4 N 4	5	22-Oct-20		1/				į	ļ	ļi		4/7/	4444	14444	1444	85454			<u> </u>					·			
	Tie In 12" CWS Conduit 4 - Util Water (North) - YP	15	23-Nov-20	14-Dec-20	0					1			1///		1//////	4//////	111111	duit 4 - Viti		piorth) - \					1	ĺ		
A6245	Chem Tie In Conduit 4 - YP	10	15-Dec-20	28-Dec-20	0					į							N////	duit 4 - X	//////	4				i			i	
	PWB Disinfect, Fill and Place Conduit back into service - Conduit 4	5	29-Dec-20	05-Jan-21	0					İ			1///			PWB	Disinfed	( Fill and	ace Co	moduit bac	K Into se	rvice - C	onduit 4	i				
A6216		131	11-Sep-20	16-Mar-21	0					!			1///							2				!		!		
A6216 Conduit 3											: !			- AW mile	n Rebúés	st to PWE	3 to Shut	down Con	duit 3//	A.	i				:	:		;
A6216 Conduit 3 A6218	Written Request to PWB to Shutdown Conduit 3	40	11-Sep-20	05-Nov-20	41				į	ļ	ii		/////	4444	77777	11.21.21	グスノンエノン	111111	111111	ģ					·	<del> </del>		<del> </del>
A6216 Conduit 3 A6218 A6219	PWB Isolate, Dewater, complete shutdown Operation Conduit 3	5	06-Jan-21	12-Jan-21	0				ļ	} 	ļi					D PW	/B Isolat	Dewate	comple	e shutda	wn Oper	ration Co	nduit 3					
A6216 Conduit 3 A6218 A6219 A6220	•				0				   	   						PW	B Isolat	111111	comple Conduit	se shutda B Util Wa	wn Oper iter (Nort	ration Co	nduit3					- <del> </del> -

Run Date: 04-May-20 Data Date: 30-Apr-20 Project ID: PWB 90% Page 3 of 6





A6221 PW Conduit 2 A6248 Writ A6249 PW A6125 Tie A6250 Che A6251 PW A6825 End Sted Road Pip 3188 Dev da Ash Facilit 3265 Exc 3270 Inst	evelop Access to HDD Launch Pads	10 5 144 40 5 8 15 5 0 2 2 190 10 5	24-Feb-21 10-Mar-21 09-Oct-20 09-Oct-20 17-Mar-21 24-Mar-21 05-Apr-21 26-Apr-21 03-Aug-20 03-Aug-20	09-Mar-21 16-Mar-21 30-Apr-21 04-Dec-20 23-Mar-21 02-Apr-21 23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0 0 71 0 0 0	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan en Requi			nduit 3 S	ofect, Fi	e In - YP Il and Plac	e Çonduit	baick into	service -	- Conduit	3	Dec	
A6221 PW Conduit 2 A6248 Writ A6249 PW A6125 Tie A6250 Che A6251 PW A6825 End Sted Road Pip 3188 Dev da Ash Facilit 3265 Exc 3270 Inst	WB Disinfect, Fill and Place Conduit back into service - Conduit 3  Witten Request to PWB to Shutdown Conduit 2  WB Isolate, Dewater, complete shutdown Operation Conduit 2  e in 12" CWS to Conduit 2 (North) - YP  hem Tie In Conduit 2 - YP  WB Disinfect, Fill and Place Conduit back into service - Conduit 2  nd of Conduit Shutdown  ipe Crossing  evelop Access to HDD Launch Pads  ity  coavate Silo Foundation - Soda Ash Facility  stall Sub Grade Piping - Soda Ash Facility  stall Sub Grade Electrical - Soda Ash Facility	5 144 40 5 8 15 5 0 2 2 190	10-Mar-21 09-Oct-20 09-Oct-20 17-Mar-21 24-Mar-21 05-Apr-21 26-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	16-Mar-21 30-Apr-21 04-Dec-20 23-Mar-21 02-Apr-21 23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0 71 0 0 0 0										Write	en Requi	est to PM		WB Disi	ofect, Fi	I and Place		utdown O					
A6248 Write A6249 PW A6125 Tie A6250 Che A6251 PW A6825 End A6825 End A6825 Exc A6250 Exc A6270 Inst A6275 Inst	Initten Request to PWB to Shutdown Conduit 2  WB Isolate, Dewater, complete shutdown Operation Conduit 2  e in 12" CWS to Conduit 2 (North) - YP  them Tie In Conduit 2 - YP  WB Disinfect, Fill and Place Conduit back into service - Conduit 2  and of Conduit Shutdown  ipe Crossing  evelop Access to HDD Launch Pads  ifty  coavate Silo Foundation - Soda Ash Facility  stall Sub Grade Piping - Soda Ash Facility  stall Sub Grade Electrical - Soda Ash Facility	40 5 8 15 5 0 2 2 190	09-Oct-20 17-Mar-21 24-Mar-21 05-Apr-21 26-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	04-Dec-20 23-Mar-21 02-Apr-21 23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0 71 0 0 0 0								7//		Writte	en Requ	est to PV			//			utdown O					Ť
A6249 PW A6125 Tie A6250 Che A6251 PW A6825 End sted Road Pip 3188 Dev da Ash Facilit 3265 Exc 3270 Inst	WB Isolate, Dewater, complete shutdown Operation Conduit 2 e in 12" CWS to Conduit 2 (North) - YP hem Tie In Conduit 2 - YP WB Disinfect, Fill and Place Conduit back into service - Conduit 2 nd of Conduit Shutdown ipe Crossing evelop Access to HDD Launch Pads ifty scavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	40 5 8 15 5 0 2 2 190	09-Oct-20 17-Mar-21 24-Mar-21 05-Apr-21 26-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	04-Dec-20 23-Mar-21 02-Apr-21 23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	71 0 0 0 0 0								1//		Witte	en Requ	st to PV	B to Shu	totown Co	miduit 2		mplete sh		pération (	Conduit 2	!		
A6249 PW A6125 Tie A6250 Che A6251 PW A6825 End sted Road Pip 3188 Dev da Ash Facilit 3265 Exc 3270 Inst	e in 12" CWS to Conduit 2 (North) - YP hem Tie In Conduit 2 - YP WB Disinfect, Fill and Place Conduit back into service - Conduit 2 nd of Conduit Shutdown ipe Crossing evelop Access to HDD Launch Pads ifty kcavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	8 15 5 0 2 2 190	17-Mar-21 24-Mar-21 05-Apr-21 26-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	23-Mar-21 02-Apr-21 23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0 0 0 0													7////		//	i.	mplete sh		peration (	Conduit 2			•
A6125 Tie A6250 Che A6251 PW A6825 End sted Road Pip 3188 Dev da Ash Facilit 3265 Exc 3270 Inst	e in 12" CWS to Conduit 2 (North) - YP hem Tie In Conduit 2 - YP WB Disinfect, Fill and Place Conduit back into service - Conduit 2 nd of Conduit Shutdown ipe Crossing evelop Access to HDD Launch Pads ifty kcavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	5 0 2 2 190 10	24-Mar-21 05-Apr-21 28-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	02-Apr-21 23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0 0 0 0 7						i		1111		1//////	1/////		%/// <del>/</del>	PWB1s	olate. D	ewater. co							- 1
A6250 Che A6251 PW A6825 End sted Road Pip B188 Dev da Ash Facilit B265 Exc B270 Inst	hem Tie In Conduit 2 - YP  WB Disinfect, Fill and Place Conduit back into service - Conduit 2  nd of Conduit Shutdown  ipe Crossing  evelop Access to HDD Launch Pads  ifty  cavate Silo Foundation - Soda Ash Facility  stall Sub Grade Piping - Soda Ash Facility  stall Sub Grade Electrical - Soda Ash Facility	5 0 2 2 190 10	05-Apr-21 26-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	23-Apr-21 30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0 0 0 7		 			1	:		11/1		(//////	V////		//////	///////	//	VS to Con	duit 2 (No	rth) - YP		!			į
A6251 PW A6825 End sted Road Pip 8188 Dev da Ash Facilit 8265 Exe 8270 Inst	WB Disinfect, Fill and Place Conduit back into service - Conduit 2 and of Conduit Shutdown ipe Crossing evelop Access to HDD Launch Pads iity cavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	5 0 2 2 190 10	28-Apr-21 03-Aug-20 03-Aug-20 10-Dec-20	30-Apr-21 30-Apr-21* 04-Aug-20 04-Aug-20	0			·		1			1///						///////	//	Tie In Con	1	i				1	- 1
A6825 End sted Road Pip 3188 Dev da Ash Facilit 3265 Exe 3270 Inst	nd of Conduit Shutdown  ipe Crossing evelop Access to HDD Launch Pads lity cavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	0 2 2 190	03-Aug-20 03-Aug-20 10-Dec-20	30-Apr-21* 04-Aug-20 04-Aug-20	0			١,	!	- <del> </del>	<del> </del>	<del></del>	-///			<del>}</del>	X444	<del>}</del> /////		//	B Disinfect	·						4
sted Road Pip 3188 Dev da Ash Facilit 3265 Exc 3270 Inst 3275 Inst	ipe Crossing evelop Access to HDD Launch Pads lity cavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	2 2 190 10	03-Aug-20 10-Dec-20	04-Aug-20 04-Aug-20	7		i	, '					1///							77	i	1	i	i	i		1	- 1
3188 Dev da Ash Facilit 3265 Exc 3270 Inst 3275 Inst	evelop Access to HDD Launch Pads  ifty  cavate Silo Foundation - Soda Ash Facility  stall Sub Grade Piping - Soda Ash Facility  stall Sub Grade Electrical - Soda Ash Facility	2 190 10	03-Aug-20 10-Dec-20	04-Aug-20	,		i	1					777	1111111	111111	77777	121121	77777	77777	7¥ LIN	Condu	Landidow	"					
da Ash Facilit 3265 Exc 3270 Inst 3275 Inst	ifty cavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	190 10	10-Dec-20	_	7			'			n David		LLUDE	D Launch F														- 1
3265 Exc 3270 Inst 3275 Inst	cavate Silo Foundation - Soda Ash Facility stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	10		07 C 24	22			( '	İ		Deve	pp Acces	  -	Launch	laus	1		1		i	İ		İ		İ	İ		i
3270 Inst 3275 Inst	stall Sub Grade Piping - Soda Ash Facility stall Sub Grade Electrical - Soda Ash Facility	_		07-Sep-21	33		<del>.</del>	t <sup>/</sup>			<del>!</del>	<del>.</del>	<del>-</del>	· <del> </del>	· <u></u>	<u>.</u>		<u> </u>			<del> </del>			· <del>-</del>			<del></del>	
3275 Inst	stall Sub Grade Electrical - Soda Ash Facility	5	10-Dec-20	23-Dec-20	37			1	i						!	!	!	!	- Soda As		* !		i		İ		i	i
		_	24-Dec-20	30-Dec-20	97			<i>i</i> '			1				-	i	i	i	- Soda A	i	i							-
1300 Bac	ackfill to slab sub Grade - Soda Ash Facility	5	31-Dec-20	07-Jan-21	97			i i	İ	İ	İ				ļ	1		1	ctrical - S				į		į	İ	İ	į
	•	5	25-Jan-21	29-Jan-21	60			1									- i	i	i	i	a Ash Faci	lity						
	ubgrade Prep - Soda Ash Facility	5	01-Feb-21	05-Feb-21	81	ļ	ļ	ļ'		. <u> </u>	ļ	ļ	ļ		ļ	<u> </u>	Sul	<del></del>	ep - Soda	<del>-</del>								
	RP Silo Slab on Grade - Soda Ash Facility	10	25-Feb-21	10-Mar-21	42			i '										!	!	!	rade - Sod	!						-
	stall Silos with spiral stairs - Soda Ash Facility	10	11-Mar-21	24-Mar-21	42			'	1						İ	İ			Install S	i	n spiral sta	i	i	7			1	
	stall Soda Ash Unloading Canopy - Soda Ash Facility	20	25-Mar-21	21-Apr-21	64	1		1											:	!	Soda Ash I		!	!	n Facility			
3850 Inst	stall Soda Ash Canopy - Soda Ash Facility	5	08-Apr-21	14-Apr-21	59			'	i	i	İ				İ	i	i	İ	□ Ir	nstall So	da Ash Ca	nopy - So	da Ash Fa	acility			i	i
3325 Inst	stall Silo Process Mechanical Equipment - Soda Ash Facility	10	28-Apr-21	11-May-21	40	l	<u> </u>	L'		<u> </u>	<u> </u>	ļ <u>.</u>	<u> </u>		ļ 	<u> </u>		<u> </u>			nstall Silo					a Ash Fa	lity	
3330 Inst	stall Silo Process Piping - Soda Ash Facility	10	12-May-21	25-May-21	40			1													Install					у		ĺ
3335 Elec	ectrical Rough in - Soda Ash Facility	15	26-May-21	16-Jun-21	40			i '													$\dot{-}$	Electrical	Rough in	- Soda Ar	sh Facility	у		- 1
3865 Insu	sulate Exterior Process - Soda Ash	3	26-May-21	28-May-21	95		i	1													0 Insula	ite Exterio	r Process	- Soda A	ısh			i
3340 Pair	ainting - Soda Ash Facility	20	17-Jun-21	15-Jul-21	40			i '	İ		1				İ	1		İ	1	İ			Painting - \$	Soda Ash	Pacility	İ	1	İ
3345 Inst	stall Panels and Control Instruments - Soda Ash Facility	10	19-Jul-21	30-Jul-21	39			1			1				!					-			Install	Panels a	and Contr	ol Instrun	ents - So	da
350 Silo	lo Electrical pull and terminate - Soda Ash Facility	10	02-Aug-21	13-Aug-21	39	1	<del></del>	(:	-	· <del> </del>	<del>:</del>	:i	<del>†</del>	· i	i	†	-†	†					: S	ld Electri	cal pull an	nd termina	e - Soda	A
355 Pre	re Start Up - Soda Ash Sys	1	24-Aug-21	24-Aug-21	33			1																	art Up - So			
	OPI - Soda Ash Sys	2	25-Aug-21	26-Aug-21	33		i	1	İ		İ			į	İ	İ				i	İ		i	i	- Soda As	i		i
	unctional Test - Soda Ash Sys	2	27-Aug-21	30-Aug-21	33			i '	1		1				İ	1		1	1	İ	İ		!		tional Tes	! *	sh Svs	İ
	artup and Commission - Soda Ash Facility	5	31-Aug-21	07-Sep-21	33		!	<i>'</i>	1	!	!	! !	!	!	!					-				7	artup and	i	i	 A
mp Station	and commission code/isin dumy	210	28-Oct-20	23-Aug-21	33		·	:			<del>-</del>	·i	÷	· <del> </del>	ļ	<del></del>	·÷	÷									7	
<u> </u>	stall Dewatering System - Pump Station	5	28-Oct-20	03-Nov-20	37			'						install	Dowstori	ing Syste	one - Pum	n Station										-
	stall Structural Shoring System - Pump Station	10	04-Nov-20	17-Nov-20	37			1		-			,	T	i	1	i	· i	imp Statio									
	cavate Pump Station - Pump Station	15	18-Nov-20	09-Dec-20	37			'						:	Exca	:	:	:										- 1
	•	15			37			1						-	i	i	ï											i
	ubgrade Prep - Pump Station	5	24-Dec-20	30-Dec-20	3/	ļ	<u> </u>	t'			<del>!</del>	ļi	<del>-</del>	· <del> </del>	<del>-</del>	i		÷	<del> -</del>								<del></del>	
	RP Slab on Grade - Pump Station	10	31-Dec-20	14-Jan-21	37			(							•		!	!	Pump									- 1
	RP Walls - Pump Station	15	15-Jan-21	04-Feb-21	37			1								: <b>-</b>	:	:	Pump Sta									
	stall Vault Access Door 4' x 8' - Pump Station	1	05-Feb-21	05-Feb-21	37			'	i	i	i				i	İ	1	1	1	1	8' - Pump	Station	i		i	i	i	i
	RP elevated Deck - Pump Station	7	08-Feb-21	16-Feb-21	37			i '								!	!	!	ated Dec	1	· i							
	stall Interior Ladders - Pump Station	1	17-Feb-21	17-Feb-21	37	ļ	ļ	ļ'	. į	. <u>ļ</u>	ļ	ļ	ļ	.į	ļ	<u>į</u>	<u></u>	÷			ump Statio	· <del>¦</del>	ļ	. <b></b> .			<u>.</u>	
3424 App	oply Damp Proofing - Pump Station	5	17-Feb-21	23-Feb-21	38			i '									!	!	! "	! -	umb Statio	!						į
3420 Inst	stall Pump Station CWS Pump Cans - Pump Station	5	18-Feb-21	24-Feb-21	37			1							İ			Install	Pump Sta	ation CW	/S Pump C	ans - Pu	np Station	1				
3425 Bac	ackfill & Remove Shoring of main structure Pump Station - Pump Station	10	25-Feb-21	10-Mar-21	37			'	1		1				İ	İ	į	— Ba	ckfill & Re	emove S	Shoring of	main stru	cture Pum	p Station	- Pump §	Station		i
3860 Inst	stall Sump Pumps & Pipe - Pump Station	3	25-Feb-21	01-Mar-21	64			i '								!		Insta	II \$ump P	umps &	Pipe - Pun	np Station						
3430 Inst	stall Pump Station Process Piping - Pump Station	15	11-Mar-21	31-Mar-21	37			'								į			Instal	ll Pump	Station Pro	cess Pip	ing - Pump	Station				
3435 Inst	stall Pump Station CWS Pumps - Pump Station	5	01-Apr-21	07-Apr-21	37	1	[		-1	-[	Ĭ	]	·	]	]	T	7	T	Inst	tall Pum	p Station C	W/S Pum	ps - Pump	Station	·	[	T	-;
3440 Pair	ainting - Pump Station	10	08-Apr-21	21-Apr-21	37	1	į	i '	İ	İ	1				į	İ				Paintin	g - Pump S	Station			İ		İ	
3445 Elec	ectrical Rough in - Pump Station	15	22-Apr-21	12-May-21	37	1		· '												i	Electrical F	i	Pump Sta	itibn				i
	stall Panels and Control Instruments - Pump Station	10	13-May-21	26-May-21	37	-		i '	1	!	!				!	!		!		-	Install	1		1	ents - Pur	np:Station		
	ectrical pull and terminate - Pump Station	15	27-May-21	17-Jun-21	37	1		'								1				-			pull and to			* 1		
	re Start Up - Pump Station	1			33	ļ	<u> </u>	[i		- <del> </del> -	<del></del>	<del></del>	ţ		<del></del>	<del></del>		÷	<del> </del>		<del></del>			<del> </del> -	- Pump S		÷	
	PI - Pump Station	3	06-Aug-21	06-Aug-21	33		į	i '	i	İ	į				į								!	! .	np Station	!	İ	
	•		09-Aug-21	11-Aug-21				'	1	-	1					-	į				-				- 1		j	
	unctional Acceptance Test - Pump Station	3	12-Aug-21	16-Aug-21	33			1								!								:	al Accepta	:	! '	
	art Up and Commissioning - Pump Station	5	17-Aug-21	23-Aug-21	33			'	1						İ	-							"	Start Up	p and Cor	mirnission !	g - Pump	1
2 Tank 3485 Exc	cavate CO2 Facility - CO2 Tank	263	28-Oct-20 28-Oct-20	05-Nov-21 30-Oct-20	142	ļ	ļ	<b></b> '	-¦	. <u>ļ</u>	<del> </del>	ļ	ļ	Excava	ļ	ļ	<u>.</u>	ļ	- <del></del> -		<u> </u>	<del> </del>	<del> </del>				<del>-</del>	

Run Date: 04-May-20 Data Date: 30-Apr-20 Project ID: PWB 90% Page 4 of 6






y ID	Activity Name	Orig Dur	Start	Finish	Total Float					020				T	Τ-		1		т.	1		2021			0.1		_
AR40E	Jacks Cuth Grade Floatrian CO2 Test		10 les 24	22 Jan 24		Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar Grado	Apr	May	_	Jul	Aug	Sep	Oct	Nov	Dec
A6495	Install Sub Grade Electrical - CO2 Tank	3	18-Jan-21 08-Feb-21	22-Jan-21 10-Feb-21	89												i	i	Prep - CO	i	iank						
A6500	Subgrade Prep - CO2 Tank				61												i i Sut	-		:		d T - L					
A6505	FRP CO2 Facility SOG - CO2 Tank	5	11-Mar-21	17-Mar-21					ļ										!	!	scig - co	!		<u>.</u> .	İ	İ	İ
A6515	Place Pedestrian Ramp @ CO2 Storage - CO2 Tank	3	18-Mar-21	22-Mar-21	61				<u></u>	ļ	<del>!</del>	<u> </u>			. <u> </u>	<u> </u>	<u> </u>	<u> </u>	Place Pe	- <del>-</del>	Ramp @	·	· <del>-</del> ·	- <del></del>			
A6525	Install CO2 Canopy - CO2 Tank	10	04-May-21	17-May-21	51				İ												Install CO		!	!!			i
A6530	Install CO2 Process Mechanical - CO2 Tank	10	17-Jun-21	30-Jun-21	30																_	1	1		anical - CO		
A6535	Install CO2 Process Piping - CO2 Tank	10	01-Jul-21	15-Jul-21	30				İ									İ				ļ lr	1	1 1	iping - CO2	- 1	i
A6540	Painting - CO2 Tank	5	27-Aug-21	02-Sep-21	0											!						!		Paintin	g - CO2 Tar	nk !	
A6545	Electrical Rough in - CO2 Tank	15	03-Sep-21	24-Sep-21	0				<u> </u>	<u></u>	<u>:</u>	<u> </u>				<u> </u>	<u> </u>	<u>:</u>	<u> </u>	<u>.</u>		<u>.</u>	<u>.</u>		Electrical R	ough in -	CO2 Ta
A6550	Install Panels and Control Instruments - CO2 Tank	10	27-Sep-21	08-Oct-21	0																			•	Install F	Panels an	d Contro
A6555	Electrical pull and terminate - CO2 Tank	10	11-Oct-21	22-Oct-21	0				į		İ				İ	İ		İ	į			į			■ Be	ectrical pu	ıll and te
A6560	Pre Start Up - CO2 Sys	1	25-Oct-21	25-Oct-21	0																				I Pr	re Starf U	p - CO2
A6565	COPI - CO2 Sys	2	26-Oct-21	27-Oct-21	0																				I C	OPI-ÇO	02 Sys
A6575	Functional Test - CO2 Sys	2	28-Oct-21	29-Oct-21	0																				I F	Functional	l Test - (
A6580	Start Up and Commissioning - CO2 Sys	5	01-Nov-21	05-Nov-21	0				ļ		<u></u>	1			1	1	1	<del></del>	<b>†</b>	7		<u> </u>		† <u>†</u>	<b>=</b>	Start Up	and Co
Chemical E	Building	306	16-Sep-20	24-Nov-21	0														İ							į	İ
A6890	FRP Propane Tank Pad	3	16-Sep-20	18-Sep-20	147	1						0 F	RP Propa	ane Tank	Pad												
A6585	Excavate Foundation - Chemical Bldg	10	14-Oct-20	27-Oct-20	23	1								Excava	:	tion - Ch	emical Bk	<b>l</b> g	į		İ	İ			į	i	
A6590	Install Sub Grade Piping - Chemical Bldg	10	01-Dec-20	14-Dec-20	0	1							_		Ins	tall Sub G	Grade Pio	ing - Ch	emical Bld	lg							
A6855	Install Sub Grade Plumbing - Chemical Bldg	5	08-Dec-20	14-Dec-20	8	ļ			<del></del>	<u> </u>	<del></del>	†			. 4	4	-i	<b></b>	Chemical			+		<del> </del>	·		
A6595	Install Sub Grade Electrical - Chemical Bldg	15	25-Dec-20	15-Jan-21	0											!	!	: -	lectrical -	: -	al Bida						
A6625	Backfill to slab sub Grade - Chemical Bldg	5	18-Jan-21	22-Jan-21	0	1			i						-	i	i	i	b Grade -	i							
A6600	Subgrade Prep - Chemical Bidg	5	25-Jan-21	29-Jan-21	0				į		į				İ		1	1	-{Chemic	1	July	į			İ	į	į
					0											•	!		!								
A6629	Install Trench Drain - Chem Building	3	01-Feb-21	03-Feb-21	0				<del></del>	<u> </u>	<del></del>	<del>-</del>		· <del> </del>	· <del> </del>	<del>-</del>	Insta	<del>-</del>	Drain - C			<del> </del>		÷	·	<del>-</del>	
A6630	FRP Slab on Grade - Chemical Bldg	15	04-Feb-21	24-Feb-21	0													FRPS	!	!	emical Bld	-!		<u>i</u> i			
A6635	Install Metal Building -Structural Framework - Chemical Bldg	20	25-Feb-21	24-Mar-21	0												•		!	!	!	!	!	Chemical E	Bldg		
A6619	FRP Walkway Canopy Footing - Chem Building	5	23-Mar-21	29-Mar-21	61				İ						İ	İ		:	:		Canopy Fo		:	ng	İ		į
A6640	Install Doors & Skylights - Chemical Bldg	3	25-Mar-21	29-Mar-21	51															1	Skylights						
A6815	Install Metal Building - Secondary Framing & Panels- Chemical Bldg	10	25-Mar-21	07-Apr-21	0	l			<u> </u>	<u> </u>	<u>.</u>	<u> </u>		<u>. į</u>	<u> </u>	<u>į</u>	<u>i</u>		Inst	all Metal	Building -	Secondar	y Framing	& Panels	Chemical E	Bldg	i
A6641	Install Architectural Finishes - Chemical Bldg	10	30-Mar-21	12-Apr-21	51														ins Ins	stall Arch	hitectural F	inishes -	Chemical	Bldg		İ	i
A6650	Install Soda Ash Metering Pumps - Chemical Bldg	7	08-Apr-21	16-Apr-21	0														lr 🔲 Ir	nstall So	da Ash Me	tering Pu	mps - Che	mical Bldg			
A6675	Install Chem Building HVAC - Chemical Bldg	10	08-Apr-21	21-Apr-21	69															Install C	chem Build	ing HVAC	- Chemic	al Bldg			
A6645	Install Walkway Canopy - Chemical Bldg	15	13-Apr-21	03-May-21	51															inst	all Walkwa	Canopy	Chemic	al Bidg			
A6655	Install CO2 Feed Equipment - Chemical Bldg	7	19-Apr-21	27-Apr-21	0	1			į						İ	İ		İ		Install	ICO2 Fee	d Equipme	nt - Chen	ical Bldg	İ	i	į
A6660	Install Soda Ash Process Piping - Chemical Bldg	15	28-Apr-21	18-May-21	0				İ			1		1	1	<u> </u>	1		†		Install So	da Ash Pro	cess Api	ng - Chem	ical Bldg		
A6665	Install CO2 Process Piping - Chemical Bldg	15	19-May-21	09-Jun-21	0	1															Ins	tall CO2 F	nocess Pi	iping - Che	mical Bldg		
A6870	Install 1/2" AA Lines - Chemical Bldg	2	19-May-21	20-May-21	48																Install 1/2	AA Line	S - Chemi	cal Bldg	Ī		
A6670	Install Plumbing - Chemical Bldg	5	10-Jun-21	16-Jun-21	0				!												i	i	i	emical Bld	a		
A6681	Install Misc Specialties - Chemical Bldg	5	17-Jun-21	23-Jun-21	0				į		į				İ	İ		į	į		!	!		!!!	mical Blog	į	į
A6685	Electrical Rough in - Chemical Bldg	25	24-Jun-21	29-Jul-21	0				<del></del>	<del></del>	<del>!</del>	<del></del>		·{	· <del>{</del>	<del></del>	÷	<del>!</del>	÷		· <del> </del>				n - Chemica		
	-	20	30-Jul-21	26-Aug-21	0	1			İ						İ	İ						1	i	1 1	Chemical E	i	i
A6680	Painting - Chemical Bidg	10			E2	1																	i	i -i	rm System	- 1	D. Jak
A6691	Install Fire Alarm System - Chem Building		30-Jul-21	12-Aug-21	28				İ									i					ins	: :	arm System stall Panels		7
A6690	Install Panels and Control Instruments - Chemical Bldg	15	27-Aug-21	17-Sep-21	28	1														1			•	!!!			
A6695	Electrical pull and terminate - Chemical Bldg	15	20-Sep-21	08-Oct-21	28						<del></del>	į		·	·	<b></b>	÷	<del>-</del>	÷	÷			. <b>.</b>	ļ <b>-</b>	Electric		
A6705	COPI - Chemical Systems	5	08-Nov-21	12-Nov-21	0										-	-	1		-	-	İ	ĺ			į '	COPI	
A6710	Pre Commissioning - Chemical System	5	13-Nov-21	17-Nov-21	0																					Pre	i
A6715	Commissioning Test - Chemical System	7	18-Nov-21	24-Nov-21	0				İ									i		-						_ C	ommissi
Electrical B		111	03-Mar-21	06-Aug-21	39				į						İ	İ	1							į i		į	
A6720	Excavate - Electrical Building	2	03-Mar-21	04-Mar-21	60	l		<u> </u>	ļ		<u> </u>	ļ	<b></b>			<u> </u>	ļ	Exca	vate - Ele	otrical B	Building			<u> </u>			<u></u>
A6725	Below Slab Electrical Rough In - Electrical Building	15	05-Mar-21	25-Mar-21	60														Below S	lab Elec	tridal Roug	h In - Ele	ctrical Buil	ding			
A6730	Subgrade Prep - Electrical Building	3	26-Mar-21	30-Mar-21	60														Subgra	ade Pre	p - Electric	al Building	ı.				
A6735	FRP Electrical Building SOG - Electrical Building	5	31-Mar-21	06-Apr-21	60	1			i						1	1			FRE	Electric	al Building	SOG - E	ectrical B	uilding		i	
A6740	Install FRP - Electrical Building	5	07-Apr-21	13-Apr-21	70	1			İ				İ		1	1	İ	İ	i	i	P - Electric	1	i		i	i	i
A6745	Install Electrical Gear - Electrical Building	15	14-Apr-21	04-May-21	70	1			!			1						!			tall Electric	1	1	uildina			į
A6750	Electrical Rough in - Electrical Building	20	18-Jun-21	16-Jul-21	39	· · · · · ·			i		<del>!</del>	<u> </u>		·	·	<del>†</del>	÷	<del>:</del>	÷	-		<del></del>			lectrical Bu	uildina	
A8755		15	19-Jul-21	-	39	1								1							-	: _		! - !	nd terminat	- !	ical Build
	Electrical pull and terminate - Electrical Building			06-Aug-21	-																	-		arcai puli al	na terminati	e - deçin	cai build
Generator		116	05-Mar-21	17-Aug-21	70				!	!	!	1		1	1	!	!	!	1	1	1	1	1	: :	1	!	ŀ

Run Date: 04-May-20 Data Date: 30-Apr-20 Project ID: PWB 90% Page 5 of 6





Activity ID		Activity Name	Orig	Start	Finish	Total	2020									2021								2022					
			Dur			Float	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Jan
	A6765	Electrical Rough In - Generator	5	26-Mar-21	01-Apr-21	158														Electric	al Rough	In - Gen	erator						
	A6790	Electrical pull and terminate - Generator	1	02-Apr-21	02-Apr-21	158						i		i				i i		Electric	al pull an	d termina	te - Gene	rator		·i	i	í í	
	A6795	Testing - Generator	7	09-Aug-21	17-Aug-21	70						!												■ Те	sting - G	enerator			,











MWH Constructors

# Community Equity and Inclusion Plan

Corrosion Control Improvements Project, City of Portland

2-28-2020, Revision 1

## Table of Contents

- 1. Community Equity and Inclusion Plan Commitment
- 2. Subcontracting Plan Procurement and Outreach
- 3. Workforce Apprenticeship/Pre-Apprenticeship, and Diversity, Recruitment, and Retention
- 4. Compliance

#### Attachments

- A. Bid Packaging Plan
- B. MWH Harassment Free Workplace Sample Signature page

# 1. Community Equity and Inclusion Plan Commitment

The purpose of the Community Equity and Inclusion Plan (CEIP) is to ensure that the public served by the City receives the fullest benefit of the Project undertaken by the City, to improve and increase construction contracting and employment opportunities for racial and ethnic minorities, women, and economically disadvantaged individuals on City projects, to ensure that the City is making conscious and specific efforts through its contracting processes to not discriminate or indirectly perpetuate the historic under-inclusion of racial and ethnic minorities, women, and economically disadvantaged individuals in the construction industry and trades, and to ensure that the City receives the benefit of a highly skilled and well-trained workforce, and provides opportunities for firms that reflect the diversity of Portland in the Contractor and Subcontractor pools.

MWH's objective for this project is to use the goals as a floor and the spirit of the CEIP to maximizing the utilization of DMWESB contractors and suppliers, maximize the utilization of apprentices, and utilize a diverse workforce during construction. In addition, we will make special efforts to outreach to historic under-utilized racial and ethnic minorities, women, and economically disadvantaged individuals in the construction industry and trades and firms. To ensure that the agreed upon goals and aspirations are met, and to assist in the implementation and monitoring, MWH Project Manager, Steve Bjerke, has designated Andre' Baugh, at Group AGB, and Jennifer Erickson, at Pacific Project Partners, LLC, as the DMWESB Coordinators for the project. Andre' and Jennifer will assist MWH in the preparation of Community Equity Inclusion and Subcontracting Plan, Workforce and Hiring Plan, outreach and compliance, and monitoring and reporting during the construction phase.

#### The MWH CEIP requirements and goals, excerpted from the plan, include:

- Community Apprenticeship Requirements a requirement of 20% of the labor hours in each apprenticeable trade shall be worked by apprentices
- Community Workforce Goals a set of goals for women and minority workforce participation are as follows:
  - A. Apprentices: The workforce diversity goals for minority and women apprentice workers shall be thirty-one percent (31%) of total apprenticeable labor hours by trade, which shall be disaggregated as follows:
    - i. Twenty-two percent (22%) of total apprentice hours by trade shall be worked by minority apprentices; and
    - ii. Nine percent (9%) of total apprentice hours by trade shall be worked by women apprentices.
  - B. Journey Level: The workforce diversity goals for minority and women journey level workers shall be twenty-eight percent (28%) of total journey level hours, which shall be disaggregated as follows:

- i. Twenty-two percent (22%) of total journey level hours by trade shall be worked by minority journey level workers; and
  - ii. Six percent (6%) of total journey level hours by trade shall be worked by women journey level workers.
- Subcontracting Goals –goals of 22% overall- 12% D/MBE, 5% WBE, 5% DMWESB for DMWESB participation on all construction contracts subject to the CEIP.

Aspirational Diversity Targets are not requirements for this Contract; however, MWH views the targets as goals and encourages the highest possible participation of minorities and women in the workforce.

## Subcontracting Plan

MWH recognizes that a barrier to entry for many DMWESBs is that they are afforded fewer opportunities to contract with non-DMWESB primes on commercial construction contracts and that historical disparity has adversely impacted opportunities for disadvantaged, minority, and women owned firms in the construction industry. MWH views the CEIP DMWESB 22% as a floor and MWH is committed to exceeding the subcontracting goals that are listed below and we have prepared a bid packaging plan (Attachment 1) detailing how these goals will be met.

Subcontracting Goals -goals (22% overall, 12% D/MBE, 5% WBE, 5% DMWESB) for DMWESB participation

## Procurement Plan / Bid Packaging Plan

MWH is committed to building the capacity of local DMWESBs, cultivating relationships and building teamwork that will provide specific benefits for us on this project and in the future, and general benefits to the contracting community. MWH will start the evaluation process with the assumption that all non-self performed subcontracted work is potentially available for DMWESB participation. Scopes of work will be further evaluated and refined to maximize the number of opportunities tailored to DMWESB participation. With this goal in mind, MWH was guided by the following principles in designing bid packages:

- 1. Unbundle large bid packages to create the largest number of opportunities specifically making sure there are opportunities below \$150,000.
- 2. Research the local DMWESB marketplace to determine the scopes of work with highest DMWESB availability
- 3. Utilize the City's Prime Contractor Development Program ("PCDP") participants as a first source, where possible, in either direct contracting or soliciting for scopes of work for the Project.
- 4. Contract with more than one DMWESB for areas of high availability to expand MWH subcontracting pool and increase the number of opportunities to DMWESBs
- Require DMWESB sub tier outreach and target DMWESBs for all Formal Packages and incorporate participation commitments into our selection criteria.

MWH's procurement/bid packaging plan is summarized in <u>Attachment 1</u>. This plan details our approach to subcontract bid packages, equipment procurement packages, and self-perform work packages and is designed to meet the requirement and goals of the CEIP.

The MWH bid packaging plan shows DMWESB subcontractor participation at 25%, exceeding the 22% set by the City's CEIP.

Estimated values of the hard construction costs shown on the attached bid packaging plan are based on MWH's estimate of the 90% design documents.

MWH will require that all contracts include all CEIP requirements and goals. Also, we will require at bid time, both a plan for meeting the apprenticeship hours for the project and we will require that bidders include their plan for meeting the diversity in the trades goals, as well. Bids received without a demonstrable plan will be considered non-responsive and rejected.

MWH's bid packaging plan – included in Attachment 1 – details:

- Package Number
   — Package numbers beginning with an "S" represent subcontracted work. Packages beginning with a "P" represent process equipment to be directly purchased by CM/GC.
- Package Description Describes the scope to be completed under that bid package.
- Estimated Value (of the bid package) The values shown are based on the 90% Estimate and represent the most accurate and
  current information available at the time this plan was prepared.
- Opportunity for DMWESB Participation 1<sup>st</sup> Tier represents subcontracts directly with the CM/GC. 2<sup>nd</sup> Tier represents opportunities to work as a subcontractor to the party working directly for CM/GC.
- Procurement Method "Informal", "Best-Value", and "Price-Based" shall have the meanings defined in Section 3 of this Plan.
   Bid packages highlighted in yellow on <a href="Attachment 1">Attachment 1</a> will be procured using the "informal" selection method and will be targeted specifically at D/M/W firms.

Packages highlighted in green on Attachment 1 will be procured using the "best-value" selection method. Best-value selections will be made based on a combination of DMWESB participation, qualifications, and price. In order to be considered for award, bidders must demonstrate a minimum D/M/W participation level as shown in the columns entitled "DMWESB \$" and "DMWESB % Package". Bids unable to demonstrate this level of participation will not be considered and will be rejected.

For certain "informal" and "best value" packages, <u>and with the City's approval</u>, MWH may bypass the standard procurement procedures and target participants in the City's Prime Contractor Development Program (PCDP) directly.

Bid Packages highlighted in orange on <u>Attachment 1</u> will be procured using the "price-based" method. Price-based packages will include a prequalification process. These "price-based" packages will include a requirement for a minimum D/M/W participation level as shown in the columns entitled "DMWESB \$" and "DMWESB % Package". Bids unable to demonstrate this level of participation will not be considered and will be rejected.

- DMWESB (\$) Values shown represent the expected dollars to be awarded to a qualified DMWESB contractor.
- DMWESB (% Package) Dollars expected to be awarded to a qualified DMWESB contractor divided by estimated value of the
  package as expressed as a percentage.
- DMWESB (% Project) Dollars expected to be awarded to a qualified DMWESB contractor divided by estimated total hard construction cost as expressed as a percentage.

MWH's self-perform work, as approved by the City, shall include purchase, installation, start-up, testing and commissioning of the above-ground components of the soda ash storage and feed system and the carbon dioxide feed system including the associated piping, valves, appurtenances, etc.

#### Early-Out Bid Packages

As required by our Phase 1 (pre-Construction) scope of work, MWH worked with the City and Stantec to identify bid packages beneficial to fast-tracking of construction including:

- Bid Package S-03B Tree Removal, and
- Bid Package S-09 Pre-Engineered Metal Building and Metal Canopies

These early-out bid packages will be let based on the 60% Design Documents provided by Stantec. It is the desire of the project team that the tree removal work included under package S-03B be completed prior to the onset of migratory bird mating season beginning in the month of March. It is the intention of the project team that the manufacturer-specific design details for packages S-09 be secured in advance, and incorporated into, the 100% Design Documents.

#### Outreach Plan

To assure maximum utilization of DMWESB subcontractors in the work of the Project, solicitation for all informal, formal, best value and RFP project packages will be created utilizing the process discussed below. MWH will utilize equitable procurement procedures which shall consist of an open, fair, and competitive solicitation process, including the following:

- Early identification of bidding opportunities, including:
  - i. Contractor shall identify all divisions of work that will be subcontracted.
    - b. DMWESB subcontractor availability determined through state-certified OMWESB list and local market
  - ii. Outreach shall start during the pre-construction services phases to provide advance notice to DMWESBs, including:
    - a. Advance notice will be sent to key trade and business organizations that promote the utilization of minorities and women in public works projects.
    - b. Contractor shall contact firms by email and/or fax notifying them of the anticipated work available on the Project.
    - c. Information shall be posted on the Contractor's website, or to a shared website approved by City, to facilitate assessment of the interest of DMWESBs for the Work on the Project.
    - d. If deemed necessary by the City, outreach shall continue during the life of the Project and will be tailored to specific opportunities made available in solicitation packages.
  - iii. Contractor shall conduct pre-bid/pre-proposal meetings for all solicitation packages, including:
    - a. Fulfilling the purpose of the meeting which is to provide clarity and understanding of the Project and solicitation requirements, view the jobsite, and to advise bidders of the importance of the commitment to and expectations for DMWESB utilization.
    - b. Bidders/Proposers will be offered assistance in conducting effective solicitation steps to obtain DMWESB participation.
    - c. Contractor is required to notify the City's Contract Compliance Specialist and City of all pre-bid/pre-proposal meetings.
    - d. For solicitation packages with an estimated value greater than \$150,000, Contractor shall coordinate meetings with the City's Contract Compliance Specialist who must attend all pre-bid/pre-proposal meetings.

- iv. During the construction services phase, the Contractor and Subcontractors with subcontracts in excess of \$150,000 shall conduct outreach apprising the construction industry and DMWESBs of the subcontracting procurement process and approach to DMWESB utilization, including:
  - a. Information on anticipated solicitation dates and divisions of work identified for DMWESB participation.
  - b. Information on the resources that will be available to them during the bidding and construction phases.
- Targeted solicitation methods and conditions, including:
  - i. Contractor shall provide a solicitation package to interested DMWESBs and/or make it available for pick-up including all of City's contracting requirements as referenced in the Project's Contract Documents, including:
    - a. Before a solicitation is released, the City's Contract Compliance Specialist and the City's Representative will be provided with a copy of the solicitation package for review and comment.
    - b. Contractor will make themselves available to assist prospective DDMWESB bidders in understanding solicitation requirements.
  - ii. Contractor shall procure all Subcontractors and Suppliers for all divisions of work in the completion of the Project by selecting the bidder using one or more of the following methods:

Informal Solicitations - Work packages estimated up to \$150,000

- a. Optional advertisement at least three weeks prior to bid opening; if advertised, MWH will ensure the package is placed in two of the following publications and will rotate the advertisement for each package – The Skanner, The Portland Observer, The Asian Reporter and El Latino.
- b. An advertisement / notification will be placed at least three weeks prior to bid opening:
  - The City of Portland for posting on the web page
  - Oregon Association of Minority Entrepreneurs (OAME)
  - Portland Business Development Group (PBDG)
  - Latino Build
  - · National Association of Minority Contractors Oregon (NAMC)
  - Metropolitan Contractor Improvement Partnership Portland (MCIP)

- BEST Hq
- Oregon Native American Chamber
- c. Target a minimum of three DMWESBs in each division of work.
- d. Hold pre-bid one week prior to bid opening
- e. Contractor or Subcontractor shall notify DMWESBs in writing who specialize in the type of work that will be subcontracted and shall provide adequate information for submission of a bid, along with the date and time that sub-bids are due. Contractor shall obtain a total of three (3) bids from DMWESBs who specialize in the type of work that will be subcontracted.
- f. If less than two responsive bids are received, proceed to the following steps:
  - i. MWH will review all bids received with City of Portland to evaluate responsiveness.
  - ii. If bids are found to be responsive, then a subcontractor selection will be made.
  - iii. If no responsive bid is received, the proceed to process below.

ID#	Informal	\$ Estimated		
S-01	Site Conditions Survey	\$15,000		
S-01A	Construction Survey (Quality Assurance)	\$15,000		
S-08	Removal & Disposal of Contaminated Material	\$10,000		
S-12	Paintings and Coatings	\$134,560		
S-20	Chain Link Fencing	\$34,300		
S-22	Tree Removal	\$73,600		

Solicit to Open Market - Price Based

Formal Price-Based Solicitations – Work packages estimated at greater than \$150,000

- 1. Project solicitation packages shall be advertised in the Daily Journal of Commerce and a minimum of two minority publications 4 weeks prior to bid opening date (e.g., El Hispanic News, The Skanner, The Portland Observer, The Asian Reporter).
- 2. Contractor or Subcontractor shall notify DMWESBs in writing who specialize in the type of work that will be subcontracted and shall provide adequate information for submission of a bid, along with the date and time that sub-bids are due. Contractor shall obtain a total of three (3) bids from DMWESBs who specialize in the type of work that will be subcontracted, where possible.
- 3. Contractor may maintain three (3) full sets of plans and specifications for solicitation packages where possible for review at local plan centers, such as (but not limited to), Daily Journal of Commerce, Oregon Association of Minority Entrepreneurs ("OAME") Plan Center, Latino Build, Metropolitan Contractors Improvement Partnership ("MCIP"), Portland Business Development Group (PBDG), I-Plan, and Ford Graphics. Confidential drawings must be handled separately and will only be distributed following the City's Confidentiality Policy.

ID#	Priced Based	(\$) Estimated
S-03D	Earthwork - Utility Water Pump Station Earthwork	\$570,934
S-05	Site Concrete	\$683,673
S-09	PEMB and Metal Canopies - Completed	\$300,981
S-10	Tensile Membrane Structure	\$225,000
S-15	Electrical	\$2,056,269
S-15A	Instrumentation and Controls	\$188,500
S-17	Process Piping	\$2,516,758
S-18	Horizontal Directional Drilling	\$136,188
P-02	Pumps	\$121,086
P-03	Chemical Feed System	\$46,825

Best-Value Solicitations – Work packages estimated at greater than \$150,000

- 1. Where the work package involved requires specialized knowledge, skill, experience, and expertise a Request for Proposal ("RFP") may be used. RFPs must include the following criteria for diversity in contracting:
  - Describe your company's policy and practice of contracting with DMWESBs including the number of individual DMWESBs contracted, the dollar amount contracted and the amount paid to DMWESBs over the past three years. List the name, nature of work, and dollar amount of each DMWESB for the cited projects.

- Describe objectives for increasing DMWESB subcontracting capacity in the work of the Project, including an
  estimate of the dollar volume of DMWESB utilization you will aspire to achieve.
- Describe your company's hiring policy and practice for hiring, retaining and advancing minorities and women in your workforce.
- 2. RFPs shall be publicly advertised in the Daily Journal of Commerce, and a minimum of two minority publications 4 weeks prior to bid opening (e.g., El Hispanic News, The Skanner, The Portland Observer, The Asian Reporter). In addition, advertisement/notification will be placed at The City of Portland for posting on the web page, Oregon Association of Minority Entrepreneurs (OAME), Portland Business Development Group (PBDG), Latino Build, National Association of Minority Contractors Oregon (NAMC), Metropolitan Contractor Improvement Partnership Portland (MCIP), BEST Hq, and Oregon Native American Chamber
- 3. Contractor or Subcontractor notify DMWESBs in writing who specialize in the type of work that will be subcontracted and shall provide adequate information for submission of a bid, along with the date and time that sub-bids are due. The contractor shall obtain a total of three (3) bids from DMWESBs who specialize in the type of work that will be subcontracted where possible.
- 4. Contractor shall maintain three (3) full sets of plans and specifications for solicitation packages for review at local plan centers, such as (but not limited to), Daily Journal of Commerce, Latino Build, OAME Plan Center, MCIP, I-Plan, and Ford Graphics.

  Confidential drawings must be handled separately and will only be distributed following the City's Confidentiality Policy.

ID#	Best Value	(\$) Estimated				
S-02	Site Preparation	\$337,469				
S-03C	Site Earthwork and Demolition	\$368,283				
S-03E	Access Road and Staging Area	\$301,178				
S-04	Utility Water Pump Station Concrete	\$364,497				
S-14	HVAC	\$205,000				
S-16	Utilities Piping	\$395,967				
S-19	AC Pavement and Base	\$158,030				
S-21	Landscaping	\$237,295				

MWH will analyze bid response results against outreach efforts to determine where DMWESBs declined to bid on the project. MWH will follow up with those bidders who initially indicated interest in the project but later did not bid, to find out why they declined to submit. Also, the opportunity will be offered to come in and meet with MWH and review their bid. Feedback from this effort will be used to refine our bid process for future bid packages.

#### Onboarding

MWH will onboard all subcontractors by scheduling a pre-job startup meeting to go over the requirements and expectations of the CEIP including the project goals, pre-job submittals, and monthly construction submittals. Please see the compliance section for more detail.

## Technical/Business Assistance

MWH will offer and provide the following technical assistance services to all DMWESB subcontractors awarded a contract on the Project regardless of subcontracting tier:

- Establishing a schedule of values for the work to be performed
- Preparation of cash flow projections required for successful performance of the work
- Progress payment assistance with mentoring on pay requests, invoices, and required documentation
- · Advance payment for materials on hand where appropriate to facilitate successful participation of all tier DMWESBs
- Establish projected measurable capacity building elements (e.g. additional equipment, expanded expertise, improved production
  efficiency, etc.) anticipated as a result of participating in the capacity building component of this plan.
- Provide technical assistance and training on BIM as needed and as it related to specific scopes of work for subcontractors on the project
- Consider payment advance on progress payment provisions in those instances where prudent and appropriate to facilitate successful
  participation of first tier DMWESB subcontractors.
- MWH will partner with City Small Business Development Center offering growth and development opportunities for small business owners.

# Pre/Post Contract Award Monitoring

MWH will establish and maintain contact with all subcontractors, regardless of tier, to monitor and coordinate efforts to prevent problems from arising and/or solve those that have arisen, which are/or may contribute toward unsuccessful performance by the affected subcontractor(s).

# DMWESB Replacement Policy and Procedure

While affording maximum opportunities for DMWESB subcontractors to participate on the Project, it is imperative that the overall Project production schedules be maintained. Any DMWESB subcontractor on the Project deemed to warrant replacement will be terminated in accordance with the relevant contract provisions as set forth in the DMWESB Bid Specifications or Plan requirements. The basis for termination will be one or more of the following with supportive documentation:

- 1. Inability of the company to perform the work as required
- Refusal of the company to perform the work as required
- Mutual agreement of MWH Construction and the company not to perform the work due to reasons beyond the control or influence of MWH Construction

The successful bidder, regardless of tier, will not be permitted to substitute a DMWESB subcontractor without the consent of MWH.

If any subcontractor is added or replaced after the bid is submitted, the successful bidder shall make good faith efforts to contract with a DDMWESB in conformance with the Diversity Construction Plan for the work to be performed by that subcontractor. Documentation of these efforts is required and must be submitted to the CITY regardless of tier.

#### DMWESB Termination and Substitution

MWH will not terminate any first-tier DMWESB companies on the Project without adhering to the criteria set forth in this Plan. Prior to termination, MWH Construction will notify the City in a written statement of the decision and the basis upon which the DMWESB is being terminated.

- 1. Subcontractors of any tier bidding or providing quotes on any package, division of work and/or work element having an estimated value greater than \$150,000 shall be required to meet the requirements of the Plan. The contractor shall deem bid proposals not meeting this requirement to be non-responsive.
- 2. If the Contractor or an affiliate or subsidiary of the Contractor will be participating in the solicitations as a bidder for a subcontracted scope of the Work, the Contractor shall disclose that fact in the selection process and announcements. When an affiliate or subsidiary will be bidding, the Contractor shall identify the procedures the Contractor will utilize in order to make the process impartial, competitive and fair. This shall include but is not limited to, the opening of bids by a representative of the City and objective review of bids by an independent third party. The Contractor's participation in solicitations as a bidder is subject to the City's approval.

# 3. Workforce

MWH is committed to facilitating the recruitment, retention, and promotion of historically disadvantaged or underrepresented people, including racial and ethnic minorities, and women who are interested in careers in the construction industry. MWH's commitment to Workforce Training and Hiring (WFTH) goals include ensuring firm commitment of 20% apprenticeship, ensuring to have a Project workforce that reflects the workforce goals in the CEIP both for journey workers and apprentices. In addition, Steve Bjerke, the Project Manager, personally commits to maintain a Harassment-Free Workplace, in which all work must be assigned in a manner that respects training objectives for apprentices and ensures an equitable distribution of meaningful work, training, and assignments among all workers. Our goal is a Harassment-Free Workplace that is appropriate, productive, safe, free from bullying, hazing or harassment. We will have a workplace free from behaviors that may impair production or undermine the integrity of the work conditions including but not limited to job performance, safety, productivity, or efficiency of workers.

## Harassment-Free Workplace - MWH is committed to a harassment-free workplace.

MWH will complete a comprehensive Jobsite orientation for all workers, including City, MWH and all employees of MWH and all subcontractors who will enter the project site. The training is required to be completed, sign a completion form and receive a sticker before any worker enters the project. MWH's harassment-free workplace will cover the following:

- a) Dissemination of the Prohibition Against Workplace Harassment, Discrimination and Retaliation Policy
- b) Procedures to follow for reporting and expected crew behaviors
- Verification that employees have received a copy of MWH's and subcontractor's policies regarding harassment, discrimination, and retaliation
- d) Provide a list of resources to employees identifying support systems including, but not limited to, Equal Employment Opportunities, Employee Assistance Programs, community resources, and mentors.

The Workplace Harassment will be one hour paid for all who participate and is required as part of the onboarding process MWH will implement. MWH will work to maintain a responsive grievance procedure that supports retention and anti-harassment efforts which will be prominently posted on the ob Jobsite in a conspicuous and accessible location. Also, MWH will take steps to reduce feelings of isolation among racial and ethnic minorities and women by making every attempt to have several racial and ethnic minorities and women at the Jobsite by informing such workers about available support systems. Information will be provided at the jobsite about grievance procedures and complaint processes available to workers via the City of Portland, BOLI, and other resources.

While maintaining and managing a Harassment Free Workplace is MWH's responsibility, each Subcontractor will have accountability for performance in sustaining and managing their own worksite. MWH will monitor the entire worksite to ascertain whether risk or circumstance exists that may merit a remedy. Monitoring may include proactive observations of the worksite, interviews of individuals familiar with the

worksite, collection of data that may evidence disparities, investigation of complaints by an individual familiar with the worksite, or collection of other evidence. If risks or circumstances that may merit a remedy are discovered, MWH will notify and collaborate with the City of Portland to discuss appropriate remedies, and may likewise notify Subcontractors and appropriate workforce providers when necessary for the resolution of the situation, except when unusual circumstances require confidentiality.

## Equal Employment Opportunity - MWH is committed to supporting EEO initiatives and will do the following:

- Review and disseminate, at least annually, MWH and subcontractor's EEO policy and affirmative action obligations under the CEIP with all employees having any responsibility for hiring, assignment, layoff, termination and other employment decisions.
- b) Provide cultural competency training, or provide access to such training, to all managers, supervisors, and owners, and conduct a review, at least annually, of all managers' and supervisors' adherence to and performance under MWH and subcontractor's EEO policies, affirmative action obligations, and cultural competencies.
- c) Provide the number of toilet facilities in an amount proportional to the ratio of women working on the project and will maintain a clean and free from graffiti, accessible and locking toilet for crew members who identify as women to help create a respectful environment.
- d) Provide clean, accessible, private, and locking lactation facilities separate from toilet facility.
- e) Documentation will be maintained by MWH of best efforts of compliance with all EEO strategies, workplace training participants, and MWH and all subcontractors shall exercise best efforts and work in good faith to achieve the workforce diversity goals and fulfill the requirements set forth for the life of the project.

# Apprenticeship / Pre-Apprenticeship

MWH recognizes the need to support programs designed to develop adequate numbers of competent workers in the construction industry and that effort is needed to facilitate the entry of historically disadvantaged or underrepresented people, including racial and ethnic minorities, women, and low-income people, who are interested in careers in the construction industry. MWH intends to utilize the trade workers from local 290 in self preformed work.

MWH is fully committed to increasing apprenticeship opportunities to ensure successful completion and retention of workers in the trades.

#### Goal:

For contracts (including Contractor and Subcontractors) in any tier of \$300,000 or more, twenty percent (20%) labor hours in each apprenticeable trade shall be worked by apprentices enrolled in a state-approved or federally approved apprenticeship program during all of the hours worked on the project. However, MWH will encourage all subcontractors regardless of the contract value to employ apprentices on the project in accordance with apprentice ratios.

Apprenticeship/Pre-Apprenticeship Planning, Hiring, and Tracking:

- a. As referenced earlier, before each subcontractor starts work on the project, MWH will have a pre-job startup meeting to go over CEIP goals on the project.
- b. To ensure that all apprentices on the project are enrolled in a state or federally registered apprenticeship program, MWH will get a workforce/apprenticeship plan (Exhibit 2 Form) before each subcontractor starts work and will verify training agent status in each trade to be worked with BOLI.
- c. MWH will ensure that subcontractors are registered with BOLI as approved training agents in all trades of work being performed. If a subcontractor is not approved, MWH will work with the subcontractor to become an approved training agent to ensure that there are no barriers to the apprenticeship goal being met.
- d. MWH and subcontractors will work with the union and non-union hiring resources and CBOs for open apprenticeship opportunities.
- e. Using a Worker Request Form, MWH will request female and minority apprentices from the union or open shop apprenticeship program to ensure that a diverse workforce is top of mind.
- f. If the apprenticeship program is unable to satisfy MWH or subcontractor's request, MWH shall contact recognized pre-apprenticeship programs, and/or CBOs which have been approved by BOLI, as a "first source" for referrals and seek to enroll interested individuals into the apprenticeship programs.

After the "first source," outreach is exhausted, MWH and subcontractors will contact other CBOs, which may not be BOLI approved, to request information on individuals that are or may be interested in enrolling in an apprenticeship program.

MWH wants to support those who seek careers in the construction trades and their programs are designed to build the necessary skills to meet the minimum entry qualifications to enter a trade or apprenticeship program.

- g. MWH will collect from all subcontractors and keep a list of late-term apprentices or journey workers that are working on the project site who are willing to serve as mentors for apprentices and pre-apprentices.
- h. MWH will ensure that apprentices are paid in accordance with state or federal prevailing wage rates applicable with the project.
- i. MWH will maintain and submit documentation of equity efforts as outlined in the CEIP.

# Documentation, Reporting and Program Evaluation

During the life of the project, MWH will document information regarding the implementation of the CEIP Construction Plan. Information to be documented including all aspects of the program, including but not limited to:

- The creation of DMWESB packages
- Inquiries of DMWESB interest in bidding, bid amounts, and contract awards

- Level of performance
- Subcontractor payments
- Subcontractor replacement requests/decisions
- Technical Assistance Provided
- Workforce Training and Hiring results
- Problems and successes experienced
- Mentoring and capacity building results, apprenticeship results, including disaggregated racial, ethnic, and gender data by the 5th of each month
- Results will be submitted electronically via the Contract Compliance Reporting System monthly and is subject to review by the CEIC. MWY will prepare two copies of these reports and submit them electronically via email to the City by the 15<sup>th</sup> of each month.
- Within 15 days of submitting the monthly report, MWH will prepare and update the project dashboard with detailed small business and workforce project data. MWH will meet monthly with CEIP to review DMWESB, and WFTH results.

# Workforce Diversity, Recruitment, and Retention

MWH recognizes and is fully committed to the recruitment, retention, and promotion of historically disadvantaged or underrepresented people, including racial and ethnic minorities and women who are interested in careers in the construction industry.

For contracts at any tier of \$300,000 or more, the goals for workforce diversity are:

- A. Apprentices: The workforce diversity goals for minority and women apprentice workers shall be thirty-one (31%) of total apprenticeable labor hours by trade, which shall be disaggregated as follows:
  - 1. Twenty-two percent (22%) of total apprentice hours by trade shall be worked by minority apprentices; and
  - 2. Nine percent (9%) of total apprentice hours by trade shall be worked by women apprentices.
- B. Journey Level: The workforce diversity goals for minority and women journey level workers shall be twenty-eight percent (28%) of total journey level hours, which shall be disaggregated as follows:
  - 1. Twenty-two percent (22%) of total journey level hours by trade shall be worked by minority journey level workers; and
  - 2. Six percent (6%) of total journey level hours by trade shall be worked by women journey level workers.

For contracts at any tier from \$100,000 - \$300,000, the goals for workforce diversity are:

A. Journey Level: The workforce diversity goals for minority and women journey level workers shall be twenty-eight percent (28%) of total journey level hours, which shall be disaggregated as follows:

- Twenty-two percent (22%) of total journey level hours by trade shall be worked by minority journey level workers; and
- 2. Six percent (6%) of total journey level hours by trade shall be worked by women journey level workers.

Hiring Procedures – MWH will establish and maintain hiring practices and opportunities that support the achievement of the diversity goals of the CEIP.

- a. As listed above, MWH will ensure that all apprentices on the project are enrolled in a state or federally registered apprenticeship program, MWH will get a workforce/apprenticeship plan before each subcontractor starts work and will verify training agent status in each trade to be worked with BOLI.
- b. MWH and subcontractors will work with the union and non-union hiring resources and CBOs for employment opportunities.
- c. Within 15 days of being awarded the contract or acceptance of the bid, MWH and subcontractors will notify the unions and non-union organizations of all opportunities for employment on the project.
- **d**. MWH and subcontractors will continue to provide the union and non-union organizations updated information on the project as scopes of work and bid packages are delineated.
- e. To attract minority and women workforce candidates, MWH will participate in community job fairs and other community workforce outreach events including Oregon Tradeswomen Career Fair, etc. MWH and subcontractors will inform unions, non-union organizations, apprenticeship programs, and CBOs of the goals in the CEIP and will request that diverse journey level workers and apprentices be referred.
- f. MWH is designating Andre' Baugh and Jennifer Erickson to be the point person(s) for participation and fulfilment of the requirements of the CEIP.

#### Recruitment and Retention

For contracts in excess of \$500,000, MWH and all subcontractors will setup and track the following information on recruitment:

- Conduct workshops with or otherwise solicit input from employees to enlist suggestions and ideas on how to increase employment of underutilized groups.
- Participate in or conduct job fairs to discuss the project and to recruit minority and women employees and subcontractors. MWH will
  participate in the Oregon Tradeswomen Career Fair and other local fairs that promote a diverse workforce in the construction
  industry.
- c. Allow scheduled jobsite visits, as safety allows, by participants in community programs to increase awareness of job and training opportunities in the construction trades. MWH will invite Pre-Apprenticeship program to brown bag site visit and discussion with project apprentices.
- d. Keep applications from qualified women and minorities for the duration of the project and notify them when an opening occurs.
- e. Participate in community outreach events and keep sign-in sheets from outreach efforts.

# 4. Compliance

MWH fully intends to meet the compliance requirements of this plan as it is a critical component to tracking, monitoring, and meeting the equity goals.

- Pre-Construction submittals will include solicitation and outreach efforts and award of subcontracts. Also, Exhibit 2, Projected Hiring Needs Form will be submitted for each subcontractor before they start work onsite.
- 2. Construction monthly submittals Certified Payrolls/workforce tracking will be submitted monthly for each firm as well as Monthly Subcontractor Payment and Utilization Reports.
  - a. Also, recruitment, retention, and graduation data will be compiled per the CEIP to fulfill the equity requirements.
  - b. Ensure timely electronic submittals
- Monthly Monitoring and Compliance all workforce, apprenticeship and DMWESB participation will be monitored on a monthly basis to
  ensure the CEIP requirements and goals are being met for all firms.
  - a. Corrective Action Plans (CAP) will be utilized to improve participation efforts, if needed, per the monitoring and compliance that is done each month.
- 4. Monthly CEIP reporting will be compiled to share with the Community Equity and Inclusion Committee. A project dashboard will be shared monthly with the Community Equity and Inclusion Committee that details small business and workforce project data.
- 5. Quarterly MWH will compile disaggregated racial, ethnic, and gender data monthly and provide data to the City for verification, per the CEIP.

# **ATTACHMENT A**

**Portland Water Bureau** 

**Corrosion Control Improvements Project** 

**Bid Packaging Plan 90%** 

Package	Package	Estimated	Opportunity	Procurement	D/I	M/W/ESB	D/M/W/ESB	D/M/W/ESB
No.	Description	Value	1st/2nd Tier	Strategy		(\$)	(% Package)	(% Project)
S-01	Site Conditions Survey	\$15,000	1st	Informal	\$	15,000	100%	0.16%
S-01A	Construction Survey (Quality Assurance)	\$15,000	1st	Informal	\$	15,000	100%	0.16%
S-02	Site Preparation	\$337,469	1st/2nd	Best-Value	\$	253,102	75%	2.67%
S-03C	Site Earthwork and Demolition	\$368,283	1st	Best-Value	\$	276,212	75%	2.91%
S-03D	Utility Water Pump Station Earthwork	\$570,934	1st/2nd	Price-Based	\$	57,093	10%	0.60%
S-03E	Access Road and Staging Area	\$301,178	1st	Best-Value	\$	225,884	75%	2.38%
S-04	Utility Water Pump Station Concrete	\$364,497	1st/2nd	Best-Value	\$	36,450	10%	0.38%
S-05	Site Concrete	\$683,673	1st/2nd	Price-Based	\$	68,367	10%	0.72%
S-08	Removal and Disposal of Contaminated Materia	\$10,000	1st	Informal	\$	10,000	100%	0.11%
S-09	PEMB and Metal Canopies	\$300,981	1st/2nd	Price-Based	\$	15,049	5%	0.16%
S-10	Tensile Membrane Structure	\$225,000	1st/2nd	Price-Based	\$	11,250	5%	0.12%
S-12	Painting and Coatings	\$134,560	1st	Informal	\$	134,560	100%	1.42%
S-14	HVAC	\$205,000	1st	Best-Value	\$	153,750	75%	1.62%
S-15	Electrical	\$2,056,269	1st/2nd	Price-Based	\$	205,627	10%	2.17%
S-15A	Instrumentation and Controls	\$188,500	1st/2nd	Price-Based	\$	9,425	5%	0.10%
S-16	Utilities Piping	\$395,967	1st/2nd	Best-Value	\$	118,790	30%	1.25%
S-17	Process Piping	\$2,516,758	1st/2nd	Price-Based	\$	377,514	15%	3.98%
S-18	Horizontal Directional Drilling	\$136,188	1st/2nd	Price-Based	\$	13,619	10%	0.14%
S-19	AC Pavement and Base	\$158,030	1st	Best-Value	\$	118,523	75%	1.25%
S-20	Chain Link Fencing	\$34,300	1st	Informal	\$	34,300	100%	0.36%
S-21	Landscaping	\$237,295	1st	Best-Value	\$	237,295	100%	2.50%
S-22	Tree Removal - AWARDED	\$73,600	1st	Informal	\$	73,600	100%	0.78%
P-02	Pumps	\$121,086	-	Price-Based	\$	-	0%	0.00%
P-03	Chemical Feed System	\$46,825	-	Price-Based	\$	-	0%	0.00%
	Hard Construction Cost = \$9,496,393				\$2,	,460,409	25.91%	25.91%

Estimated Values shown above are based on the MWH Estimate of the 90% design documents. This bid packaging plan shows DMWESB participation at a higher rate (i.e. 25.91% of hard construction costs) than the subcontracting goal identified in the CEIP (i.e. 22% of hard construction costs). Actual DMWESB participation will not be known until the work is bid/released.

- DMWESB (\$) Values shown represent the expected dollars to be awarded to a qualified DMWESB contractor.
- DMWESB (% Package) Dollars expected to be awarded to a qualified DMWESB contractor divided by the estimated value of the package as expressed as a percentage.
- DMWESB (% Project) Dollars expected to be awarded to a qualified DMWESB contractor divided by estimated total hard construction cost as expressed as a percentage.

# **ATTACHMENT B**

# MWH Harassment Free Workplace Signature Page – Sample

MWH - Corrosion Control Improvements Project

I have read and successfully completed the MWH Harassment Free Workplace Training

Name:	
Signature:	
Date of Training and: _	
Company & Supervisor: _	 
Date:	

# COMMUNITY EQUITY AND INCLUSION PARTNERSHIP AGREEMENT

("Partnership Agreement")

The City of Portland, community-based member organizations, contracting trade organizations, building trades (both union and non-union) and training/workforce pipeline providers, as signatories to this agreement ("Parties"), commit to supporting the social equity components for construction contracts subject to the Community Equity and Inclusion Plan ("CEIP").

The Parties recognize the importance of tracking achievement of diversity goals and reporting on compliance with diversity goals and Equity Efforts set forth in the CEIP for these contracts. Diversity goals include those goals set forth in Sections 2 and 3 of this Partnership Agreement. The Parties are committed to cooperating and communicating with each other to achieve the City's diversity goals on these contracts and will support and work to achieve the diversification of contractors, suppliers, and workers in construction.

In order to further these efforts, the Parties support the following four components included in this Partnership Agreement:

- Community Apprenticeship Requirements a set of requirements for participation of apprentices on all construction contracts at any tier of \$300,000 or more subject to the CEIP, consistent with City contracting requirements for all construction contracts
- II. Community Workforce Recruitment and Retention Goals a set of standard aspirational goals for women and minority workforce participation on all construction contracts at any tier of \$300,000 or more subject to the CEIP, updated on an annual basis
- III. Subcontracting Goals- a set of standard aspirational goals for D/M/W/ESB participation on all construction contracts subject to the CEIP, updated on an annual basis
- IV. Community Equity and Inclusion Committee a standing committee (or committees) to review and support the work of the City and Contractors to achieve equity goals

Each of these is further described in the following pages.

## I. COMMUNITY APPRENTICESHIP REQUIREMENTS

The Parties recognize the need to maintain continuing support of programs designed to develop adequate numbers of competent workers in the construction industry. The Parties agree that effort is needed to facilitate the entry of historically disadvantaged or underrepresented people, including racial and ethnic minorities, women, and low-income people, who are interested in careers in the construction industry. The Parties support the goal of increasing apprenticeship opportunities on public projects and ensuring successful completion and retention of workers in the trades.

For City construction contracts subject to a Community Equity and Inclusion Plan, the requirements for community apprenticeship opportunities shall be as follows.

# Community Apprenticeship Requirements

For contracts (including Contractor and Subcontractors) in any tier of \$300,000 or more, twenty percent (20%) labor hours in each apprenticeable trade shall be worked by apprentices enrolled in a state-approved or federally-approved apprenticeship program during all of the hours worked on the Project.

Apprenticeable trades shall include only those that are state or federally-certified. It shall not include the following trades or classifications: flag person, timekeeper, office engineer, estimator, bookkeeper, clerk/typist, or secretary. Such trades are exempt from this requirement.

# II. COMMUNITY WORKFORCE RECRUITMENT AND RETENTION GOALS

The Parties recognize the need to facilitate the recruitment, retention, and promotion of historically disadvantaged or underrepresented people, including racial and ethnic minorities, and women who are interested in careers in the construction industry.

For City construction contracts subject to a Community Equity and Inclusion Plan, the aspirational goals for community workforce recruitment and retention shall be as follows.

## Community Workforce Goals

For contracts at any tier of \$300,000 or more, the aspirational goals for workforce diversity as set forth below shall apply.

A. Apprentices: The aspirational workforce diversity goals for minority and women apprentice workers shall be thirty-one percent (31%) of total apprenticeable labor hours by trade, which shall be disaggregated as follows:

- Twenty-two percent (22%) of total apprentice hours by trade shall be worked by minority apprentices; and
- Nine percent (9%) of total apprentice hours by trade shall be worked by women apprentices.
- B. Journey Level: The aspirational workforce diversity goals for minority and women journey level workers shall be twenty-eight percent (28%) of total journey level hours, which shall be disaggregated as follows:
  - Twenty-two percent (22%) of total journey level hours by trade shall be worked by minority journey level workers; and
  - Six percent (6%) of total journey level hours by trade shall be worked by women journey level workers.

The Parties support allowing for and encouraging workforce providers to prioritize the placement of women and minorities to meet these community workforce goals, and will make efforts to assist the Contractor in achieving these goals.

## III. SUBCONTRACTING GOALS

The Parties recognize that one of the barriers to entry for many Disadvantaged Business Enterprise, Minority-OwnedBusiness, Women-OwnedBusiness and Emerging Small Businesses ("D/M/W/ESB") is that D/M/W/ESB firms are afforded fewer opportunities to contract with non-D/M/W/ESB prime contracting firms on commercial construction contracts of the type generally contracted for by the City of Portland. Historical disparity has adversely impacted opportunities for disadvantaged, minority-owned and women-owned firms in the construction industry.

For City construction contracts subject to a Community Equity and Inclusion Plan, the aspirational goals for D/M/W/ESB participation shall be as follows:

# Subcontracting Goals

For all work performed on Projects subject to CEIPs, the aspirational base-line utilization goal for firms that have been certified by the State of Oregon as a Disadvantaged Business Enterprise, Minority-Owned Business, a Women-Owned Business, or an Emerging Small Business ("D/M/W/ESB") is twenty-two percent (22%) of the Hard Construction Costs for the Project, which shall be disaggregated as follows:

A. Twelve percent (12%) minimum aspirational goal for firms certified as

Disadvantaged Business Enterprises ("DBE") or Minority-Owned Business Enterprises ("MBE");

- B. Five percent (5%) minimum aspirational goal for firms certified as Women-Owned Business Enterprises ("WBE"); and
- C. The remaining percentage may be any combination of Disadvantaged Business Enterprises, Minority-Owned Businesses, Women-Owned Businesses, or Emerging Small Businesses.

The Parties support these subcontracting goals and will make efforts to assist the Contractor in achieving these goals.

## IV. COMMUNITY EQUITY AND INCLUSION COMMITTEE

In order to help achieve diversity goals and review compliance, the Community Equity and Inclusion Committee ("CEIC") is established as a review body and resource for the City and its Contractors and the broader community. The Contractor and Subcontractors for each project subject to the CEIP are responsible for achieving the Equity Efforts as set forth in the CEIP and for ensuring compliance with the requirements of the CEIP. The CEIC will assist the Contractor and Subcontractors to achieve the goals herein, and will review compliance and Equity Eff ort s.

## The CEIC shall:

- Review the performance of City projects subject to the Plan;
- Report on a quarterly basis on whether projects are achieving goals;
- Provide guidance and advice to Contractors on achieving diversity goals, providing assistance in real time in order to help Contractors increase utilization of D/M/W/ESB firms and minority and female workforce on City projects;
- Provide guidance on outreach and engagement of Subcontractors;
- Provide guidance on outreach and engagement of workers, including helping with securing apprentices;
- Facilitate connections to and among Contractor, Subcontractors, unions, non-union organizations, pre-apprenticeship training programs, community organizations, and workers;
- Advise Procurement Services and the bureaus on whether Contractors are meeting the Equity Efforts in the Plan;
- Advise annually on any modifications to standard requirements and goals contained in this agreement;

- Advise on any requests for project-specific exemptions or modifications to the goals contained in this agreement;
- Provide recommendations to the City on potential uses of Community Opportunity and Enhancement Funds.

The City of Portland as Owner is responsible for enforcing the terms of CEIPs and Contracts. The CEIC provides advice, guidance, and input to the City and project managers ("Owner") and to Contractors subject to CEIPs.

# Composition of the CEIC

The CEIC shall be composed of individuals representative of the following groups.

- Community Member Organizations
- Contractors (including at least one DMWBE firm and at least one non-DMWESB firm)
- Contracting trade associations (including at least one minority contracting trade association)
- Building Trades (both union and non-union)
- Training/Pipeline Providers (pre-apprenticeship and apprenticeship programs)

Collectively the CEIC should have generalized or specific knowledge of workforce and subcontractor market availability, union and non-union resources, community interests and needs.

# Selection of CEIC Members

The Chief Administrative Officer, the Director of the Office of Equity and Human Rights, and a Bureau Director representing one of the major infrastructure bureaus (Water, Parks, BES, or PBOT), will solicit applications and recommendations for members and will appoint members, with the committee including a balance of members from the groups described above.

## Size of CEIC

The CEIC may have between nine and fifteen members at any one time with only one person as an official representative of any one organization. The group may split into different sub- committees to consider projects, in order to best use the time of members, address capacity issues (with multiple ongoing projects), and/or avoid potential conflicts of interest for particular members.

## Reporting Relationship

The CEIC provides advice and guidance to the Owner (bureau directors and project managers) and the Contractor for construction contracts covered by CEIPs and to the Chief Procurement Officer.

# Advisory Role

The CEIC is not a "decision-making" body, but rather an advisory body. The body is not required to vote on recommendations, but rather discusses matters, and individually or collectively, provides advice and guidance.

# Staff Support

The CEIC receives staff support from the Procurement Services Division of the Bureau of Revenue and Financial Services.

# Conflicts of Interest

All members of the CEIC shall complete Conflict of Interest/Non-Disclosure forms each year they serve as volunteers on the committee. Members will recuse themselves from participating in reviewing and advising on projects that they are involved in which could or would result in financial benefit or detriment to that member, a relative of the member, or a business with which either is associated.

## Meetings

Monthly meetings will be scheduled, with a mix of different projects discussed at each meeting.

## <u>Attendees</u>

Additional attendees at CEIC meetings may include Contractors, Subcontractors, unions, non- union organizations, CBOs, workers, and any other interested individual or organization.

# Parties to the Community Equity and Inclusion Partnership Agreement

City of Portland (CPO, Bureau Directors), community member organizations, contractors, contracting trade associations, building trades, training/pipeline providers.

Signatures:		
Mchau Maar	MWH Constructors	6/10/20
1		Date
		Date
		Date
		Date
		- Date