



Project Title:
**HRC 9 Core
Lab Equipment
Replacement**

PKA Project Number: 201006
Client Project Number: 21HRC064

Hatfield Research Center
3251 SW Sam Jackson
Park Rd, Portland, OR
97239
Key Plan

Revisions shown below may not apply to
this publication

Revision	Date
AS 001	29 Sept 2021

Sheet Title
**Floor Plan
Phase 5**

Sheet Number:
A2.9.10

BID & PERMIT SET

20 MAY 2021

Floor Plan General Notes:

- For General Drawing Standards and Abbreviations see sheet G0.2.01
- For General Notes see sheet A0.1.01
- For Standard mounting heights of fixtures/equipment see sheet A0.2.01
- For Fixture/Equipment abbreviations see sheet A0.2.01

Floor Plan Keynotes:

- a01. Relocated existing equipment.
- a02. Patch flooring where seismic anchoring of old equipment was located throughout.
- a03. New electrical panel. See electrical.
- a04. New equipment.
- a05. Patch back fireproofing at anchoring connections.
- a06. Remove and replace ceiling as required for installation of anchoring.
- a07. Provide new metal side panel on cabinet.
- a08. Remove and relocate backslash or provide new. Push up tight to column.
- a09. Relocated power pole see electrical.
- a10. Replace grid and ceiling tile where exhaust is removed. Match existing.

