Development Services

From Concept to Construction

Phone: 503-823-7300 Email: bds@portlandoregon.gov 1900 SW 4th Ave, Portland, OR 97201 More Contact Info (http://www.portlandoregon.gov//bds/article/519984)

APPEAL	SUMMARY
	0011111/1 (1 (1

Status: Decision Rendered

Appeal ID: 14726	Project Address: 7119 SE Milwaukie Ave
Hearing Date: 3/8/17	Appellant Name: Jennifer Nye
Case No.: B-008	Appellant Phone: 5032236693
Appeal Type: Building	Plans Examiner/Inspector: Natalie Davis
Project Type: commercial	Stories: 4 Occupancy: R-2, S-2, A-2, A-3 Construction Type: I-A, V-A
Building/Business Name: Sellwood Mixed Use	Fire Sprinklers: Yes - throughout
Appeal Involves: Erection of a new structure	LUR or Permit Application No.: 16-289044-CO
Plan Submitted Option: pdf [File 1] [File 2] [File 3] [File 4] [File 5]	Proposed use: Mixed Use Apartment Building

APPEAL INFORMATION SHEET

Appeal item 1

Code Section	1207 Sound Transmission
Requires	STC ratings tested in accordance with ASTM E 90 and IIC transmission tested in accordance with ASTM E 492.
Proposed Design	Provide STC and IIC ratings evaluated by a licensed acoustical engineer specific to the floor/wall assemblies proposed. Floor assembly 5, 7, 8; wall assembly 43.
Reason for alternative	The assemblies were based on reaching a 1-hr fire rating but the rated assemblies contain the components that are not proposed in our project (cushioned sheet vinyl) or do not have associated sound test.
	The analysis provided by the professional acoustical engineer provides an equivalent assurance of sound performance to at tested/listed assembly.
Appeal item 2	
Code Section	703.2 Fire-resistive ratings
Requires	The fire-resistance rating of building elements, components or assemblies shall be determined in accordance with the test procedures set forth in ASTM E 119 or UL 263 or in accordance with 703.3.

Proposed Design	We have proposed a 3x decking with 1/2" plywood over the commercial spaces in lieu of a listed 1-hr floor assembly, a fire engineer's letter is attached.					
Reason for alternative	For the commercial space we wanted a more open post/beam look with exposed deck while					
	maintaining a 1-hr fire rating.					
	The proposed use of alternative materials provide equivalent fire ratings based the fire engineer's letter.					
Appeal item 3						
Code Section	1812 Radon Control					
Requires	Section 1812.1 Scope. The provisions of this section apply to new Group R-2 and R-3					
	Yambill Counties for which initial building permits are issued on or after April 1, 2011					
	Section 1812.3.2 – Subfloor Preparation. A layer of gas permeable material shall be placed under all concrete slabs and other floor systems that directly contact the ground and are within the walls of the living spaces of the building, to facilitate future installation of a sub-slab depressurization system, if needed.					
	Section 1812.3.3 – Soil-gas-retarder. A minimum 6-mil polyethylene or equivalent flexible sheeting					
	floor assembly to serve as a soil-gas-retarder by bridging any cracks that develop in the slab or					
	floor assembly and to prevent concrete from entering the void spaces in the aggregate base material.					
	Section 1812.3.6 – Passive subslab depressurization system (basement or slab-on-grade). In basement or slab-on-grade buildings, subslab soil exhaust system ducts complying with Section 1812.3.7 shall be installed during construction.					
	Section 1812.3.7 – Subslab soil exhaust system ducts (SSESD). SSESD's shall be provided in accordance with this section and shall run continuous from below the soil-gas-retarder to the termination point described in section 18.12.3.7.5					
Proposed Design	We have proposed a 4-story apartment building over a basement garage with a section of the building having on-grade commercial space and 3-stories of apartments above. No residential units are slab-on-grade.					
	The basement level is a mechanically ventilated garage and support spaces that are either mechanically ventilated or naturally ventilated meeting the requirements of the OSSC.					
	The unfinished commercial shell space will meet, at a minimum, a ventilation rate per (IMC 403.3).					
	With the proposed system, all spaces between the slab-on-grade conditions and the residential/living areas will be ventilated at a rate that exceeds that which is required for Radon					
	Control with a Passive Subslab depressurization system.					
Reason for alternative	The code compliant mechanical ventilation systems for the ground floor uses of retail, restaurant,					
	and support spaces meet the requirements of the mechanical code. We propose that due to the ground floor spaces having ventilation and exhaust rates that exceed that which is required for					
	radon control, that the building meets or exceeds the intention of the code to prevent radon gas impacts to residential spaces.					

Appeal item 4

https://www.portlandoregon.gov/bds/appeals/index.cfm?action=entry&appeal_id=14726

Appeals | The City of Portland, Oregon

Code Section	510.2 Horizontal building separation allowance
Requires	The buildings are separated with a horizontal assembly having a fire-resistance rating of not less than 3 hours.
Proposed Design	We have proposed to separate our residential floor area into two buildings to allow us to have two V-A buildings separated by a fire wall. The fire wall sits on a I-A podium (cast-in-place concrete) with a 3 hour rating using the provision of section 510.2. We have proposed a 3 hour horizontal assembly separating the basement from the upper levels of the building but turned the 3 hour separation down to a wall generally where the basement meets the slab-on-grade area.
	The two locations where the 3-hour wall does not follow this elevation difference are the exit passageway and NE stair. We made exceptions at these two locations based on wanting the keep the exit passageway within the building it is primarily serving and the NE Stair because it the edge of the concrete enclosure at this edge due to the stair shaft.
	Section 510.2 allows vertical penetrations through the 3 hour horizontal assembly to be 2-hour rating with 90-minute openings. We have proposed the western stair shafts be 3-hour rated with 180 minute doors. The NE Stair & Exit Passageway will have a 3-hr wall at the building separation line with 180-minute door. The opening separating the Street Lobby and the Lower Lobby will have a 180-minute horizontal sliding, accordion folding fire door. The elevator shafts will be separated from the basement by 3 hour walls with 90-minute doors and separate smoke curtains. The smoke curtains and the horizontal sliding, accordion folding fire door will be connected the fire alarm system. In addition we propose to provide a fire sprinkler head within 5-feet of the elevator doors.
Reason for alternative	The basement level sits below the street grade of the commercial spaces, we needed to transition the fire separation vertically at some location. We considered turning the rating up and encompassing the commercial spaces within the lower building but this posed structural challenges and we did not believe that it created a safer building than what we have proposed. The building has aerial fire apparatus access on the two long sides and four stairs connecting the building vertically, the SE stair provides roof access through a roof hatch. The building has a sprinkler system throughout. The horizontal separation is not being used for additional building height. Based on these considerations we believe the prosed 3-hr wall and associated opening protections provide an equivalent level of fire safety.

APPEAL DECISION

1. Sound transmission rating at wall and floor-ceiling assemblies per Engineered analysis: Granted as proposed for wall assembly and joisted floor assemblies. HOLD for additional clarification of heavy timber floor assembly.

2. Alternate method for determining 1 hour fire resistance rating of exposed floor/ceiling assembly: Granted provided the clear spans are 5'-3" supporting public areas and 6'-9" maximum supporting residential uses.

3. Omission of radon control measures in mixed use building: Granted as proposed and provided mechanical ventilation is installed in all first floor spaces.

4. Discontinuous 3 hour horizontal assembly separating buildings: Denied. Proposal does not provide equivalent separation.

Appellant may contact Catherine Heeb (503-823-7657) for additional information.

Appeals | The City of Portland, Oregon

Pursuant to City Code Chapter 24.10, you may appeal this decision to the Building Code Board of Appeal within 180 calendar days of the date this decision is published. For information on the appeals process and costs, including forms, appeal fee, payment methods and fee waivers, go to www.portlandoregon.gov/bds/appealsinfo, call (503) 823-7300 or come in to the Development Services Center.

II. Performance Standards

City of Portland Building Code

The City of Portland Development Services Center states that common wall and floor/ceiling assemblies between adjacent units and between dwelling units and adjacent public areas such as halls, corridors, stairs, or services areas have a minimum Sound Transmission Class (STC) of 50 and floor-ceiling assemblies also have a minimum Impact Insulation Class (IIC) of 50.

The designer has three options for documenting required STC and IIC ratings:

- 1. Detail listed and approved STC and IIC assemblies on the plans from approved list of published assemblies, noted <u>here</u>.
- Obtain approval from Administrative Appeal Board for an alternative assembly. To be approved, the Appeal must include a detail of the proposed assembly, and an analysis stamped by a qualified state of Oregon licensed professional that concludes that the proposed assembly will provide the required STC and IIC ratings.
- 3. Specify an assembly to be Field Tested. Be aware there is a risk that an assembly can fail the field test, and require modifications after the building is finished.

International Building Code (IBC)

Section 1207 – Sound Transmission

1207.1 Scope. This section shall apply to common interior walls, partitions and floor/ceiling assemblies between adjacent dwelling units or between dwelling units and adjacent public areas such as hall, corridors, stairs and service areas.

1207.2 Air-borne sound. Walls, partitions, and floor/ceiling assemblies separating dwelling units from each other or from public or service areas hall have a sound transmission class (STC) of not less than 50 (45 if field tested) for air-borne noise when tested in accordance with ASTM E 90.

1207.3 Structure-borne sound. Floor/ceiling assemblies between dwelling units or between a dwelling unit and a public or service area within the structure shall have an impact insulation class (IIC) rating of not less than 50 (45 if field tested) when tested in accordance with ASTM E 492.

These ASTM standards are the laboratory equivalent of the field tests conducted for finished assemblies.

III. Assembly Description

The following proposed roof-ceiling assembly was evaluated with respect to air-borne sound and footfall noise impact performance to the STC 50 and IIC 50 performance requirements.

Floor-Ceiling Assembly

Luxury Vinyl Tile (LVT) or similar flooring finish 1-1/4" gypsum lightweight concrete (13 psf) 1/4" acoustic underlayment (0.2 psf) 1/2" plywood (1.6 psf) 3" tongue & groove wood decking (5.4 psf)

FLOOR FINISH, SEE ROOM FINISH SCHEDULE 14" GYPSUM UNDERLAYMENT OVER 14" ACCOUSTICE SOUND CONTROL MAT 10000, SEE STRUCA × DECKING, SEE STRUCT

IV. Predicted Performance

The predicted performance for the heavy timber floor-ceiling assembly is noted below for the pieces evaluated from laboratory test results, independent field tests, and computer modeling software.

Baseline Proposed Assembly Evaluated	Performance
Prediction for assembly: Laboratory Test Results: NGC Report # 5014082, 7014109 June 2, 2014 (attached to this report) 1. No finished floor 2. 4" concrete 3. 1x6 T&G wood plank 4. 3x6 T&G wood plank 5. 8' on-center wood beams	STC 40 IIC 34
Predicted improvement / reduction from: Plus (+) 1/4" acoustic sound control mat Plus (+) finished floor luxury vinyl tile (LVT) Minus (-) 1-1/4" lightweight gypsum underlayment, instead of 4" concrete	<u>STC</u> 1. Plus (+) 10 to 12 2. Plus (+) 0 to 1 3. Minus (-) 6 to 8 <u>IIC</u> 1. Plus (+) 10 to 12 2. Plus (+) 2 to 4 3. Minus (-) 6 to 8
Predicted Acoustic Performance	STC 44 – 46 IIC 40 – 44

V. Recommendations

Due to limited laboratory performance data for heavy timber construction floor/ceiling assemblies the following recommendations are based on similar projects and laboratory tests that note the performance difference between the recommended options and the tested assemblies.

Option 1 – Code Compliant: Predicted Lab STC 50 – 52 / IIC 50 – 52

- 1. Install 2.0-inches of lightweight concrete on 3/4" to 1" thick acoustic sound control mat below the gypcrete.
 - a. Material Options:
 - i. 3/4" thickness: Keene Building Products <u>Quiet Qurl 65/075 N MT</u>, Maxxon <u>Acousti-Mat 3 HP</u>
 - ii. 1" thickness dimpled recycled rubber: <u>Pliteq GenieMat FF-25</u>, <u>Regupol SonusWave</u> 25-mm, <u>Ecore QTrbm</u> QT3025-7
- 2. Install 2nd layer of plywood or 1 layer of 1/2" cement board over the plywood sheathing with the 3/4" thick sound control mats; not necessary with 1" thick due to additional material weight for rubber mat.
- 3. Install hard surface flooring (engineered wood, vinyl, or similar) on 1/8" thick recycled rubber underlayment.
 - a. Products: <u>Pliteq GenieMat RST</u>, <u>Regupol Sonus</u>, <u>Ecore QTscu</u>, <u>Durason</u>

Option 2 – Improved Performance: Predicted Lab STC 52+ / IIC 52+

- 1. Install 2.0-inches of standard concrete or 3.0-inches of lightweight concrete on 1-3/8" thick acoustic sound control mat below the gypcrete.
 - a. Material Options:
 - iii. 1-3/8" thickness dimpled recycled rubber (1 layer of 1" and 1 layer of 3/8"): <u>Pliteq GenieMat FF-17 and FF-25</u>, <u>Regupol SonusWave</u> 17-mm and 25-mm, <u>Ecore QTrbm</u> QT3017-8 and 3025-7
- 2. Install 2nd layer of plywood or 1 layer of 1/2" cement board over the plywood sheathing.
- 3. Install hard surface flooring (engineered wood, vinyl, or similar) on 1/8" thick recycled rubber underlayment.
 - a. Products: Pliteq GenieMat RST, Regupol Sonus, Ecore QTscu, Durason

VI. Predicted Performance with code compliant recommendations

Due with respect to sound transmission (STC) and footfall impact noise (IIC), the assembly has been split into parts to evaluate the impact of these materials and installations on the overall predicted performance.

Recommended Assembly Evaluated	Performance
Prediction for overall assembly: Laboratory Test Results: NGC Testing Services, test # 5014141, #7014194; 9/12/2014	
96" OC	
	STC 53
GenieMat ^{TW} RST05 2" USG Levelrock GenieMat ^{TW} FF42 Underlayment 1/2" Durock Cement Board 1x6 Wood Plank 3x6 Wood Plank	IIC 52
12"x12" Wood Beam 8' OC	
Field tests for similar heavy timber construction had STC and IIC ratings greater than STC/IIC 55, but the assembly details were less specific than the above noted laboratory tests.	
Predicted improvement / reduction from: Minus (-) 3 mm instead of 5 mm under hard-flooring; 1"	<u>STC</u> 1. Minus (-) 0 to 3
concrete	IIC
	1. Minus (-) 1 to 2
	STC
	50 – 53
Predicted Acoustic Performance	
	IIC
	50 – 51

VII. Conclusion

The proposed flooring-ceiling assembly will satisfy the International Building Code (IBC) sound transmission requirements of STC 50 and IIC 50 with one of the recommended alternatives.

Please contact us if you have any questions or for additional information.

Sincerely,

Erik Miller-Klein, P.E. Partner & Acoustical Consultant

A3 Acoustics, LLP 1455 NW Leary Way, Suite 400 Seattle, WA 98107 206.489.5183 – Office 206.658.7920 – Cell erik@a3acoustics.com



RENEWAL DATE: 12/31/2016



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 1 of 5

TEST REPORT

For

Pliteq, Inc.

1370 Don Mills Road, Unit 300 Toronto, ON. Canada M3B 3N7 Wilson Byrick/ 416-449-0049

Sound Transmission Loss Test

ASTM E 90 - 04 / E 413 - 10

On

Wood Beam Factory Style Floor-Ceiling Assembly Overlaid with; 4 Inch Concrete Slab

Report Number: NGC 5014082

Assignment Number: G-877

Test Date: 6/02/2014

Report Approval Date: 6/18/2014

Submitted by: _

Andrew E. Heuer Senior Test Engineer

Reviewed by: Robert J. Menchetti Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

> NGC 5014082 Pliteq, Inc. 6/18/2014 Page 2 of 5

Revision Summary:

Date	SUMMARY
Approval Date: 6/18/2014	Original issue date. Original NGCTS report: NGC 5014082

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Report Number: NGC 5014082

Page 3 of 5

Test Method: This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements - Designation: E 90 - 04 / E 413 - 10.

Specimen Description: Wood Beam Factory Style Floor-Ceiling assembly overlaid with, according to client, 4 inch concrete slab

The test specimen was a floor-ceiling assembly observed to consist of the following: All measured weights and dimensions are averaged:

- 101.6 mm (4 in.) concrete slab, weighing: 223.30 kg/m² (45.74 PSF)
- 1 layer of, according to the client, 1" T&G wood planks. The top layer of subflooring was nailed to the bottom layer of subflooring at random lenths. Subfloor measured dimensions: 3657.60 mm x 149.23 mm x 19.05 mm (144 in. x 5-7/8 in. x 0.75 in.). Subfloors measured weight: 7.37 kg/m² (1.51 PSF)
- 1 layer of, according to client, 3" T&G wood planks. The bottom layer of subflooring was nailed to the underlying support beams at random lengths. Subfloor measured dimensions: 4876.8 mm x133.4 mm x 57.15 mm (192 in. x 5-1/4 in. x 2-1/4 in) Subfloor measured weigh: 26.32 kg/m² (5.39 PSF)
- Two (2), 3505.2 mm x 304.8 mm x 304.8 mm (138 in. x 12 in. x 12 in.) Support beams placed 2438.4 mm (96 in.)
 O.C, allowing 1219.2 mm (48 in.) of space from each end of the test frame.
 Measured weight of the beams: 206.95 kg/m² (5.07 PSF)

The overall weight of the test assembly: 281.74 kg/m2 (57.71 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough. The test assembly was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)
Conditioning: All materials were tested as received. Concrete cured a minimum of 28 days.
Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Sound Trar	nsmissior	ו Loss Te	st Data				
Test: ASTM E 90	0 - 04 / ASTM	E 413 - 10					
Test Report: I Specimen Size [r	NGC5014082 n²]:	17.8		Date:	6/2/2014		Page 4 of 5
Source room Volume [m³]: Rm Temp [°C]: 2 Humidity [%]:	53.2 22.5 54				Receiving roo Volume [m ³]: Rm Temp [°C] Humidity [%]:	m 69.3 : 21.5 59	
Sound Transmis Sum of Unfavorable I Max. Unfavorable De	ssion Class S Deviations [dB]: viation [dB]:	STC [dB]: 26 5	40 at	315	Hz		
Frequency	STL	L1	L2	d	Corr.	u.Dev.	∆STL
[Hz]	[dB]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
100	24	101.9	82.7	29.2	4.8		1.61
125	24	101.2	83.3	23.8	6.1		2.58
160	24	100.9	82.9	22.7	6.0	3	2.28
200	26	100.9	80.9	24.6	6.0	4	1.44
250	31	101.7	76.2	29.6	5.5	2	0.93
315	31	98.3	72.3	28.8	5.0	5	1.72
400	35	99.3	69.8	29.6	5.5	4	0.57
500	36	98.5	67.6	30.4	5.1	4	1.21
630	40	99.9	64.9	34.2	5.0	1	0.55
800	39	99.6	64.4	37.9	3.8	3	0.58
1000	43	96.1	57.3	40.3	4.2		0.91
1250	48	95.3	51.1	40.7	3.7		0.90
1600	53	95.5	46.5	39.2	3.9		1.05
2000	56	97.7	45.1	39.6	3.4		0.74
2500	60	98.5	42.1	39.7	3.6		0.74
3150	63	97.2	38.0	43.6	3.8		0.92
4000	64	94.1	32.8	52.2	2.6		0.62
5000	66	86.4	22.4	55.6	1.9		0.94
	۵	STL = Sou L1 = Sou L2 = Rec d = Dec STL = Unc	nd Transmiss rce Room Lev eiving Room I ay Time, dB/s ertainty for 95	ion Loss, dB rel, dB ∟evel, dB econd 5% Confidence	e Level		

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 1 of 5

TEST REPORT

for

Pliteq, Inc. 1370 Don Mills Road, Unit 300 Toronto, ON. Canada M3B 3N7 Wilson Byrick/ 416-449-0049

Impact Sound Transmission Test

ASTM E 492 - 09 / ASTM E 989 - 06

On

Wood Beam Factory Style Floor-Ceiling Assembly Overlaid with; 4 Inch Concrete Slab

Report Number:	NGC 7014109
Assignment Number:	G-877
Test Date:	6/02/2014
Report Approval Date:	6/18/2014
Submitted by:	Cid C
Reviewed by:	Andrew E. Heuer Senior Test Engineer Robert J. Mehchetti Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

> NGC 7014109 Pliteq, Inc. 6/18/2014 Page 2 of 5

Revision Summary:

Date	SUMMARY		
Approval Date: 6/18/2014	Original issue date. Original NGCTS		
	report: NGC 7014109		

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 3 of 5

Report Number: NGC 7014109

Test Method: This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine -Designation: E 492-09/ E 989-06.

The uncertainty limits of each tapping machine location met the precision requirements of section A1.4 of ASTM E 492-09.

Specimen Description: Wood Beam Factory Style Floor-Ceiling assembly overlaid with, according to client, 4 inch concrete slab.

The test specimen was a floor-ceiling assembly observed to consist of the following: All measured weights and dimensions are averaged:

- 101.6 mm (4 in.) concrete slab, weighing: 223.30 kg/m² (45.74 PSF)
- 1 layer of, according to the client, 1" T&G wood planks. The top layer of subflooring was nailed to the bottom layer of subflooring at random lenths. Subfloor measured dimensions: 3657.60 mm x 149.23 mm x 19.05 mm (144 in. x 5-7/8 in. x 0.75 in.). Subfloors measured weight: 7.37 kg/m² (1.51 PSF)
- 1 layer of, according to client, 3" T&G wood planks. The bottom layer of subflooring was nailed to the underlying support beams at random lengths. Subfloor measured dimensions: 4876.8 mm x133.4 mm x 57.15 mm (192 in. x 5-1/4 in. x 2-1/4 in) Subfloor measured weigh: 26.32 kg/m² (5.39 PSF)
- Two (2), 3505.2 mm x 304.8 mm x 304.8 mm (138 in. x 12 in. x 12 in.) Support beams placed 2438.4 mm (96 in.)
 O.C, allowing 1219.2 mm (48 in.) of space from each end of the test frame.
 Measured weight of the beams: 206.95 kg/m² (5.07 PSF)

The overall weight of the test assembly: 281.74 kg/m² (57.71 PSF)

The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough. The test assembly was structurally isolated from the receiving room.

Specimen size:3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)Conditioning:All materials were tested as received.Test Results:The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

						Page 4 of 5
Test Report:	NGC7014109)		Date	: 6/2/2014	- ig-
Specimen Size	[m²]:	17.8				
Source room					Receiving roo	m
					Volume [m ³]:	69.3
Rm Temp [°C]:	22.5				Rm Temp [°C]:	21.5
Humidity [%]:	54				Humidity [%]:	59
Impact Insulati	on Class IIC	[dB]:	34			
Sum of Unfavorable	Deviations [dB]:	31				
Max. Unfavorable D	eviation [dB]:	8	at	3150	Hz	
Frequency	L	L2	d	Corr.	u.Dev.	ΔL _n
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
100	66	68.3	31.7	-2.3		2.78
125	64	67.3	22.5	-3.3		0.89
160	69	73.5	21.2	-4.5		1.24
200	74	76.9	24.5	-2.9		1.36
250	74	76.9	29.9	-2.9		0.75
315	75	78.0	29.0	-3.0		0.41
400	76	78.9	29.8	-2.9		0.38
500	75	77.6	29.7	-2.6		0.44
630	76	77.8	34.2	-1.8	1	0.40
800	76	77.3	38.1	-1.3	2	0.62
1000	75	76.1	40.7	-1.1	2	0.20
1250	73	73.9	40.0	-0.9	3	0.32
1600	70	71.6	38.8	-1.6	3	0.30
2000	69	70.5	38.5	-1.5	5	0.21
2500	68	69.0	39.7	-1.0	/	0.29
3150	66	67.4	43.3	-1.4	8	0.32
4000	67	66.7	52.2	0.3		0.51
5000	61	60.6	55.5	0.4	L	0.02
		I NI		aund Dras		
		$L_n = N$	ormalized S	ound Pres	sure Level, aB	
		L2 = R	leceiving Ro	om Level,	dB	
		a = D	lecay lime,	dB/second		
		$\Delta L_n = U$	ncertainty to	JI 95% CO	indence Level	

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL^{®**}

NVLAP

Laboratory

Acoustical Testing

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 1 of 5

TEST REPORT

For

Pliteq, Inc.

1370 Don Mills Road, Unit 300 Toronto, ON. Canada M3B 3N7 Matthew Golden/ 202-714-0600

Sound Transmission Loss Test

ASTM E 90 - 04 / E 413 - 10

On

2 Inch USG LEVELROCK[®] Poured Floor Underlayment Over GenieMat[™] FF17 Over GenieMat[™] FF25 On USG DUROCK[®] Cement Board Adhered To Wood Beam Factory Style Floor-Ceiling Assembly

Report Number: NGC 5014141

Assignment Number: G-877

Test Date: 8/27/2014

Report Approval Date: 9/12/2014

Submitted by: Andrew E. Heuer Senior Test Engineer

Director

le CH

Reviewed by:

Robert J. Menchetti

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

> NGC 5014141 Pliteq, Inc. 9/12/2014 Page 2 of 5

Revision Summary:

Date	SUMMARY
Approval Date: 9/12/2014	Original issue date. Original NGCTS report: NGC 5014141

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL[®]

Report Number: NGC 5014141

Acoustical Testing

Laboratory

NVLAP®

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 3 of 5

Test Method:	This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements – Designation: E 90 - 04 / E 413 - 10.
Specimen Description:	Wood Beam Factory Style Floor-Ceiling assembly overlaid with, according to client, USG LEVELROCK [®] 2500 poured floor underlayment on GenieMat TM FF17 on GenieMat TM FF25 over USG DUROCK [®] Cement board.
	The test specimen was a floor-ceiling assembly observed to consist of the following: All measured weights and dimensions are averaged:
	 1 layer of, according to client, USG LEVELROCK[®] 2500 poured floor underlayment. The USG LEVELROCK[®] 2500 poured floor underlayment was poured directly onto the The GenieMat[™] FF17. Measured thickness: 50.8 mm (2in.) Measured weight: 100.67 kg/m² (20.62PSF) 1 layer of, according to client, GenieMat[™] FF17. The GenieMat[™] FF17 was floating over The GenieMat[™] FF25. Measured thickness: 15.88 mm (0.625 in.) Measured weight: 7.42 kg/m² (1.52 PSF) 1 layer of, according to client, GenieMat[™] FF25. The GenieMat[™] FF25 was floating over the USG DUROCK[®] cement board. Measured thickness: 24.30 mm (0.957 in.) Measured weight: 10.06 kg/m² (2.06 PSF) 1 layer of, according to client, USG DUROCK[®] Cement board. The USG DUROCK[®] cement board was screwed and adhered to the factory floor with, a latex mortar, using a 6.35 mm x 6.35 mm x 6.35 mm (1/4 in. x 1/4 in. x 1/4 in.) Square notch trowel, and secured with 31.75 mm (1-1/4 in.) Type W screws spaced 203.20 mm (8 in.) o.c. Measured thickness: 12.45 mm (0.49 in.) Measured weight: 13.74 kg/m² (3.04 PSF) 1 layer of, according to client, 3" T&G wood planks. The top layer of subflooring was nailed to the bottom layer of subflooring at random lenths. Subfloor measured dimensions: 3657.60 mm x 149.23 mm x 19.05 mm (144 in. x 5-7/8 in. x 0.75 in.). Subfloor measured weight: 7.37 kg/m² (1.51 PSF) 1 layer of, according to client, 3" T&G wood planks. The bottom layer of subflooring was nailed to the underlying support beams at random lengths. Subfloor measured dimensions: 4876.8 mm x133.4 mm x 57.15 mm (192 in. x 5-1/4 in. x 20.4 in.) Subfloor measured weigh: 26.32 kg/m² (5.39 PSF) Two (2), 3505.2 mm x 304.8 mm x 304.8 mm (138 in. x 12 in. x 12 in.) Support beams placed 2438.4 mm (96 in.) o.c. allowing 1219.2 mm (48 in.) of space from each end of the test frame. Measured weight of the beams: 206.95 kg/m² (5.07 PSF)
	The overall weight of the test assembly: 191.42 kg/m^2 (39.21 PSF)
	The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough/ Curb to compensate for test frame height. The test assembly was structurally isolated from the receiving room.
Specimen size: Conditioning:	3657.6 mm x 4876.8 mm (12 ft. x 16 ft.) All materials were tested as received.Poured underlayment cured a minimum of 14 days. Mortar cured minimum 7 days. Adhesives cured a minimum 24 hours.

Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL

NVLAP

Laboratory

Acoustical Testing

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Sound Transmission Loss Test Data							
Test: ASTM E 9	0 - 04 / ASTM E	413 - 10					
Test Report:	NGC 5014141			Date	· 8/27/2014		Page 4 of 5
Specimen Size	m²]:	17.8		Date	. 0/21/2014		
Source room		11.0			Receiving roo	m	
Volume [m ³]:	53.2				Volume [m ³].	69.3	
Rm Temp [°C]:	24				Bm Temp [°C].	22	
Humidity [%]:	57				Humidity [%]	51	
Sound Transmi	ssion Class ST	C [dB]:	53		i iaimaity [/o]:		
Sum of Unfavorable	Deviations [dB]:	26					
Max. Unfavorable De	eviation [dB]:	8	at	315	Hz		
Frequency	STL	L1	L2	d	Corr.	u.Dev.	ASTL
[Hz]	[dB]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
100	31	103.9	79.5	20.7	6.6		2.64
125	38	104.9	73.1	21.7	6.2		1.64
160	40	104.5	71.9	18.2	7.4		2.63
200	41	104.5	70.3	20.2	6.8	2	1.46
250	42	104.6	69.2	23.6	6.6	4	1.13
315	41	102.0	66.8	22.8	5.8	8	0.54
400	45	102.4	63.3	25.4	5.9	7	0.64
500	49	102.6	59.5	27.1	5.9	4	0.73
630	53	102.6	54.3	30.5	4.7	1	0.38
800	56	102.9	51.2	32.3	4.3		0.40
1000	58	99.3	46.0	33.6	4.7		0.55
1250	58	96.9	43.1	35.4	4.2		0.55
1600	63	97.0	38.3	34.9	4.3		0.39
2000	67	99.2	36.6	35.9	4.4		0.23
2500	70	99.7	34.0	37.9	4.3		0.73
3150	73	98.6	28.7	42.0	3.1		1.03
4000	76	95.7	22.1	50.1	2.5		1.25
5000	78	88.8	13.2	54.8	2.5		1.51
	2	STL = Sou L1 = Sour L2 = Rece d = Deca A STL = Unc	nd Transmissi rce Room Leve eiving Room L ay Time, dB/se ertainty for 95	on Loss, dB el, dB evel, dB econd % Confidenc	e Level		

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL

Laboratory

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Page 1 of 5

TEST REPORT

for

Pliteq, Inc.

1370 Don Mills Road, Unit 300 Toronto, ON. Canada M3B 3N7 Matthew Golden/ 202-714-0600

Impact Sound Transmission Test

ASTM E 492 - 09 / ASTM E 989 - 06

On

2 Inch USG LEVELROCK[®] Poured Floor Underlayment Over GenieMat[™] FF17 Over GenieMat[™] FF25 On USG DUROCK[®] Cement Board Adhered To Wood Beam Factory Style Floor-Ceiling Assembly Overlaid with; Shaw Click LVT on GenieMat[™] RST-05 Underlayment.

Report Number: NGC 7014194

Assignment Number: G-877 Test Date: 8/27/2014 Report Approval Date: 9/12/2014 Submitted by: Andrew E. Heuer Senior Test Engineer Reviewed by: Robert J. Menchetty Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

> NGC 7014194 Pliteq, Inc. 9/12/2014 Page 2 of 5

Revision Summary:

Date	SUMMARY
Approval Date: 9/12/2014	Original issue date. Original NGCTS report: NGC 7014194

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Report Number: NGC 7014194

Page 3 of 5

This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Test Method: Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine - Designation: E 492-09/ E 989-06. The uncertainty limits of each tapping machine location met the precision requirements of section A1.4 of

ASTM E 492-09.

Specimen Description:

Wood Beam Factory Style Floor-Ceiling assembly overlaid with, according to client, Shaw Click LVT Flooring on GenieMat[™] RST-05 underlayment over USG LEVELROCK[®] 2500 poured floor underlayment on GenieMat[™] FF17 on GenieMat[™] FF25 over USG DUROCK[®] Cement board.

Laboratory

The test specimen was a floor-ceiling assembly observed to consist of the following: All measured weights and dimensions are averaged:

- 1 layer of, according to client, Shaw Click LVT. The Shaw Click LVT was floating on the GenieMat[™] RST-05 underlayment. Measured dimensions: 184.15 mm x 1212.85 mm (7-1/4 in. x 47-3/4 in.) Measured thickness: 5.08 mm (0.20 in.) Measured weight: 8.20 kg/m² (1.68 PSF) - 1 layer of, according to client, GenieMat[™] RST-05 underlayment. The GenieMat[™] RST-05 was floating on the USG
- LEVELROCK® 2500 poured floor underlayment. Measured thickness: 4.95 mm (0.195 in.) Measured weight: 4.20 mm (0.86 PSF)
- 1 layer of, according to client, USG LEVELROCK[®] 2500 poured floor underlayment. The USG LEVELROCK[®] 2500 poured floor underlayment was poured directly onto the The GenieMat[™] FF17. Measured thickness: 50.8 mm (2in.) Measured weight: 100.67 kg/m² (20.62PSF)
- 1 layer of, according to client, GenieMat[™] FF17. The GenieMat[™] FF17 was floating over The GenieMat[™] FF25. Measured thickness: 15.88 mm (0.625 in.) Measured weight: 7.42 kg/m² (1.52 PSF)
- 1 layer of, according to client, GenieMat[™] FF25. The GenieMat[™] FF25 was floating over the USG DUROCK[®] cement board. Measured thickness: 24.30 mm (0.957 in.) Measured weight: 10.06 kg/m² (2.06 PSF)
- 1 layer of, according to client, USG DUROCK® Cement board. The USG DUROCK® cement board was screwed and adhered to the factory floor with, a latex mortar, using a 6.35 mm x 6.35 mm x 6.35 mm (1/4 in. x 1/4 in.) Square notch trowel, and secured with 31.75 mm (1-1/4 in.) Type W screws spaced 203.20 mm (8 in.) o.c. Measured thickness: 12.45 mm (0.49 in.) Measured weight: 14.84 kg/m² (3.04 PSF)
- 1 layer of, according to the client, 1" T&G wood planks. The top layer of subflooring was nailed to the bottom layer of subflooring at random lenths. Subfloor measured dimensions: 3657.60 mm x 149.23 mm x 19.05 mm (144 in. x 5-7/8 in. x 0.75 in.). Subfloors measured weight: 7.37 kg/m^2 (1.51 PSF)
- 1 layer of, according to client, 3" T&G wood planks. The bottom layer of subflooring was nailed to the underlying support beams at random lengths. Subfloor measured dimensions: 4876.8 mm x133.4 mm x 57.15 mm (192 in. x 5-1/4 in. x 2-1/4 in) Subfloor measured weigh: 26.32 kg/m² (5.39 PSF)
- Two (2), 3505.2 mm x 304.8 mm x 304.8 mm (138 in. x 12 in. x 12 in.) Support beams placed 2438.4 mm (96 in.) o.c, allowing 1219.2 mm (48 in.) of space from each end of the test frame. Measured weight: 24.75 kg/m² (5.07 PSF)

The overall weight of the test assembly: 203.82 kg/m^2 (41.75 PSF) The perimeter of the test frame was sealed with a rubber gasket and a sand filled trough. The test assembly was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.) Conditioning: All materials were tested as received. Poured underlayment cured a minimum 14 days. Mortar cured a minimum 7 days and adhesives cured a minimum 24 hours. Test Results: The results of the tests are given on pages 4 and 5 of the report.

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL

Acoustical Testing

Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Test. ASTIVIE 4	192 - U97 ASTIN	1 E 989 - 06				Dama 4 at 5
Test Report: NGC 7014194 Date					8/25/2014	Page 4 of 5
Specimen Size	[m²]:	17.8		Dute.	0/20/2014	
Source room					Receiving room	m
					Volume [m ³]:	69.3
Rm Temp [°C]:	23				Rm Temp [°C]:	22
Humidity [%]:	55				Humidity [%]:	51
mpact Insulati	on Class IIC	[dB]:	52			
Sum of Unfavorable	e Deviations [dB]:	29				
Max. Unfavorable D	eviation [dB]:	7	at	100	Hz	
Frequency	L _n	L2	d	Corr.	u.Dev.	ΔL _n
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
100	67	71.8	20.0	-4.8	7	2.95
125	63	67.4	21.7	-4.4	3	1.87
160	64	68.2	18.3	-4.2	4	2.45
200	65	69.0	20.5	-4.0	5	1.95
250	64	67.4	23.0	-3.4	4	0.96
315	63	67.0	22.4	-4.0	3	0.88
400	62	64.9	25.3	-2.9	3	0.82
500	52	54.9	26.5	-2.9		0.64
630	42	44.1	30.1	-2.1		0.60
800	33	35.8	31.6	-2.8		0.65
1000	25	29.2	33.1	-4.2		0.66
1250	21	25.0	35.2	-4.0		0.69
1600	19	22.9	34.3	-3.9		1.01
2000	16	19.8	36.4	-3.8		1.15
2500	13	16.9	38.0	-3.9		1.18
3150	11	14.2	42.2	-3.2		0.71
4000	9	11.6	49.5	-2.6		0.67
5000	8	9.6	54.7	-1.6		0.52
$L_n = Normalized Sound Pressure Level, dB$ $L2 = Receiving Room Level, dB$ $d = Decay Time, dB/second$ $\Delta L_n = Uncertainty for 95\% Confidence Level$						

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL®

Laboratory



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen. The laboratory's accreditation or any of its test reports in no way constitute or imply product certification, approval, or endorsement by NVLAP or any agent of the U.S. Government. This report may not be reproduced except in full, without written approval of the laboratory.



ACOUSTICAL • FIRE • STRUCTURAL • ANALYTICAL

Test Number : NGC 7014194

Test Date: 8/27/2014

Extended Frequency Measurements

The following is the extended frequency range test data during the subject test.

Frequency	L _n	L2	d	Corr.	u.Dev.	ΔL _n
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
50*	53	58.5	14.4	- 5.5		2.5
63*	53	57.8	18.9	- 4.8		2.7
80	63	67.6	16.8	- 4.6		2.9

Laboratory

*Note: Test data measured in the 50 Hz and 63 Hz bandwidths are not qualified and have higher uncertainties.



241 South Lander St, Suite 200 Seattle, WA 98134 (206) 792-7796 *www.a3acoustics.com*

February 21, 2017

Jennifer Nye William Wilson Architects PC 1022 SW Salmon St. Portland, OR 97205

Predicted Acoustic Performance for the Sellwood Apartments Proposed Assemblies

Dear Ms. Nye,

This letter presents our results from our acoustic analysis of the proposed floor-ceiling assemblies and wall types to ensure they meet the City of Portland Building Code STC 50 and IIC 50 performance for the Sellwood Apartments. The airborne sound and footfall transmission performance have been calculated using existing laboratory test data, computer modeling software, and based on our previous experiences with floor-ceiling assemblies.

I. Predictive Methods

This performance prediction is based on laboratory test results from the California *Catalog* of STC and IIC Ratings for Wall and Floor/Ceiling Assemblies, the Gypsum Association *Fire Resistance Design Manual Sound Control*, and *National Research Council of Canada*; predictions of each piece of the total assembly with the Marshall Day Acoustics INSUL sound insulation prediction tool for floor/ceilings; field test results from similar assemblies. The laboratory test results used for this prediction were completed per ASTM E 90 Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements and E 492 Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor Ceiling Assemblies Using the Tapping Machine. Sound Transmission Class (STC) and Impact Insulation Class (IIC) ratings are not directly equivalent to decibel values, but the ratings are based on the exponential decibel scale.

II. Performance Standards

City of Portland Building Code

The City of Portland Development Services Center states that common wall and floor/ceiling assemblies between adjacent units and between dwelling units and adjacent public areas such as halls, corridors, stairs, or services areas have a minimum Sound Transmission Class (STC) of 50 and floor-ceiling assemblies also have a minimum Impact Insulation Class (IIC) of 50.

The designer has three options for documenting required STC and IIC ratings:

- 1. Detail listed and approved STC and IIC assemblies on the plans from approved list of published assemblies, noted <u>here</u>.
- Obtain approval from Administrative Appeal Board for an alternative assembly. To be approved, the Appeal must include a detail of the proposed assembly, and an analysis stamped by a qualified state of Oregon licensed professional that concludes that the proposed assembly will provide the required STC and IIC ratings.
- 3. Specify an assembly to be Field Tested. Be aware there is a risk that an assembly can fail the field test, and require modifications after the building is finished.

International Building Code (IBC)

Section 1207 – Sound Transmission

1207.1 Scope. This section shall apply to common interior walls, partitions and floor/ceiling assemblies between adjacent dwelling units or between dwelling units and adjacent public areas such as hall, corridors, stairs and service areas.

1207.2 Air-borne sound. Walls, partitions, and floor/ceiling assemblies separating dwelling units from each other or from public or service areas hall have a sound transmission class (STC) of not less than 50 (45 if field tested) for air-borne noise when tested in accordance with ASTM E 90.

1207.3 Structure-borne sound. Floor/ceiling assemblies between dwelling units or between a dwelling unit and a public or service area within the structure shall have an impact insulation class (IIC) rating of not less than 50 (45 if field tested) when tested in accordance with ASTM E 492.

These ASTM standards are the laboratory equivalent of the field tests conducted for finished assemblies.

III. Assembly Description & Predicted Performance

The following proposed roof-ceiling assembly was evaluated with respect to air-borne sound and footfall noise impact performance to the STC 50 and IIC 50 performance requirements. When assemblies were noted to perform below the requirements remediation measures are noted and the improved performance documented to show compliance.

Floor-Ceiling Assembly – 5A

Floor Finish - Vinyl 1-1/4" gypsum lightweight concrete (13 psf) 1/4" acoustic underlayment (0.2 psf) 3/4" plywood (1.6 psf) 9-1/2" TJI Joists 3-1/2" batt insulation (3A); fill cavity for 3B 1/2" resilient channel 2 layers of 5/8" GWB (4.4 psf)



Table 1: Floor/Ceiling Assembly 5A / 5C

Proposed Assembly Evaluated	Performance
Comparable Lab Test	
Laboratory Test Results: NGC 5012050 (STC) / NGC 7012109 (IIC)	
(attached to this report)	
1. Finished Floor – Vinyl	
2. 1" gypcrete	
Maxxon AcoustiMat II (1/4" thick sound control mat)	STC 58
4. 23/32" OSB	
 Acoustically equivalent to proposed plywood subfloor 	IIC 53
5. 9-1/2" wood I-Joists	
6. 3-1/2" batt insulation	
a. 5C includes additional 6-inches of insulation (+ STC 0 / IIC 2)	
7. 1/2" resilient channel	
8. 2 layers of 5/8" GWB	

Floor-Ceiling Assembly – 5B 9-1/2" LSL Wood Joists, instead of TJI

Table 2: Floor/Ceiling Assembly 5A / 5B

Proposed Assembly Evaluated	Performance
Comparable Lab Test Laboratory Test Results: Intertek 10033655CRT-001g (STC) /	
Intertek 100336557CRT-001m (IIC)	
(attached to this report)	
1. Finished Floor – Sheet Vinyl	STC 52
2. 1 gypsum lightweight concrete	
4 5/8" Plywood	IIC 53
5 - 9 - 1/2" sold wood joists	
6. 3-1/2" batt insulation	
7. 1/2" resilient channel	
8. 1 layer of 5/8" GWB	
Predicted Improvement	
Differences (calculated with INSUL 8.0 Sound Insulation Predictor)	SIC +4 to +8
1. Additional 1/4" of lightweight concrete (1-1/4" total)	
2. Additional layer of 5/8" GWB	
	STC
	56 - 60
Predicted Laboratory Measured Performance	
	IIC
	53 – 55

Roof Deck Assembly 7A

Cement pedestal paver (13 - 20 psf) AWS Pedestal System (ABS & PVC Plastic) Roofing Membrane (1.75 psf) R-20 Rigid Insulation (<0.5 psf) 5/8" Plywood Sheathing (1.8 psf) 5/8" Type X gypsum board battens 9-1/2" LVL wood joists 3-1/2" batt insulation 1/2" Resilient Channel 2 Layers of 5/8" Type X gypsum board (4.4 psf)



FIRE: 1-HR ASSEMBLY: GA FILE NO. FC 5532 STC: 55, IIC 50 ASSEMBLY: AS PER ENGINEER'S REPORT

Laboratory data for similar roof deck assemblies was published in January 2017.
Table 3: Roof Deck Assembly 7A

Proposed Assembly Evaluated	Performance
Prediction for overall assembly Laboratory Test Results: Architectural Testing, Inc. G6527.13-113-11 (01/17/17)	
 2" Stone Pavers 2" adjustable deck supports 2" Owens Corning FOAMULAR 250 R-10 Insulation Sheathing 	STC 59
 1/2" Plywood Sheathing 3/4" Oriented Strand Board Sheathing 9-1/2" Owens Corning R-30 Fiberglass Insulation 12" T.II. Joist 	IIC 63
 1/2" Resilient Channel (ClarkDietrich RC Deluxe) 2 Layers of 5/8" GWB 	
Predicted Improvement Differences (calculated with INSUL 8.0 Sound Insulation Predictor) 1. 3-1/2" batt insulation instead of 9-1/2" 2. 3/4" OSB is equivalent to 5/8" GWB battens 3. 9-1/2" LSL instead of 12" TJI	STC -4 IIC -5
Predicted Measured Performance (includes corrections for installed conditions based on field tests completed for similar conditions and buildings)	STC 55 IIC 58



Interior Party Wall Assembly – 43A

<u>43A</u>

1 layer of 5/8" GWB on one side (2.2 psf) 2x4 Double Studs (16" on-center with 1-inch gap between studs) 2 layers of 3-1/2 batt insulation

2 layers of 5/8" GWB on one side (4.4 psf)

<u>43B</u>

2 layers of 5/8" GWB on each side (4.4 psf) 2x4 Double Studs (16" on-center with 1-inch gap between studs) 2 layers of 3-1/2 batt insulation

Table 4: Interior Party Wall Assemblies 43A & 43B

Proposed Assemblies Evaluated	Performance
Prediction for assembly 43A:	
Laboratory Test Results: NRCC TL-93-267	
(attached to this report)	
1. 1 layer of 5/8" GWB on one side	STC 62
2. 2 layers of 3-1/2" insulation	510.02
3. Double Stud (2x4, 16" on-center) with 1" gap	
Sealed at the bottom and top track	
5. 2 layers of 5/8" GWB on one side	
Prediction for assembly 43B:	
Laboratory Test Results: NRCC TL-93-269	
(attached to this report)	
1. 2 layers of 5/8" GWB on each side	SIC 67
2. 2 layers of 3-1/2" insulation	
3. Double Stud (2x4, 16" on-center) with 1" gap	
4. Sealed at the bottom and top track	

IV. Conclusion

The proposed flooring-ceiling assemblies will satisfy the International Building Code (IBC) sound transmission requirements of STC 50 and IIC 50 with one of the recommended alternatives.

Please contact us if you have any questions or for additional information.

Sincerely,

Erik Miller-Klein, P.E. Partner & Acoustical Consultant

A3 Acoustics, LLP 241 South Lander St., Suite 200 Seattle, WA 98134 206.792.7796 – Office 206.658.7920 – Cell erik@a3acoustics.com



RENEWAL DATE: 12/31/2018



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

TEST REPORT

for

Weyerhaeuser 2910 East Amity Road Boise, ID 83716

Sound Transmission Loss Test ASTM E 90 – 04 / E 413 - 10

On

Cushioned Vinyl on 1 Inch Gypcrete over Acousti-Mat[®] II – Side 1 Single Layer of 5/8 Inch Wallboard over RC1 Channel (24 Inch o.c.) – Side 2 on 9-1/2 Inch I Joists and 23/32 Inch OSB with 3-1/2 Inch Fiberglass Insulation

Report Number: NGC 5012050

Assignment Number: G-780

Test Date: 8/1/2012

Report Date: 9/12/2012

role (#

Submitted by:

Andrew E. Heuer Senior Test Engineer

Reviewed by:

Robert J. Ma hchetti

Robert J. Director

The results reported above apply to specific samples submitted for measurement. No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written enpreud of the

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of it's test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.

1650 Military Road

Buffalo, NY 14217-1198 (716) 873-9750

Fax (716) 873-9753

www.ngctestingservices.com Page 1 of 4 Reissued 10/22/12



Report Number: NGC 5012050

Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

> Page 2 of 4 Reissued 10/22/12

Test Method: This test method conforms explicitly with the American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements - Designation: E 90 - 04 / E 413 - 10.

Specimen Description: Wood floor-ceiling assembly, including a gypsum board ceiling, overlaid with, according to client, Cushioned Vinyl on Gypcrete Underlayment over Acousti-Mat[®] II with 3-1/2 inch Fiberglass Insulation.

The test specimen was a floor-ceiling assembly consisting of the following:

- 1 layer of, according to client, 1.7 mm (.065 in.) thick Cushioned Vinyl Flooring. Sample weight was 1.46 kg/m² (0.30 PSF).
- 25.4 mm (1 in.) direct pour gypcrete underlayment, weighing 49.32 kg/m² (10.1 PSF).
- 1 layer of, according to client, 6.2 mm (.245 in.) thick Acousti-Mat[®] II sound control system. Sample weight was 1.46 kg/m² (0.30 PSF).
- 1 layer of 18.3 mm (23/32 in.) OSB. The subfloor was screwed perpendicular to wood joists. Screws were spaced 152.4 mm (6 in.) o.c. at the perimeter and 304.8 mm (12 in.) o.c. in the field. The OSB weight was 10.69 kg/m² (2.19 PSF).
- 9-1/2 in. I Joists spaced 609.6 mm (24 in.) o.c. The joists were attached to rim boards, doubled on each side. The I Joist weight was 6.0 kg/m² (1.23 PSF). The rim board weight was 5.71 kg/m² (1.17 PSF).
- 1 layer of 88.9 mm (3-1/2 in.) un-faced fiberglass insulation, friction fit into joist cavities. The sample weight was 0.78 kg/m² (0.16 PSF).
- RC1 Channel spaced 609.6 mm (24 in.) o.c. The channels attached perpendicular to the joists with 31.8 mm (1-1/4 in.) type W drywall screws. The weight was 0.54 kg/m² (0.11 PSF).
- 1 layer of 15.9 mm (5/8 in.) gypsum board. The board was attached using 31.8 mm (1.25 in.) Type S drywall screws 304.8 mm (12 in.) on center. The board joints were taped. Gypsum board weight was 11.23 kg/m² (2.3 PSF).

The overall weight of the test assembly was 87.21 kg/m² (17.86 PSF).

The perimeter of the assembly was sealed with a rubber gasket and a sand filled trough. The test assembly was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Test Results: The results of the tests are given on pages 3 and 4.

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.



Testing Services

Accredited by the National Voluntary

Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Sound Transmission Loss Test Data							
Test: ASTM E 90	- 04 / ASTM	E 413 - 04					
				2017 12			Page 3 of 4
Test Report: N	NGC5012050			Date:	8/1/2012		
Specimen Size [n	n²]:	17.8					
Source room					Receiving roo	m	
Volume [m ³]: 5	53.2				Volume [m ³]:	61.2	
Rm Temp [°C]: 2	23.5				Rm Temp [°C]:	23.5	
Humidity [%]: 5	53				Humidity [%]:	53	
Sound Transmis	sion Class	STC [dB]:	58				
Sum of Unfavorable [Deviations [dB]:	27					
Max. Unfavorable De	viation [dB]:	5	at	315	Hz		
Frequency	STL	L1	L2	d	Corr.	u.Dev.	∆STL
[Hz]	[dB]	[dB]	[dB]	[dB/s]	[dB]	[dB]	
100	38	105.7	74.6	22.0	6.9		2.82
125	44	104.7	67.9	21.6	7.3		3.35
160	47	106.6	67.1	18.5	7.5		2.11
200	44	106.2	69.8	17.5	7.6	4	1.11
250	47	106.1	66.9	19.3	7.8	4	1.17
315	49	102.7	61.0	21.8	7.4	5	0.35
400	52	102.9	57.9	22.0	7.0	5	1.27
500	56	103.3	53.9	26.0	6.6	2	0.46
630	59	102.1	49.7	27.0	6.5		0.32
800	59	101.8	48.3	27.8	5.5	1	0.48
1000	57	98.2	46.8	29.7	5.7	4	0.51
1250	60	97.2	43.1	31.1	5.8	2	0.75
1600	64	96.3	37.3	33.0	5.1		0.77
2000	67	99.0	36.5	35.5	4.5		0.60
2500	68	100.6	37.3	39.8	4.6		0.73
3150	72	99.6	31.4	42.6	3.8		1.07
4000	76	97.1	25.1	47.0	4.0		1.22
5000	79	90.5	15.0	52.6	3.5		1.55
	۵	STL = Sou L1 = Sou L2 = Rec d = Dec STL = Unc	ind Transmiss rce Room Lev eiving Room I ay Time, dB/s certainty for 95	sion Loss, dB rel, dB Level, dB second 5% Confidence	e Level		

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.





Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.





Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

for

TEST REPORT

Weyerhaeuser 2910 East Amity Road Boise, ID 83716

Impact Sound Transmission Test ASTM E 492 – 09 / ASTM E 989 – 06

On

Cushioned Vinyl on 1 Inch Gypcrete over Acousti-Mat[®] II – Side 1 Single Layer of 5/8 Inch Wallboard over RC1 Channel (24 Inch o.c.) – Side 2 on 9-1/2 Inch I Joists and 23/32 Inch OSB with 3-1/2 Inch Fiberglass Insulation

Report Number: NGC 7012109

Assignment Number: G-780

Test Date: 8/1/2012

Report Date: 9/12/2012

Submitted by:

Andrew E. Heuer Senior Test Engineer

Reviewed by:

Robert J. Merchetti Director

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.

The laboratory's accreditation or any of it's test reports in no way constitutes or implies product certification, approval, or endorsement by NVLAP or any agency of the U.S. Government.

Page 1 of 4 Reissued 10/22/12



Report Number: NGC 7012109



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

> Page 2 of 4 Reissued 10/22/12

Test Method: This test method is in accordance with American Society for Testing and Materials Standard Test Method for Laboratory Measurement of Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine - Designation: E 492-09/ E 989-06. The uncertainty limits of each tapping machine location met the precision requirements of section A1.4 of ASTM E 492-09. Specimen Description: Wood floor-ceiling assembly, including a gypsum board ceiling, overlaid with, according to client, Cushioned Vinyl on Gypcrete Underlayment over Acousti-Mat® II with 3-1/2 inch Fiberglass Insulation. The test specimen was a floor-ceiling assembly consisting of the following: - 1 layer of, according to client, 1.7 mm (.065 in.) thick Cushioned Vinyl Flooring. Sample weight was 1.46 kg/m² (0.30 PSF). - 25.4 mm (1 in.) direct pour gypcrete underlayment, weighing 49.32 kg/m² (10.1 PSF). - 1 layer of, according to client, 6.2 mm (.245 in.) thick Acousti-Mat[®] II sound control system. Sample weight was 1.46 kg/m² (0.30 PSF). - 1 layer of 18.3 mm (23/32 in.) OSB. The subfloor was screwed perpendicular to wood joists. Screws were spaced 152.4 mm (6 in.) o.c. at the perimeter and 304.8 mm (12 in.) o.c. in the

- field. The OSB weight was 10.69 kg/m² (2.19 PSF). - 9-1/2 in. I Joists spaced 609.6 mm (24 in.) o.c. The joists were attached to rim boards, doubled on each side. The I Joists weight was 6.0 kg/m² (1.23 PSF). The rim board weight was 5.71 kg/m² (1.17 PSF).
- 1 layer of 88.9 mm (3-1/2 in.) un-faced fiberglass insulation, friction fit into joist cavities. The sample weight was 0.78 kg/m² (0.16 PSF).
- RC1 Channel spaced 609.6 mm (24 in.) o.c. The channels attached perpendicular to the joists with 31.8 mm (1-1/4 in.) type W drywall screws. The weight was 0.54 kg/m² (0.11 PSF).
- 1 layer of 15.9 mm (5/8 in.) gypsum board. The board was attached using 31.8 mm (1.25 in.) Type S drywall screws 304.8 mm (12 in.) on center. The board joints were taped. Gypsum board weight was 11.23 kg/m² (2.3 PSF).

The overall weight of the test assembly was 86.21 kg/m² (17.86 PSF).

The perimeter of the assembly was sealed with a rubber gasket and a sand filled trough. The test assembly was structurally isolated from the receiving room.

Specimen size: 3657.6 mm x 4876.8 mm (12 ft. x 16 ft.)

Test Results: The results of the tests are given on pages 3 and 4.

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.





Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291

Normalized impact sound pressure level								
Test: ASTM E 492 - 09 / ASTM E 989 - 06								
						Page 3 of 4		
Test Report: NGC7012109 Date: 8/1/2012								
Specimen Size	[m²]:	17.8						
Source room					Receiving room	n		
					Volume [m ³]:	61.2		
Rm Temp [°C]:	27.5				Rm Temp [°C]:	23.5		
Humidity [%]:	53				Humidity [%]:	53		
Impact Insulati	ion Class IIC [dB]:	53					
Sum of Unfavorable	e Deviations [dB]:	27						
Max. Unfavorable D	eviation [dB]:	7	at	100	Hz			
Frequency	Ln	L2	d	Corr.	u.Dev.	ΔL _n		
[Hz]	[dB]	[dB]	[dB/s]	[dB]	[dB]			
100	66	70.4	24.5	-4.4	7	2.22		
125	61	65.4	22.6	-4.4	2	1.53		
160	66	71.0	17.6	-5.0	7	1.69		
200	65	70.4	17.0	-5.4	6	0.93		
250	64	69.0	19.7	-5.0	5	0.62		
315	59	64.0	21.4	-5.0		0.42		
400	55	59.2	22.3	-4.2		0.34		
500	50	53.6	25.5	-3.6		0.24		
630	42	45.8	27.4	-3.8		0.33		
800	35	38.5	27.8	-3.5		0.17		
1000	34	36.8	29.5	-2.8		0.36		
1250	28	30.9	31.4	-2.9		0.39		
1600	17	20.6	32.9	-3.6		0.42		
2000	16	19.3	35.7	-3.3		0.61		
2500	16	18.8	39.7	-2.8		0.33		
3150	12	15.3	42.3	-3.3		0.45		
4000	10	12.6	47.5	-2.6		0.54		
5000	8	10.9	52.6	-2.9		0.58		
		$L_n = Nc$	ormalized S	ound Press	sure Level, dB			
		L2 = R	eceiving Ro	om Level,	dB			
		d = D	ecay Time,	dB/second				
		$\Delta L_n = Ur$	ncertainty fo	or 95% Cor	nfidence Level			

The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.



Accredited by the National Voluntary Laboratory Accreditation Program for the specific scope of accreditation under Lab Code 200291



The results reported above apply to specific samples submitted for measurement.

No responsibility is assumed for performance of any other specimen.

This report may not be reproduced except in full, without the written approval of the laboratory.



REPORT

3933 US ROUTE 11 CORTLAND, NEW YORK 13045

Order No. 100336557

Date: June 24, 2011

REPORT NO. 100336557CRT-001g

SOUND TRANSMISSION LOSS TEST AND CLASSIFICATION OF MAXXON GYPSUM UNDERLAYMENT OVER A SOUND CONTROL MAT ON A WOOD JOIST FLOOR/CEILING ASSEMBLY

MAXXON CORPORATION 920 HAMEL ROAD, P. O. BOX 253 HAMEL, MN 55340-9610

INTRODUCTION

This report gives the results of a Sound Transmission Loss Test and Classification of Maxxon Gypsum Underlayment over a Sound Control Mat on a wood joist floor/ceiling assembly. The floor/ceiling assembly was supplied and installed by Intertek. The gypsum topping and the acoustical mat underlayment were supplied and installed by a representative of Maxxon Corporation. The sample appeared to be in a new, unused condition.

AUTHORIZATION

Signed Quote No. 500285443.

TEST METHOD

The specimen was tested in general accordance with the American Society for Testing and Materials designation ASTM E90-09, "Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements", and classified in accordance with the American Society for Testing and Materials designation ASTM E413-04, "Classification for Rating Sound Insulation". The size of the source room for the measurements is smaller than the minimum recommended of 125m³. This leads to slightly elevated uncertainties in the measurement data at low frequencies and does not allow microphones to be placed in full accordance with section A.2.

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to copy or distribute this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report and then only that the material, product, or service is or has ever been under an Intertek certification program. Measurement uncertainty budgets have been determined for applicable test methods and are available upon request.



<u>GENERAL</u>

The sound-insulating property of a partition element is expressed in terms of the sound transmission loss. The procedure for determining this quantity is to mount (and perimeter seal) the test specimen as a partition between two reverberation rooms. Sound is introduced in one of the rooms (the source room) and measurements are made of the noise reduction between source room and receiving room. The rooms are so arranged and constructed that the only significant sound transmission between them is through the test specimen.

The purpose of the Sound Transmission Class (STC) is to provide a single figure rating that can be used for comparing the sound-insulating properties of partition elements used for general building design purposes. The higher the rating (STC) the greater the sound insulating properties of the partition.

DESCRIPTION OF THE FLOOR/CEILING ASSEMBLY

The test floor is a 100 sq. ft. opening that forms the horizontal separation of the two rooms, one directly above the other. The materials used in the assembly from top to bottom are:

- Nominal 1 inch thick Maxxon Gypsum Underlayment (poured March 10, 2011)
- Acousti-Mat II Sound Control Mat
- 5/8 inch thick T & G OSB nailed 6 inches on perimeter and 12 inches in field and glued to the joists using OSI PL400 adhesive
- 10 inch high nominal 2 X 10 lumber joists spaced 16 inches on center.
- R-11 unfaced batt insulation installed in the top of the cavities
- Dietrich RC Deluxe (dog bone) resilient channels spaced 24 inches on center
- One layer of 5/8 inch thick Type "X" gypsum board fastened to the channels with 1 inch screws 12 inches on center. Joint compound was applied at screw holes and joints.



RESULTS OF MEASUREMENTS

1/3 Octave Band	
Center Frequency	
Hz	Sound Transmission Loss in dB
	<u>Test #1</u>
80	24
100	30
125	33
160	38
200	38
250	42
315	44
400	48
500	50
630	54
800	55
1000	59
1250	61
1600	62
2000	63
2500	67
3150	71
4000	75
5000	77
Sound Transmission Class	53

PRECISION

For the Intertek flooring test facility, the 95% confidence interval Δ TL, is as follows:

Range of	Transmission Loss
One-Third Octave	95% Confidence
Bands	<u>Uncertainty, dB</u>
125 and 200	<4
250 and 315	<2
400 - 4000	<1.5



<u>Test #1</u>



Sound Transmission Loss

MAXXON CORPORATION



REMARKS

- 1. Ambient Temperature: 70°F
- 2. Relative Humidity: 23%

CONCLUSION

The test method employed for this test has no pass-fail criteria, therefore, the evaluation of the test results is left to the discretion of the client.

Date of Test: March 22, 2011

Report Approved by:

Driven Cy

Brian Cyr Engineer Acoustical Testing

Report Reviewed By:

James R. Kline

James R. Kline Engineer/Quality Supervisor Acoustical Testing

Attachments: None



FOR THE SCOPE OF ACCREDITATION UNDER NVLAP LAB CODE 100402-0.

REPORT

3933 US ROUTE 11 CORTLAND, NEW YORK 13045

Order No. 100336557

June 24, 2011

REPORT NO. 100336557CRT-001m

IMPACT SOUND TRANSMISSION TEST AND CLASSIFICATION OF SHEET VINYL OVER MAXXON GYPSUM UNDERLAYMENT OVER A SOUND CONTROL MAT ON A WOOD JOIST FLOOR/CEILING ASSEMBLY

RENDERED TO

MAXXON CORPORATION 920 HAMEL ROAD, P. O. BOX 253 HAMEL, MN 55340-9610

INTRODUCTION

This report gives the results of an Impact Sound Transmission Loss Test and Classification Sheet Vinyl over Maxxon Gypsum Underlayment over a Sound Control Mat on a wood joist floor/ceiling assembly. The floor/ceiling assembly was supplied and installed by Intertek. The gypsum topping and the acoustical mat underlayment were supplied and installed by a representative of Maxxon Corporation. The sample appeared to be in a new, unused condition.

AUTHORIZATION

Signed Quote No. 500285443.

TEST METHOD

The specimen was tested in accordance with the American Society for Testing and Materials designation ASTM E492-09, "Standard Test Method for Laboratory Measurement of Impact Sound Transmission through Floor-Ceiling Assemblies Using the Tapping Machine". It was classified in accordance with ASTM E989-2006, entitled, "Standard Classification for Determination of Impact Insulation Class (IIC)".

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to copy or distribute this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program. Measurement uncertainty budgets have been determined for applicable test methods and are available upon request.





GENERAL

The method is designed to measure the impact sound transmission performance of a floorceiling assembly, in a controlled laboratory environment. A standard tapping machine (Bruel & Kjaer Type 3207) was placed at four positions on a test floor that forms the horizontal separation between two rooms, one directly above the other. The data obtained was normalized to a reference room absorption of 10 square meters in accordance with the test method.

The standard also prescribes a single-figure classification rating called "Impact Insulation Class, IIC" which can be used by architects, builders and code authorities for acoustical design purposes in building construction.

The IIC is obtained by matching a standard reference contour to the plotted normalized one-third octave band sound pressure levels at each test frequency. The greater the IIC rating, the lower the impact sound transmission through the floor-ceiling assembly

DESCRIPTION OF THE FLOOR/CEILING ASSEMBLY

The test floor is a 100 sq. ft. opening that forms the horizontal separation of the two rooms, one directly above the other. The materials used in the assembly from top to bottom are:

- Nominal 1 inch thick Maxxon Gypsum Underlayment (poured March 10, 2011)
- Acousti-Mat II Sound Control Mat
- 5/8 inch thick T & G OSB nailed 6 inches on perimeter and 12 inches in field and glued to the joists using OSI PL400 adhesive
- 10 inch high nominal 2 X 10 lumber joists spaced 16 inches on center.
- R-11 unfaced batt insulation installed in the top of the cavities
- Dietrich RC Deluxe (dog bone) resilient channels spaced 24 inches on center
- One layer of 5/8 inch thick Type "X" gypsum board fastened to the channels with 1 inch screws 12 inches on center. Joint compound was applied at screw holes and joints.

<u>Test #1</u> – Armstrong Memories Sheet Vinyl – full glued





RESULTS OF TEST

The data obtained in the room below the panel normalized to $A_o = 10$ square meters, is as follows:

1/3 Octave Band Center Frequency <u>Hz</u>	1/3 Octave Band Sound Pressure Level dB re 0.0002 Microbar
$ \begin{array}{r} 100 \\ 125 \\ 160 \\ 200 \\ 250 \\ 315 \\ 400 \\ 500 \\ 630 \\ 800 \\ 1000 \\ 1250 \\ 1600 \\ 2000 \\ 2500 \\ 3150 \\ \end{array} $	<u>Test #1</u> 65 64 64 65 64 62 61 60 58 57 54 51 48 48 43 36
Impact Insulation Class (IIC)	52

The 95% uncertainty level for each tapping machine location is less than 3 dB for the 1/3 octave bands centered in the range from 100 to 400 Hz and less than 2.5 dB for the bands centered in the range from 500 to 3150 Hz.

For the floor/ceiling construction, the 95% uncertainty limits (ΔL_n) for the normalized sound pressure levels were determined to be less than 2 dB for the 1/3 octave bands centered in the range from 100 to 3500.





<u>TEST #1</u>

Impact Insulation Class







REMARKS

- 1. Ambient Temperature: 71 F
- 2. Relative Humidity: 53 %

CONCLUSION

The test method employed for this test has no pass-fail criteria, therefore, the evaluation of the test results is left to the discretion of the client.

This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the federal government.

Date of Test: April 26, 2011

Report Approved by:

Driven Cy

Brian Cyr Engineer Acoustical Testing

Report Reviewed By:

James R. Kline

James R. Kline Engineer/Quality Supervisor Acoustical Testing

Attachments: None



Page 342

Element Description:

TestID

STC

50 Hz

63 Hz

80 Hz

100 Hz

125 Hz

160 Hz

200 Hz

250 Hz

315 Hz

400 Hz

500 Hz

630 Hz

800 Hz

1000 Hz

1250 Hz

1600 Hz

2000 Hz

2500 Hz

3150 Hz

4000 Hz

5000 Hz

6300 Hz

- 1 single layer of 16 mm type X gypsum board
- 2 90 mm wood studs at 406 mm on centre
- 3 90 mm of glass fibre insulation in cavity
- 4 25 mm gap filled with air

81.1

74.1

74.2

79.6

85.4

90.0

87.2

- 5 90 mm wood studs at 406 mm on centre
- 6 90 mm of glass fibre insulation in cavity
- 7 single layer of 16 mm type X gypsum board
- 8 single layer of 16 mm type X gypsum board

G16_WS90(406)_GFB90_AIR25_WS90(406)_GFB90_2G16

	XxxxxxxxxxXxxxxxxxxxxxxxxx
_	XxxxxxxxxXXXxXXXXXXXXXXXXXXXXXXXXXXXXX

TL-93-267	TL-93-267	element 1	element 2	element 3	element 4	element 5	element 6	element 7	element 8
62									
21.2	type	gypsum board	stud	insulation	gap	stud	insulation	gypsum board	gypsum board
22.6	material	сх	wood	G1	air	wood	G1	сх	сх
27.8	thickness mm	16	90	90	25	90	90	16	16
34.3	gauge								
38.0	spacing mm		406			406			
44.7	surface density kg/m ²	11.5		1.1			1.1	11.4	11.4
50.4	linear density kg/m		1.4			1.4			
56.1	total weight kg	85.6	37.0	7.1		37.9	7.1	84.4	84.7
61.3	fastener spacing - edge mm	406						610	406
64.8	fastener spacing - field mm	406						610	406
68.5	fastener top track pattern	с						с	с
71.7	fastener base track pattern	с						с	с
75.6	stud attached to top track		yes			yes			
78.3	double header								
80.8	orientation	vertical						vertical	vertical







Page 348

2G16_WS90(406)_GFB90_AIR25_WS90(406)_GFB90_2G16

Element Description:

TestID STC 50 Hz 63 Hz 80 Hz 100 Hz 125 Hz 160 Hz 200 Hz 250 Hz 315 Hz 400 Hz 500 Hz 630 Hz 800 Hz 1000 Hz 1250 Hz 1600 Hz

2000 Hz

2500 Hz

3150 Hz

4000 Hz

5000 Hz

6300 Hz

74.6

75.5

82.4

88.4

92.7

91.0

- 1 single layer of 16 mm type X gypsum board
- 2 single layer of 16 mm type X gypsum board
- **3** 90 mm wood studs at 406 mm on centre
- 4 90 mm of glass fibre insulation in cavity
- 5 25 mm gap filled with air
- **6** 90 mm wood studs at 406 mm on centre
- 7 90 mm of glass fibre insulation in cavity8 single layer of 16 mm type X gypsum bo
- 8 single layer of 16 mm type X gypsum board9 single layer of 16 mm type X gypsum board

TL-93-269	TL-93-269	element 1	element 2	element 3	element 4	element 5	element 6	element 7	element 8	element 9
67										
24.7	type	gypsum board	gypsum board	stud	insulation	gap	stud	insulation	gypsum board	gypsum board
25.4	material	сх	сх	wood	G1	air	wood	G1	СХ	сх
32.2	thickness mm	16	16	90	90	25	90	90	16	16
39.1	gauge									
42.8	spacing mm			406			406			
49.6	surface density kg/m ²	11.6	11.5		1.1			1.1	11.4	11.4
55.3	linear density kg/m			1.4			1.4			
61.1	total weight kg	85.9	85.6	37.0	7.1		37.9	7.1	84.4	84.7
65.9	fastener spacing - edge mm	406	610						610	406
69.1	fastener spacing - field mm	406	610						610	406
72.4	fastener top track pattern	с	с						с	с
75.1	fastener base track pattern	с	с						с	с
77.9	stud attached to top track			yes			yes			
80.7	double header									
83.7	orientation	vertical	vertical						vertical	vertical
83.9										









G6527.13-113-11-R0 ACOUSTICAL PERFORMANCE TEST REPORT ASTM E 90 AND ASTM E 492

Rendered to

PLITEQ INC.

Series/Model: Stone Pavers on Pillar System - Owens Corning FOAMULAR 250

Specimen Type: Weyerhauser TJI Assembly - 305 mm (12")

Overall Size: 3023 mm by 3632 mm (119" by 143")

STC	59
IIC	63

Test Specimen Identification:

Floor Topping: 50.8 mm (2") Stone Pavers
Supports: 50.08 mm (1.97") Bison Low Adjustable Deck Supports
Floor Underlayment: 50.8 mm (2") Owens Corning FOAMULAR 250 R-10 Insulation Sheathing
Subfloor Topping: 12.7 mm (0.5") Plywood Sheathing
Subfloor: 18.8 mm (0.74") Oriented Strand Board Sheathing
Insulation: 241.3 mm (9.5") Owens Corning Unfaced R-30 Fiberglass Insulation
Joist: 301.63 mm (11.88") Weyerhaeuser TrusJoist® 360 TJI Joist
Ceiling Isolation: 12.7 mm (0.5") ClarkDietrich RC Deluxe™ Resilient Channel
Ceiling: 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel
Ceiling: 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel

Reference should be made to Intertek-ATI Report G6527.13-113-11 for complete test specimen description. This page alone is not a complete report.

p. 717.764.7700f. 717.764.4129





Acoustical Performance Test Report

PLITEQ INC. 1370 Don Mills Road, Unit 300 Toronto, Ontario M3B 3N7 CANADA

Report	G6527.13-113-11
Test Date	12/22/16
Report Date	01/17/17

Project Scope

Architectural Testing, Inc., an Intertek company (Intertek-ATI), was contracted to conduct airborne sound transmission loss and impact sound transmission tests. The complete test data is included as attachments to this report. The full test specimen was assembled on the day of testing by Intertek-ATI. All materials provided by the client were installed on an existing Intertek-ATI assembly (Weyerhauser TJI Assembly - 305 mm (12")) utilizing Intertek-ATI-supplied materials.

Test Methods

The acoustical tests were conducted in accordance with the following standards. The equipment listed in the attachments meets the requirements of the following standards.

ASTM E 90-09, Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E 413-10, Classification for Rating Sound Insulation

ASTM E 492-09(2016)e1, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

ASTM E 989-06 (2012), Classification for Determination of Impact Insulation Class (IIC)

ASTM E 2235-04 (2012) Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

Test Procedure

All testing was conducted in the VT test chambers at Intertek-ATI located in York, Pennsylvania. The microphones were calibrated before conducting the tests.

The airborne transmission loss test was conducted in accordance with the ASTM E 90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Four sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.





Test Procedure (Continued)

The impact sound transmission test was conducted in accordance with the ASTM E 492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E 492, and five sound absorption measurements were conducted at each of five microphone positions.

The air temperature and relative humidity conditions were monitored and recorded during all measurements.

Test Conditions

Source Room		Receive Room	
Average Temperature	19.6°C (67.3°F)	Average Temperature	20.9°C (69.7°F)
Average Relative Humidity	46%	Average Relative Humidity	38%

Test Calculations

The STC (Sound Transmission Class) and IIC (Impact Insulation Class) ratings were calculated in accordance with ASTM E 413 and ASTM E 989, respectively.

Material	Dimensions (mm/inch)	Thickness (mm/inch)	Manufacturer and Series	Quantity	Average Weight		
Stone Pavers	603.3 by 603.3 23.8 by 23.8	50.8 / 2	N/A	10.98 m ² 118.19 ft ²	119.58 kg/m ² 24.49 lb/ft ²		
	Note: Laid on the	supports with	one on each of the four corners of the sq	uare pavers			
Deels Supports	203.2 by 203.2 8 by 8	50.1 / 1.97	Bison Low Adjustable	42 units	3.27 kg/unit 7.21 lb/unit		
Deck Supports	Note: Extended to 24") grid.	o maximum hei	ght, placed on the floor slab to create a	a 610 mm by	v 610 mm (24" by		
	1219 by 2438	50.8 / 2	Owens Corning FOAMULAR 250	10.98 m ²	1.6 kg/m ²		
Insulation Sheathing	48 by 96		R-10	118.19 ft ²	0.33 lb/ft^2		
	Note: Loose laid						
	1219 by 2438	127/05	N/A	10.98 m ²	6.72 kg/m ²		
Plywood Sheathing	48 by 96	12.77 0.5		118.19 ft ²	1.38 lb/ft ²		
	Note: Fastened to subfloor with 305 mm (12") centers along the joists						
	1219 by 2438	188/074	N/A	10.98 m ²	10.25 kg/m ²		
Oriented Strand	48 by 96	18.87 0.74		118.19 ft ²	2.1 lb/ft ²		
Board Sheathing	Note: Fastened to along perimeter a	o joists with 70 nd 305 mm (12	6 mm by 3 mm (3" by 0.12") framing i ") centers in the field.	nails on 203	mm (8") centers		
	2438 by 609.6	2413/95	Owens Corning Unfaced R-30	10.98 m ²	1.61 kg/m ²		
Fiberglass Insulation	96 by 24	211.57 9.5		118.19 ft ²	0.33 lb/ft ²		
	Note: Installed in	the cavity betw	een trusses flush with the subfloor				
TJI Joist	57.2 by 3023	301.6 /	Weverbaeuser Trus Loist® 360	21.2 lin m	4.46 kg/m		
	2.3 by 119	11.88		69.4 lin ft	3 lb/ft		
	Note: Fastened to	perimeter fran	ne on 610 mm (24") centers				

Test Specimen Materials and Installation Details





Test Specimen Materials and Installation Details (Continued)

Material	Dimensions (mm/inch)	Thickness (mm/inch)	Manufacturer and Series	Quantity	Average Weight		
	68.6 by 3454	127/05	Clark Districh PC DaluyaTM	27.6 lin m	0.33 kg/m		
Resilient Channel	2.7 by 136	12.77 0.3		90.5 lin ft	0.22 lb/ft		
Resilient Chalinei	Note: Installed on	n 406 mm (16")) centers perpendicular to the trusses. T	The measure	d thickness of the		
	metal was 0.7 mm	(0.03").					
	1219 by 3023	159/063	National Gypsum Gold Bond®	10.98 m ²	11.23 kg/m ²		
	48 by 119	15.97 0.05	Fire-Shield® Type X	118.19 ft ²	2.3 lb/ft ²		
Gypsum Panel Note: Fastened to resilient channels on 305 mm (12") centers with 25.4 mm (1") type S screw and perimeter sealed with SikaFlex Construction Sealant and covered with pressure-sensitive					e S screws. Seams sensitive tape.		
	1219 by 3023	15.0/0.63	National Gypsum Gold Bond®	10.98 m ²	11.23 kg/m ²		
	48 by 119	13.97 0.03	Fire-Shield® Type X	118.19 ft ²	2.3 lb/ft ²		
Gypsum Panel	Note: Fastened to resilient channels on 305 mm (12") centers with 41.3 mm (1.63") type S screws.						
	Seams and perimeter sealed with SikaFlex Construction Sealant and covered with pressure-sensitive						
	tape.						

Comments

The total weight of the floor/ceiling assembly was 2022 kg / 4458.4 lbs. Intertek-ATI will store samples of the test specimen for four years. A photograph of the test specimen is included in the attachments. The client did not supply drawings of the test specimen.





Intertek-ATI will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by Intertek-ATI for the entire test record retention period. The test record retention period ends four years after the test date.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen tested. This report is intended to help in the client's quality assurance program, but it does not represent a continuous or exhaustive evaluation of the specimen tested or of other products or materials that were not evaluated. The statements and data provided herein do not constitute approval, disapproval, certification, or acceptance of performance or materials.

This report may not be reproduced, except in full, without the written approval of Intertek-ATI.

FOR INTERTEK-ATI:

Daniel B. Mohler Project Lead - Acoustical Testing

Jordan Strybos Project Manager - Acoustical Testing

Attachments (6 pages): This report is complete only when all attachments listed are included.

Instrumentation (1) Airborne Sound Transmission Loss Data (2) Impact Sound Transmission Data (2) Photographs (1)

* Stated by Client/Manufacturer N/A - Non Applicable





Revision Log

Revision	Date	Page(s)	Description
R0	01/17/17	N/A	Original Report Issue

This report produced from controlled document template ATI 00629(d), revised 04/14/15.





Attachments

Instrumentation

Instrument	Manufacturer	Model	ATI Number	Date of Calibration
Data Acquisition Unit	National Instruments	PXI-1033	65124	06/17 *
Microphone Calibrator	Norsonic	1251	INT00127	01/16
Receive Room Microphone	PCB Piezontronics	378B20	63748	06/16
Receive Room Microphone	PCB Piezotronics	378B20	63744	06/16
Receive Room Microphone	PCB Piezotronics	378B20	63745	06/16
Receive Room Microphone	PCB Piezotronics	378C20	65617	06/16
Receive Room Microphone	PCB Piezotronics	378B20	63747	06/16
Receive Room Environmental Indicator	Comet	T7510	63810 63811	10/16 10/16
Source Room Microphone	PCB Piezotronics	378B20	63738	05/16
Source Room Microphone	PCB Piezotronics	378B20	63739	05/16
Source Room Microphone	PCB Piezotronics	378B20	63740	05/16
Source Room Microphone	PCB Piezotronics	378B20	63742	05/16
Source Room Microphone	Scantek	378B20	63741	05/16
Source Room Environmental Indicator	Comet	T7510	63812	11/16
Tapping Machine	Look Line s.r.l.	EM50 (TM50)	65351	02/16

* The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

Test Chambers

VT Receive Room Volume	157.31 m ³ (5555.47 ft ³)
VT Source Room Volume	190 m ³ (6709.79 ft ³)





AIRBORNE SOUND TRANSMISSION LOSS

ASTM E 90



Testing Laboratory

Test Date	12/22/16
Data File No.	G6527.13
Client	Pliteq Inc.
Description	50.8 mm (2") Stone Pavers, 50.08 mm (1.97") Bison Low Adjustable Deck Supports, 50.8 mm (2") Owens Corning FOAMULAR 250 R- 10 Insulation Sheathing, 12.7 mm (0.5") Plywood Sheathing, 18.8 mm (0.74") Oriented Strand Board Sheathing, 241.3 mm (9.5") Owens Corning Unfaced R-30 Fiberglass Insulation, 301.63 mm (11.88") Weyerhaeuser TrusJoist® 360 TJI Joist, 12.7 mm (0.5") ClarkDietrich RC Deluxe [™] Resilient Channel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel
Specimen Area	10.98 m ²
Technician	Daniel B. Mohler

Ener	Background	A h	Source	Receive	Specimen	95%	Number
Freq	SPL	Absorption	SPL	SPL	TL	Confidence	of
(Hz)	(dB)	(m ²)	(dB)	(dB)	(dB)	Limit	Deficiencies
50	47.2	37.6	103	63	34	3.70	-
63	45.3	29.0	100	66	30	3.30	-
80	33.7	16.1	108	70	36	4.00	-
100	35.4	12.7	105	69	35	2.10	-
125	35.4	10.5	104	66	38	1.10	5
160	30.1	9.3	104	65	40	1.10	6
200	25.9	10.0	102	57	46	1.20	3
250	28.9	10.0	100	52	49	1.00	3
315	26.8	9.5	105	52	53	0.70	2
400	22.4	8.2	102	49	54	0.60	4
500	23.7	7.8	101	45	57	0.50	2
630	25.1	7.4	101	43	59	0.30	1
800	23.1	7.5	101	42	60	0.40	1
1000	21.5	7.6	100	42	59	0.40	3
1250	21.1	7.9	98	38	62	0.40	1
1600	15.9	8.1	99	37	64	0.50	0
2000	9.4	9.2	99	36	64	0.40	0
2500	6.3	10.2	95	31	64	0.40	0
3150	5.2	11.3	97	27	69	0.50	0
4000	5.2	13.6	97	24	72	0.30	0
5000	5.6	16.6	94	19	73	0.60	-
6300	6.2	20.5	91	11	78	0.50	-
8000	6.6	28.6	92	9	79	0.60	-
10000	6.8	36.0	90	7	78	0.60	-

STC Rating 59 (Sound Transmission Class)

Deficiencies 31 (Sum of Deficiencies)

Rw Rating58(Sound Reduction Index)

Notes:

1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.

2) Specimen TL levels listed in red are potentially limited by the laboratory flanking limit.

2) Specimen TL levels listed in *blue* indicate the lower limit of the transmission loss.

3) Specimen TL levels listed in green indicate that there has been a filler wall correction applied





AIRBORNE SOUND TRANSMISSION LOSS

ASTM E 90



Testing Laboratory

Test Date	12/22/16
Data File No.	G6527.13
Client	Pliteq Inc.
Description	50.8 mm (2") Stone Pavers, 50.08 mm (1.97") Bison Low Adjustable Deck Supports, 50.8 mm (2") Owens Corning FOAMULAR 250 R- 10 Insulation Sheathing, 12.7 mm (0.5") Plywood Sheathing, 18.8 mm (0.74") Oriented Strand Board Sheathing, 241.3 mm (9.5") Owens Corning Unfaced R-30 Fiberglass Insulation, 301.63 mm (11.88") Weyerhaeuser TrusJoist® 360 TJI Joist, 12.7 mm (0.5") ClarkDietrich RC Deluxe [™] Resilient Channel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel
Specimen Area	10.98 m ²
Technician	Daniel B. Mohler







Architectural Testing



Testing Laboratory

IMPACT SOUND TRANSMISSION ASTM E 492

Test Date 12/22/16 Data File No. G6527.13 Client Pliteq Inc. 50.8 mm (2") Stone Pavers, 50.08 mm (1.97") Bison Low Adjustable Deck Supports, 50.8 mm (2") Owens Corning FOAMULAR 250 R-Description 10 Insulation Sheathing, 12.7 mm (0.5") Plywood Sheathing, 18.8 mm (0.74") Oriented Strand Board Sheathing, 241.3 mm (9.5") Owens Corning Unfaced R-30 Fiberglass Insulation, 301.63 mm (11.88") Weyerhaeuser TrusJoist® 360 TJI Joist, 12.7 mm (0.5") ClarkDietrich RC Deluxe™ Resilient Channel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel 10.98 m² **Specimen Area** Technician Daniel B. Mohler

Ener	De alemana d CDI		Normalized Impact	95%	Number
Freq	Background SPL	Absorption	SPL	Confidence	of
(Hz)	(dB)	(m ²)	(dB)	Limit	Deficiencies
50	43.8	34.7	52	3.1	-
63	40.9	36.9	55	2.5	-
80	34.5	16.4	54	3.3	-
100	35.9	12.2	48	1.5	0
125	33.4	10.2	51	2.0	2
160	25.8	9.2	47	2.8	0
200	23.2	10.0	38	1.2	0
250	27.8	10.3	37	1.0	0
315	22.7	9.4	40	1.0	0
400	19.7	8.2	39	1.2	0
500	22.9	7.7	45	0.8	0
630	24.7	7.3	44	0.7	0
800	21.5	7.4	49	0.4	4
1000	21.1	7.6	41	0.7	0
1250	20.9	7.8	44	0.2	3
1600	16.2	8.0	46	0.7	8
2000	10.0	9.1	35	0.3	0
2500	7.1	10.3	40	0.7	8
3150	6.3	11.3	29	0.3	0
4000	6.0	13.7	23	0.3	-
5000	6.9	16.6	15	1.0	-
6300	9.2	20.7	10	0.7	-
8000	8.8	28.5	10	0.7	-
10000	9.2	35.3	11	0.8	-

IIC Rating 63 (Impact Insulation Class)

Deficiencies 25 (Sum of Deficiencies)

Note: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.





Architectural Testing



Testing Laboratory

IMPACT	SOUND	TRANSMISSION	
		E 400	

ASTM E 492

Test Date	12/22/16
Data File No.	G6527.13
Client	Pliteq Inc.
Description	50.8 mm (2") Stone Pavers, 50.08 mm (1.97") Bison Low Adjustable Deck Supports, 50.8 mm (2") Owens Corning FOAMULAR 250 R- 10 Insulation Sheathing, 12.7 mm (0.5") Plywood Sheathing, 18.8 mm (0.74") Oriented Strand Board Sheathing, 241.3 mm (9.5") Owens Corning Unfaced R-30 Fiberglass Insulation, 301.63 mm (11.88") Weyerhaeuser TrusJoist® 360 TJI Joist, 12.7 mm (0.5") ClarkDietrich RC Deluxe [™] Resilient Channel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm (0.63") National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel
Specimen Area	10.98 m ²
Technician	Daniel B. Mohler







Photograph



Construction of Test Specimen





w

02/28/17

FLS-1


FLS-2



FLS-3



3115 NW 132nd Place, Portland, OR 97229-7037 Phone 503-531-8717 Fax 503-531-8564 e-mail dgessert@frontier.com

Letter

Date:	February 27, 2017
To:	William Wilson Architects PC 1022 SW Salmon St Portland, OR 97205 Sent via email
Attention:	Jennifer Nye, AIA
From:	David Gessert, P. E. Fire Protection Engineer
Subject/Project:	Sellwood Mixed Use 7119 SE Milwaukie Ave Portland, OR 97202 Three Building Assemblies Opinion of Fire Resistance
Job No.:	2017-01.16

Total Pages: 3

Executive Summary

This engineer has been requested to provide an opinion of the fire resistance of three building assemblies for the Sellwood Mixed Use project. This project is also referred to as the Sellwood Apartments. The three details have been analyzed and each shows at least 60 minutes (1-hour) of fire resistance.

Sellwood Mixed Use – Fire Resistance of Three Building Assemblies

See Drawing A1.01 Sellwood Mixed Use

Detail 8 Floor/Ceiling shows the following layers from top to bottom:

Floor Finish 1/8 inch Rubber Underlayment 2 inch Gypsum Underlayment Over ³/₄ inch Acoustic Sound Control Mat ¹/₂ inch Plywood ³/₄ inch Plywood 3X (2¹/₂ inch actual) Decking Letter to Jennifer Nye February 27, 2017 Page **2** of **3**

Detail 9A & 9B Roof Deck Assembly

Pedestal Paver System, Flush with Interior Floor Finish Single-Ply Roof Membrane with Cover BD as Req'd by Roofing Mfr Continuous Rigid Insulation Vapor Barrier as Req'd ½ inch Plywood – Omitted on Detail 9B ¾ inch Acoustic Sound Control Mat – Omitted on Detail 9B ½ inch Plywood – Omitted on Detail 9B ½ inch Plywood – Omitted on Detail 9B ½ inch Plywood, See Structural 3X (2½ inch actual) Decking

Detail 12 Roof @ Terrace shows the following layers from top to bottom:

Roof Membrane Cover Board as Req'd by Roofing Mfr Tapered Rigid Insulation Sheathing 3X (2¹/₂ inch actual) Decking

To determine if 60 minutes of fire resistance is present in subject floor/ceiling assembly analysis of sacrificial wood char is selected. Published data shows wood chars at a rate of 1.4-1.5 inches per hour. Moreover this char rate has been written into Code for fastener protection. Code Reference: OSSC 2014 722.6.3.3 There is variation in char rates of specific species of wood and actual char is non-linear but these variations are minor.

Wood is a poor conductor of heat. While the bottom surface of the wood deck is hot, the interior of the wood deck remains cool and retains its load bearing capability.

After one hour of fire exposure the 3X T&G wood decking has been reduced to a thickness of 1 inch.

These three reduced section assemblies have been analyzed by the project structural engineer and using reasonable assumptions the assembly would remain in place. The structural engineer used a char rate of 1.8 inches per hour. See the February 24, 2017 letter to Ms. Jennifer Nye from Nishkian Dean. The letter is sealed by Robert A. Aman, P. E. (Structural Engineer).

Conclusion

The three building assemblies analyzed for the Sellwood Mixed Use project show least onehour of fire resistance.

I will be pleased to address your questions and comments.

Letter to Jennifer Nye February 27, 2017 Page **3** of **3**

References

Calculating the Fire Resistance of Exposed Wood Members, Technical Report 10, 2003, American Forest & Paper Association, American Wood Council, Washington, DC

Drawing A1.01, Construction Assemblies, Sellwood Mixed Use, 12/15/16, William Wilson Architects, Portland, Oregon

SFPE Handbook of Fire Protection Engineering, Fifth Edition, 2016, Springer International Publishing AG, Cham, Switzerland

Oregon Structural Specialty Code, 2014 Edition, International Code Council, Country Club Hills, Illinois

Dean, Nishkian, letter dated February 24, 2017 to Ms. Jennifer Nye, William Wilson Architects, Portland, Oregon, Re: Project: Sellwood Apartments, Reference: 1-Hour Fire Rating of Exposed 3x Tongue & Groove Decking, Nishkian Dean, Portland, Oregon (Letter sealed by Robert A. Aman, P. E. (Structural Engineer))

End of Report

NISHKIAN DEAN

CONSULTING AND STRUCTURAL ENGINEERS



February 24, 2017

Ms. Jennifer Nye William Wilson Architects 1022 SW Salmon St., Suite 350 Portland, OR 97205

Project: Sellwood Apartments - 7119 SE Milwaukie Ave, Portland, OR

NDI Project No.: 31601.00

Reference: 1-Hour Fire Rating of Exposed 3x Tongue & Groove Decking

Dear Jennifer:

We are writing in regards to the structural adequacy of the exposed 3x tongue and groove decking after 1 hour of char from a fire event for the subject project. There are two specific areas above the retail space, a public area (above the western side of the retail space) and a residential area (above the eastern side of the retail space). The dead loads applied to the decking in both areas is the same. The live load to each area is 100 psf and 40 psf, respectively. The decking also occurs at a roof deck condition which has a reduced dead load compared to that of the floor. The floor and roof assemblies are shown on architectural drawing sheet A1.01.

The attached structural calculations confirm that the exposed 3x decking would still be adequate to handle the design loading after being exposed to 1 hour of fire (using a char rate of 1.8" per hour).

If you have any questions please call.

Sincerely, NISHKIAN DEAN



Robert A. Aman, PE, SE Associate

h:\nd31601 sellwood apts\01 admin\1.1 letters\nd31602 sellwood apartments - 3x deck for 1-hr letter 20170224.docx

CONSULTING AND STRUCTURAL ENGINEERS SINCE 1919

 \bigcirc

1022 SW Salmon Street, Suite 300, Portland, OR 97205 Tel: (503) 274-1843 Fax: (503) 273-5696

JOB SELLWOOD	NO. 31602
SHEET NO	OF
CALCULATED BY	DATE
CHECKED BY	DATE
SCALE	

FIRE RATING VERIFICATION - I HOUR RATED DECK

1



FINISH FLOOR	*	2.0 PSF
2" LIGHT-WEIGHT	CONC	16.0 PSF
ACCOUSITIC BOA	RD	2,0 psf
12" NON STRUCT	РИ	1.7 PSF
12" PLYWOOD		1.7 PSE
3 x DECKING	f () () 1 g	7.6 PSF

DEAD 31.0 PSF

AT RESIDENTIAL AREA

DEAD LOAD = 31.0 PST
LIVE LOAD = 40.0 PSF
TOTAL LOAD = 71.0 PSF
MAX CLEAR SPAN = 7'-9" - 12" = 6'-9" = 6.75'
• CHECK DECK FOR NORMAL LOAD LOADING

$$M_{MAX} = \frac{Wl^2}{8} = \frac{(71.0 \text{ PSF})(6.75')^2}{8} = 404 \text{ feilb}$$
 (PER FORT)
 $S_c = \frac{1}{6} \text{ b } d^2 = \frac{1}{6} (\frac{12.0}{6c})(2.5 \text{ in})^2 = 12.5 \text{ in}^3$ (PER FORT)
 $F_{bs}^{\prime} = (F_b C_r) C_b C_b C_c C_c C_c$
 $= (2000 \text{ FsI})(1.0)(1.0)(1.0)(1.0) = 2000 \text{ PSU}$
 $M_s^{\prime} = F_{bs}^{\prime} S_s = (2000 \text{ PSI})(12.5 \text{ in}^3) \times \frac{16}{12.10}$
 $= 2083 \text{ ft.} \text{ lb}$
 $M_s^{\prime} \ge M_{MAX}$
 $2083 \text{ ft.} \text{ lb} \ge 404 \text{ ft.} \text{ lb}$

FOR NORMAL LOADING

NISHKIAN DEAN

CONSULTING AND STRUCTURAL ENGINEERS SINCE 1919 1022 SW Salmon Street, Suite 300, Portland, OR 97205

Tel: (503) 274-1843 Fax: (503) 273-5696

 \bigcirc

JOB SELLWOOD	NO. 31602
SHEET NO	OF
CALCULATED BY	_ DATE
CHECKED BY	_ DATE
SCALE	

AT RESIDENTIAL AREA (CONTINUED) · CHECK DECK FOR LOADING DURING FIRE MyMANX = 404 ft. 16 SF= 2 bd2 = 2 (12in) (2.5"-1.8in)2 = 0.98 m3 Fbf= (2.85)(Fb Cr) CF = (2.85)(2000 psi)(1.0) = 5700 PSU $M'_{f} = F'_{bt} S_{f} = (5700 \text{ Psi})(0.98 \text{ m}^{3})(\frac{1 \text{ ft}}{12 \text{ m}})$ = 466 fl.1b MEZ MMAX 466 fr. 10 2 404 fr. 11 1. 3x DECKING OK AT RESIDENTIAL AREA WITH A CLEAR SPAN OF 6'-9" MAX (7'-9" CENTER TO CENTER OF BEAMS)

CONSULTING AND STRUCTURAL ENGINEERS SINCE 1919

 \bigcirc

1022 SW Salmon Street, Suite 300, Portland, OR 97205 Tel: (503) 274-1843 Fax: (503) 273-5696

JOB SELLWOOD	NO. 31602
SHEET NO.	_ OF
CALCULATED BY DKB	_ DATE
CHECKED BY	_ DATE
SCALE	

AT PUBLIC AREA DEAD LOAD = 31.0 PSF LIVE LOAD = 100.0 PSF TOTAL LOAD = 131.0 PSF BEAM WIDTH (MIN) MAX CLEAR SPAN = 6-3"-12" - 5'-3" = 5:25' · CHECK DECK FOR NORMAL LOADING Mmax = wl2 = (131.0 PSF) (5.25) = 451 ft. 16 $5_5 = \frac{1}{6} b d^2 = \frac{1}{6} (12in)(2.5in)^2 = 12.5 Gill$ F'bs = (Fb Cr) CD Cm Ct CF = (2000 PSi)(1.0)(1.0)(1.0)(1.0) = 2000 PSU Ms = Fbs Ss = (2000 Psi)(12.5 1,3) x - 1 fe = 2083 fr. 1h M'S > MMAX 2083 Ft.16 2 451 ft.16 1. 3x DECKING OK FOR NORMAL LOADING CHECK DECK FOR LOADING DURING FIRE MMAX = 451 fl. 16 $S_{q} = \frac{1}{6} b d^{2} = \frac{1}{6} (12 in) (2.5'' - 1.8'')^{2} = 0.98 in^{3}$ F'bc = (2.85)(Fb Cr) CF = (2.85) (2000 Psi) (1.0) = 5700 PGI

NISHKI

	JOB_SELLWOOD	NO. 31602
CONSULTING AND STRUCTURAL ENGINEERS SINCE 1919	SHEET NO	OF
1022 SW Salmon Street, Suite 300, Portland, OR 97205	CALCULATED BY	_ DATE
Tel: (503) 274-1843 Fax: (503) 273-5696	CHECKED BY	_ DATE
	SCALE	

AT PUBLIC AREA (CONTINUED) M's = F'bi St = (5700 psi) (0.98 m3) 100 = 466 fl. 16

M'E > MMax

466 FLIL > 451 FLIL

1. 3x DECKING OK AT PUBLIC AREA WITH A MAX CLEAR SPAN OF 5-3" (6'-3" CENTER TO CENTER OF BEAMS - MIN. WIDTH OF BEAM 12")

ZIGAN