


**STRUCTURAL CALCULATIONS  
REVISIONS TO CONCRETE STRENGTH**

**PROJECT:**  
**Kramer / Falk Remodel**  
4145 SW Agate Lane  
Portland, OR 97239

for

**Eric Butler Design**  
**2400 SE Holgate Blvd**  
**Portland, OR 97202**



*James G. Pierson, Inc.*  
Consulting Structural Engineers  
610 S.W. ALDER SUITE 918 PORTLAND, OR. 97205  
(503) 226-1286 FAX 226-3130

May 9, 2022

## **REMODEL / ADDITION**

Project located in Portland, Oregon

### **GENERAL DESIGN LOADS:**


Project is designed in accord with requirements of the 2019 Oregon Structural Specialty Code. For this location the following design parameters apply:

Occupancy Category II  
Seismic Site Class D, Design Category D  
Roof Snow Load 25 PSF      Roof Dead Load 15 PSF  
Floor Live Load 40 PSF      Floor Dead Load 12 PSF  
Deck Live Load 60 PSF  
Wind: 98 MPH EXP C (ASCE 7-16)  
Allowable Soil Bearing Pressure = 2300 PSF (Per Strata Design dated 10/23/19)

### **Design Summary:**

The following revised calculations are for the house remodel in Portland, Oregon. The design strength of the site retaining walls was changed from 3000 psi to 2500 psi concrete to eliminate the requirement for special inspection (that was not done when built). The 2<sup>nd</sup> item changed is detail 7/S4.1 for the epoxied dowels to tie the new foundation to existing. These dowels work with or without epoxy and the epoxy was not inspected when installed. As such, no special inspection would be required on project.

The techniques and principles of structural analysis used for these calculations conform to generally accepted standards of the engineering community. These design calculations have been prepared based upon architectural drawings furnished by client.



H	W	t	A	B	T	V	R
MAX. HT. IN FEET	TOTAL WIDTH IN INCHES	STEM WIDTH IN INCHES	TOE LENGTH IN INCHES	HEEL LENGTH IN INCHES	FOOTING THICKNESS IN INCHES	VERTICAL WALL REINFORCING	TRANSVERSE REINF. IN FOOTING
4'-0"	30"	6"	12"	12"	12"	#4 @ 18" O/C	NOT REQUIRED
6'-0"	48"	6"	18"	24"	12"	#4 @ 18" O/C	NOT REQUIRED
8'-0"	66"	8"	24"	34"	12"	#4 @ 12" O/C	#4 @ 18" O/C

NOTES:

RETAINING WALLS ARE DESIGNED FOR THE FOLLOWING PARAMETERS:

STUDD WALL AXIAL LOAD CAN RANGE BETWEEN ZERO AND 1500 lb/ft VERTICAL LOAD

MAX. BEARING PRESSURE = 2300 psf

SUBGRADE COEFFICIENT OF FRICTION = 0.40

SOIL PASSIVE PRESSURE = 250 (h) pcf

CONCRETE TO BE  $f_c' = 2500$  psi MIN.

REBAR TO BE ASTM A615 GRADE 40 MIN.

SOIL ACTIVE PRESSURE = 40 (h) pcf

1  
S4.2

DETAIL

1" = 1'-0"

5

4

James G. Pierson, Inc.

Consulting Structural Engineers

610 S.W. Alder, Suite 918 Portland, Oregon 97205

Tel: (503) 226-1286 Fax: (503) 226-3130

Project

Kramer/Falk Remodel

Location

4145 SW Agate

Client

Butler Design

Job no.

Date

5/9/22

Sheet no.

Page 3 of 27

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 1  
Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\


RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Criteria

Retained Height	=	3.00 ft
Wall height above soil	=	0.00 ft
Slope Behind Wall	=	0.00
Height of Soil over Toe	=	6.00 in
Water height over heel	=	0.0 ft



### Load Factors

Building Code	IBC 2018,ACI
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.000
Seismic, E	1.000

### Soil Data and Lateral Earth Pressure

Allow Soil Bearing	=	2,300.0 psf	Soil Density, Heel	=	110.00 pcf
Equivalent Fluid Pressure Method			Soil Density, Toe	=	0.00 pcf
Active Heel Pressure	=	40.0 psf/ft	Footings  Soil Friction	=	0.400
	=		Soil height to ignore for passive pressure	=	12.00 in
Passive Pressure	=	250.0 psf/ft			

### Surcharge Loads

Surcharge Over Heel	=	0.0 psf	Surcharge Over Toe	=	0.0
Used To Resist Sliding & Overturning			Used for Sliding & Overturning		

### Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs	Axial Load Eccentricity	=	0.0 in
Axial Live Load	=	0.0 lbs			

### Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)

### Wind on Exposed Stem

Wind on Exposed Stem (Service Level)	=	0.0 psf
---	---	---------

### Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs	Footing Type	Line Load
Footing Width	=	0.00 ft	Base Above/Below Soil	
Eccentricity	=	0.00 in	at Back of Wall	= 0.0 ft
Wall to Ftg CL Dist	=	0.00 ft	Poisson's Ratio	= 0.300

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :

Dsgnr: Golberg

Description....

Site Retaining Wall sch.

Page : 2  
Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12

License : KW-06056929

License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Earth Pressure Seismic Load

Method : Triangular

Load at bottom of Triangular Distribution . . . . .	=	112.000 psf	Total Strength-Level Seismic Load. . . . .	=	224.000 lbs
Strength-Level)			Total Service-Level Seismic Load. . . . .	=	156.800 lbs

James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai  
 Title 4 ft :  
 Dsgnr: Golberg  
 Description...  
 Site Retaining Wall sch.

Page : 3  
 Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018, ACI 318-14, TMS 402-16

### Wall Design Summary

#### Stability Ratios

Overturning = 2.27 OK  
 Slab Resists All Sliding !

#### Soil Bearing

Total Bearing Load = 950 lbs  
 ...resultant ecc. = 4.82 in

Soil Pressure @ Toe = 746 psf OK  
 Soil Pressure @ Heel = 14 psf OK  
 Allowable = 2,300 psf  
 Soil Pressure Less Than Allowable

ACI Factored @ Toe = 1,045 psf  
 ACI Factored @ Heel = 19 psf

Footing Shear @ Toe = 2.1 psi OK  
 Footing Shear @ Heel = 2.8 psi OK  
 Allowable = 75.0 psi

### Overturning

#### Resisting Moments

<u>Resisting Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Soil Over Heel (above water table, if any)	275.0 lbs	2.08 ft	572.9ft-#
Soil Over Heel (below water table, if any)	0.0		
Water Table	0.0		
Soil Over Heel	275.0	2.08	572.9
Sloped Soil Over Heel	0.0		
Surcharge Over Heel	0.0		
Adjacent Footing Load	0.0		
Axial Dead Load on Stem	0.0		
Axial Live Load on Stem *	0.0		
Soil Over Toe	0.0	0.50	
Surcharge Over Toe	0.0		
Stem Weight(s)	300.0	1.33	400.0
Earth @ Stem Transitions	0.0		
Footing Weight	375.0	1.25	468.8
Key Weight	0.0	2.00	
Vert. Component	0.0		
<b>Total Vertical Loads</b>	950.0 lbs		

**Resisting Moment**

**1,441.7 ft-#**

**Eccentricity**

**4.8 in**

\* Axial live load NOT included in total displayed, or used for overturning or sliding resistance, but is included for soil pressure calculations.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :  
Dsgnr: Golberg  
Description....

Site Retaining Wall sch.

Page : 4  
Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018, ACI 318-14, TMS 402-16

### Overturning

#### Overturning Moments

##### Overturning Moments

	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Heel Active Pressure (above water table, if any)	320.0 lbs	1.33 ft	426.7 ft-#
Heel Active Pressure (below water table, if any)	0.0		
Hydrostatic Force	0.0		
Buoyant Force	0.0		
Surcharge over Heel	0.0		
Adjacent Footing	0.0		
Surcharge Over Toe	0.0		
Load @ Stem Above Soil	0.0		
Added Lateral Load	0.0		
Seismic Load	156.8	1.33	209.1
Seismic-Self-weight	0.0		
<b>Totals =</b>	476.8 lbs		
<b>Overturning Moment</b>			635.7 ft-#

James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :  
 Dsgnr: Golberg  
 Description....  
 Site Retaining Wall sch.

Page : 5  
 Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Stem Design Summary

Bottom		
		Stem OK
<b>Design Height Above Ftg</b>	ft =	0.00
Wall Material Above "Ht"	=	Concrete
Design Method	=	LRFD
Thickness	=	8.00
Rebar Size	= #	4
Rebar Spacing	=	9.00
Rebar Placed at	=	Edge
<b>Design Data</b>		
fb/FB + fa/Fa	=	0.057
<b>Total Force @ Section</b>		
Service Level	lbs =	
Strength Level	lbs =	414.0
<b>Moment....Actual</b>		
Service Level	ft-# =	
Strength Level	ft-# =	414.0
Moment.....Allowable	=	7,122.4
<b>Shear.....Actual</b>		
Service Level	psi =	
Strength Level	psi =	5.5
Shear.....Allowable	psi =	75.0
Anet	in2 =	
Rebar Depth 'd'	in =	6.25
<b>Masonry Data</b>		
f <sub>m</sub>	psi =	
F <sub>s</sub>	psi =	
Solid Grouting	=	
Modular Ratio 'n'	=	
Wall Weight	psf =	100.0
Short Term Factor	=	
Equiv. Solid Thick.	=	
Masonry Block Type	=	Medium Weight
Masonry Design Method	=	ASD
<b>Concrete Data</b>		
f <sub>c</sub>	psi =	2,500.0
F <sub>y</sub>	psi =	60,000.0



James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 6  
Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Concrete Stem Rebar Area Details

Bottom Stem	Vertical Reinforcing	Horizontal Reinforcing
As (based on applied moment) :	0.0155 in <sup>2</sup> /ft	
(4/3) * As :	0.0207 in <sup>2</sup> /ft	Min Stem T&S Reinf Area 0.576 in <sup>2</sup>
200bd/fy : 200(12)(6.25)/60000 :	0.25 in <sup>2</sup> /ft	Min Stem T&S Reinf Area per ft of stem Height : 0.192 in <sup>2</sup> /ft
0.0018bh : 0.0018(12)(8) :	0.1728 in <sup>2</sup> /ft	Horizontal Reinforcing Options :
	=====	One layer of : Two layers of :
Required Area :	0.1728 in <sup>2</sup> /ft	#4@ 12.50 in #4@ 25.00 in
Provided Area :	0.2667 in <sup>2</sup> /ft	#5@ 19.38 in #5@ 38.75 in
Maximum Area :	0.8467 in <sup>2</sup> /ft	#6@ 27.50 in #6@ 55.00 in

### Footing Data

Toe Width	=	1.00 ft	f <sub>c</sub>	=	2,500 psi
Heel Width	=	1.50	F <sub>y</sub>	=	60,000 psi
Total Footing Width	=	2.50 ft	Footing Concrete Density	=	150.00 pcf
Footing Thickness	=	12.00 in	Min. As %	=	0.0018
Key Width	=	0.00 in	Rebar Cover @ Top	=	2.00 in
Key Depth	=	0.00 in	@ Bottom	=	3.00 in
Key Distance from Toe	=	2.00 ft			

### Footing Design Results

	Toe	Heel
Factored Pressure	= 1,045	19 psf
Mu' : Upward	= 5,448	46 ft-#
Mu' : Downward	= 1,476	200 ft-#
Mu: Design	= 143	-15 ft-#
Actual 1-Way Shear	= 2.05	2.82 psi
Allow 1-Way Shear	= 75.00	75.00 psi
Toe Reinforcing	= # 4 @ 9.00 in	
Heel Reinforcing	= # 4 @ 9.00 in	
Key Reinforcing	= None Spec'd	

#### Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.34 in, #6@ 20.36 in, #7@ 27.77 in, #8@ 36.56 in, #9@ 46

Heel: #4@ 9.25 in, #5@ 14.34 in, #6@ 20.36 in, #7@ 27.77 in, #8@ 36.56 in, #9@ 46

Key: No key defined

Min footing T&S reinf Area 0.65 in<sup>2</sup>  
Min footing T&S reinf Area per fc 0.26 in<sup>2</sup> /ft

If one layer of horizontal bars:	If two layers of horizontal bars:
#4@ 9.26 in	#4@ 18.52 in
#5@ 14.35 in	#5@ 28.70 in
#6@ 20.37 in	#6@ 40.74 in

Footing Torsion, T<sub>u</sub> = 0.00 ft-lbs  
Footing Allow. Torsion, phi T<sub>u</sub> = 0.00 ft-lbs

If torsion exceeds allowable, provide supplemental design for footing torsion.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :  
Dsgnr: Golberg  
Description....

Site Retaining Wall sch.

Page : 7  
Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Tilt

#### Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci

Horizontal Defl @ Top of Wall (approximate only) 0.025 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe.

because the wall would then tend to rotate into the retained soil.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 4 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 8  
Date: 7 JAN 2020

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Rebar Lap & Embedment Lengths Information

Stem Design Segment: Bottom

Stem Design Height: 0.00 ft above top of footing

Lap Splice length for #4 bar specified in this stem design segment = 18.72 in

Development length for #4 bar specified in this stem design segment = 14.40 in

Hooked embedment length into footing for #4 bar specified in this stem design segment = 8.40 in

As Provided = 0.2667 in<sup>2</sup>/ft

As Required = 0.1728 in<sup>2</sup>/ft

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 1  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\


RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Criteria

Retained Height	=	5.00 ft
Wall height above soil	=	0.00 ft
Slope Behind Wall	=	0.00
Height of Soil over Toe	=	6.00 in
Water height over heel	=	0.0 ft



### Load Factors

Building Code	IBC 2018,ACI
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.000
Seismic, E	1.000

### Soil Data and Lateral Earth Pressure

Allow Soil Bearing	=	2,300.0 psf	Soil Density, Heel	=	110.00 pcf
Equivalent Fluid Pressure Method			Soil Density, Toe	=	0.00 pcf
Active Heel Pressure	=	40.0 psf/ft	Footings  Soil Friction	=	0.400
	=		Soil height to ignore for passive pressure	=	12.00 in
Passive Pressure	=	250.0 psf/ft			

### Surcharge Loads

Surcharge Over Heel	=	0.0 psf	Surcharge Over Toe	=	0.0
Used To Resist Sliding & Overturning			Used for Sliding & Overturning		

### Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs	Axial Load Eccentricity	=	0.0 in
Axial Live Load	=	0.0 lbs			

### Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)

### Wind on Exposed Stem

Wind on Exposed Stem (Service Level)	=	0.0 psf
---	---	---------

### Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs	Footing Type	Line Load
Footing Width	=	0.00 ft	Base Above/Below Soil	
Eccentricity	=	0.00 in	at Back of Wall	= 0.0 ft
Wall to Ftg CL Dist	=	0.00 ft	Poisson's Ratio	= 0.300

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 2  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Earth Pressure Seismic Load

Method : Triangular

Load at bottom of Triangular Distribution . . . . .	=	175.000 psf	Total Strength-Level Seismic Load. . . . .	=	525.000 lbs
Strength-Level)			Total Service-Level Seismic Load. . . . .	=	367.500 lbs

James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
 Dsgnr: Golberg  
 Description...  
 Site Retaining Wall sch.

Page : 3  
 Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018, ACI 318-14, TMS 402-16

### Wall Design Summary

#### Stability Ratios

Overturning = 2.40 OK  
 Slab Resists All Sliding !

#### Soil Bearing

Total Bearing Load = 2,108 lbs  
 ...resultant ecc. = 6.64 in

Soil Pressure @ Toe = 964 psf OK  
 Soil Pressure @ Heel = 90 psf OK  
 Allowable = 2,300 psf  
 Soil Pressure Less Than Allowable

ACI Factored @ Toe = 1,350 psf  
 ACI Factored @ Heel = 126 psf

Footing Shear @ Toe = 7.5 psi OK  
 Footing Shear @ Heel = 7.0 psi OK  
 Allowable = 75.0 psi

### Overturning

#### Resisting Moments

<u>Resisting Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Soil Over Heel (above water table, if any)	1,008.3 lbs	3.08 ft	3,109.0ft-#
Soil Over Heel (below water table, if any)	0.0		
Water Table	0.0		
Soil Over Heel	1,008.3	3.08	3,109.0
Sloped Soil Over Heel	0.0		
Surcharge Over Heel	0.0		
Adjacent Footing Load	0.0		
Axial Dead Load on Stem	0.0		
Axial Live Load on Stem *	0.0		
Soil Over Toe	0.0	0.75	
Surcharge Over Toe	0.0		
Stem Weight(s)	500.0	1.83	916.7
Earth @ Stem Transitions	0.0		
Footing Weight	600.0	2.00	1,200.0
Key Weight	0.0	2.00	
Vert. Component	0.0		
<b>Total Vertical Loads</b>	<b>2,108.3 lbs</b>		

**Resisting Moment**

**5,225.7 ft-#**

**Eccentricity**

**6.6 in**

\* Axial live load NOT included in total displayed, or used for overturning or sliding resistance, but is included for soil pressure calculations.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
Dsgnr: Golberg  
Description...  
Site Retaining Wall sch.

Page : 4  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018, ACI 318-14, TMS 402-16

### Overturning

#### Overturning Moments

<u>Overturning Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Heel Active Pressure (above water table, if any)	720.0 lbs	2.00 ft	1,440.0 ft-#
Heel Active Pressure (below water table, if any)	0.0		
Hydrostatic Force	0.0		
Buoyant Force	0.0		
Surcharge over Heel	0.0		
Adjacent Footing	0.0		
Surcharge Over Toe	0.0		
Load @ Stem Above Soil	0.0		
Added Lateral Load	0.0		
Seismic Load	367.5	2.00	735.0
Seismic-Self-weight	0.0		
<b>Totals =</b>	1,087.5 lbs		
	<b>Overturning Moment</b>		2,175.0 ft-#

James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
 Dsgnr: Golberg  
 Description....  
 Site Retaining Wall sch.

Page : 5  
 Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Stem Design Summary

Bottom		
		Stem OK
Design Height Above Ftg	ft =	0.00
Wall Material Above "Ht"	=	Concrete
Design Method	=	LRFD
Thickness	=	8.00
Rebar Size	= #	4
Rebar Spacing	=	9.00
Rebar Placed at	=	Edge
<b>Design Data</b>		
fb/FB + fa/Fa	=	0.272
<b>Total Force @ Section</b>		
Service Level	lbs =	
Strength Level	lbs =	1,164.6
<b>Moment....Actual</b>		
Service Level	ft-# =	
Strength Level	ft-# =	1,941.0
Moment.....Allowable	=	7,122.4
<b>Shear.....Actual</b>		
Service Level	psi =	
Strength Level	psi =	15.5
Shear.....Allowable	psi =	75.0
Anet	in2 =	
Rebar Depth 'd'	in =	6.25
<b>Masonry Data</b>		
f <sub>m</sub>	psi =	
F <sub>s</sub>	psi =	
Solid Grouting	=	
Modular Ratio 'n'	=	
Wall Weight	psf =	100.0
Short Term Factor	=	
Equiv. Solid Thick.	=	
Masonry Block Type	=	Medium Weight
Masonry Design Method	=	ASD
<b>Concrete Data</b>		
f <sub>c</sub>	psi =	2,500.0
F <sub>y</sub>	psi =	60,000.0



James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 6  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018, ACI 318-14, TMS 402-16

### Concrete Stem Rebar Area Details

Bottom Stem	Vertical Reinforcing	Horizontal Reinforcing
As (based on applied moment) :	0.0727 in <sup>2</sup> /ft	
(4/3) * As :	0.097 in <sup>2</sup> /ft	Min Stem T&S Reinf Area 0.960 in <sup>2</sup>
200bd/fy : 200(12)(6.25)/60000 :	0.25 in <sup>2</sup> /ft	Min Stem T&S Reinf Area per ft of stem Height : 0.192 in <sup>2</sup> /ft
0.0018bh : 0.0018(12)(8) :	0.1728 in <sup>2</sup> /ft	Horizontal Reinforcing Options :
	=====	One layer of : Two layers of :
Required Area :	0.1728 in <sup>2</sup> /ft	#4@ 12.50 in #4@ 25.00 in
Provided Area :	0.2667 in <sup>2</sup> /ft	#5@ 19.38 in #5@ 38.75 in
Maximum Area :	0.8467 in <sup>2</sup> /ft	#6@ 27.50 in #6@ 55.00 in

### Footing Data

Toe Width	=	1.50 ft	f <sub>c</sub>	=	2,500 psi
Heel Width	=	2.50	F <sub>y</sub>	=	60,000 psi
Total Footing Width	=	4.00 ft	Footing Concrete Density	=	150.00 pcf
Footing Thickness	=	12.00 in	Min. As %	=	0.0018
Key Width	=	0.00 in	Rebar Cover @ Top	=	2.00 in
Key Depth	=	0.00 in	@ Bottom	=	3.00 in
Key Distance from Toe	=	2.00 ft			

### Footing Design Results

	Toe	Heel
Factored Pressure	= 1,350	126 psf
Mu' : Upward	= 16,160	526 ft-#
Mu' : Downward	= 3,321	1,412 ft-#
Mu: Design	= 553	-172 ft-#
Actual 1-Way Shear	= 7.46	6.97 psi
Allow 1-Way Shear	= 75.00	75.00 psi
Toe Reinforcing	= # 4 @ 9.00 in	
Heel Reinforcing	= # 4 @ 9.00 in	
Key Reinforcing	= None Spec'd	

#### Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.34 in, #6@ 20.36 in, #7@ 27.77 in, #8@ 36.56 in, #9@ 46

Heel: #4@ 9.25 in, #5@ 14.34 in, #6@ 20.36 in, #7@ 27.77 in, #8@ 36.56 in, #9@ 46

Key: No key defined

Min footing T&S reinf Area 1.04 in<sup>2</sup>  
Min footing T&S reinf Area per fc 0.26 in<sup>2</sup> /ft

If one layer of horizontal bars: If two layers of horizontal bars:  
#4@ 9.26 in #4@ 18.52 in  
#5@ 14.35 in #5@ 28.70 in  
#6@ 20.37 in #6@ 40.74 in

Footing Torsion, T<sub>u</sub> = 0.00 ft-lbs  
Footing Allow. Torsion, phi T<sub>u</sub> = 0.00 ft-lbs

If torsion exceeds allowable, provide supplemental design for footing torsion.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
Dsgnr: Golberg  
Description....

Site Retaining Wall sch.

Page : 7  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Tilt

#### Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci

Horizontal Defl @ Top of Wall (approximate only) 0.033 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe.

because the wall would then tend to rotate into the retained soil.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 6 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 8  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Rebar Lap & Embedment Lengths Information

Stem Design Segment: Bottom

Stem Design Height: 0.00 ft above top of footing

Lap Splice length for #4 bar specified in this stem design segment = 18.72 in

Development length for #4 bar specified in this stem design segment = 14.40 in

Hooked embedment length into footing for #4 bar specified in this stem design segment = 8.40 in

As Provided = 0.2667 in<sup>2</sup>/ft

As Required = 0.1728 in<sup>2</sup>/ft

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
Dsgnr: Golberg  
Description....  
Site Retaining Wall sch.

Page : 1  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\


RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Criteria

Retained Height	=	7.00 ft
Wall height above soil	=	0.00 ft
Slope Behind Wall	=	0.00
Height of Soil over Toe	=	6.00 in
Water height over heel	=	0.0 ft



### Load Factors

Building Code	IBC 2018,ACI
Dead Load	1.200
Live Load	1.600
Earth, H	1.600
Wind, W	1.000
Seismic, E	1.000

### Soil Data and Lateral Earth Pressure

Allow Soil Bearing	=	2,300.0 psf	Soil Density, Heel	=	110.00 pcf
Equivalent Fluid Pressure Method			Soil Density, Toe	=	0.00 pcf
Active Heel Pressure	=	40.0 psf/ft	Footings  Soil Friction	=	0.400
	=		Soil height to ignore for passive pressure	=	12.00 in
Passive Pressure	=	250.0 psf/ft			

### Surcharge Loads

Surcharge Over Heel	=	0.0 psf	Surcharge Over Toe	=	0.0
Used To Resist Sliding & Overturning			Used for Sliding & Overturning		

### Axial Load Applied to Stem

Axial Dead Load	=	0.0 lbs	Axial Load Eccentricity	=	0.0 in
Axial Live Load	=	0.0 lbs			

### Lateral Load Applied to Stem

Lateral Load	=	0.0 #/ft
...Height to Top	=	0.00 ft
...Height to Bottom	=	0.00 ft
Load Type	=	Wind (W) (Service Level)

### Wind on Exposed Stem

Wind on Exposed Stem (Service Level)	=	0.0 psf
---	---	---------

### Adjacent Footing Load

Adjacent Footing Load	=	0.0 lbs	Footing Type	Line Load
Footing Width	=	0.00 ft	Base Above/Below Soil	
Eccentricity	=	0.00 in	at Back of Wall	= 0.0 ft
Wall to Ftg CL Dist	=	0.00 ft	Poisson's Ratio	= 0.300

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
Dsgnr: Golberg  
Description....

Page : 2  
Date: 9 MAY 2022

Site Retaining Wall sch.

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Earth Pressure Seismic Load

Method : Triangular

Load at bottom of Triangular Distribution . . . . .	=	343.000 psf	Total Strength-Level Seismic Load. . . . .	=	1,372.000 lbs
Strength-Level)			Total Service-Level Seismic Load. . . . .	=	960.400 lbs

James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
 Dsgnr: Golberg  
 Description...  
 Site Retaining Wall sch.

Page : 3  
 Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018, ACI 318-14, TMS 402-16

### Wall Design Summary

#### Stability Ratios

Overturning = 2.14 OK  
 Slab Resists All Sliding !

#### Soil Bearing

Total Bearing Load = 3,707 lbs  
 ...resultant ecc. = 10.87 in

Soil Pressure @ Toe = 1,340 psf OK  
 Soil Pressure @ Heel = 8 psf OK  
 Allowable = 2,300 psf  
 Soil Pressure Less Than Allowable

ACI Factored @ Toe = 1,876 psf  
 ACI Factored @ Heel = 11 psf

Footing Shear @ Toe = 17.6 psi OK  
 Footing Shear @ Heel = 15.2 psi OK  
 Allowable = 75.0 psi

### Overturning

#### Resisting Moments

<u>Resisting Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Soil Over Heel (above water table, if any)	2,181.7 lbs	4.08 ft	8,908.5ft-#
Soil Over Heel (below water table, if any)	0.0		
Water Table	0.0		
Soil Over Heel	2,181.7	4.08	8,908.5
Sloped Soil Over Heel	0.0		
Surcharge Over Heel	0.0		
Adjacent Footing Load	0.0		
Axial Dead Load on Stem	0.0		
Axial Live Load on Stem *	0.0		
Soil Over Toe	0.0	1.00	
Surcharge Over Toe	0.0		
Stem Weight(s)	700.0	2.33	1,633.3
Earth @ Stem Transitions	0.0		
Footing Weight	825.0	2.75	2,268.8
Key Weight	0.0	2.00	
Vert. Component	0.0		

**Total Vertical Loads** 3,706.7 lbs

**Resisting Moment**

**12,810.6 ft-#**

**Eccentricity**

**10.9 in**

\* Axial live load NOT included in total displayed, or used for overturning or sliding resistance, but is included for soil pressure calculations.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
Dsgnr: Golberg  
Description....

Site Retaining Wall sch.

Page : 4  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Overturning

#### Overturning Moments

<u>Overturning Moments</u>	<u>Force</u>	<u>Distance</u>	<u>Moment</u>
Heel Active Pressure (above water table, if any)	1,280.0 lbs	2.67 ft	3,413.3 ft-#
Heel Active Pressure (below water table, if any)	0.0		
Hydrostatic Force	0.0		
Buoyant Force	0.0		
Surcharge over Heel	0.0		
Adjacent Footing	0.0		
Surcharge Over Toe	0.0		
Load @ Stem Above Soil	0.0		
Added Lateral Load	0.0		
Seismic Load	960.4	2.67	2,561.1
Seismic-Self-weight	0.0		
<b>Totals =</b>	2,240.4 lbs		
	<b>Overturning Moment</b>		5,974.4 ft-#

James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
 Dsgnr: Golberg  
 Description....  
 Site Retaining Wall sch.

Page : 5  
 Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Stem Design Summary

Bottom		
		Stem OK
Design Height Above Ftg	ft =	0.00
Wall Material Above "Ht"	=	Concrete
Design Method	=	LRFD
Thickness	=	8.00
Rebar Size	= #	4
Rebar Spacing	=	9.00
Rebar Placed at	=	Edge
<b>Design Data</b>		
fb/FB + fa/Fa	=	0.857
<b>Total Force @ Section</b>		
Service Level	lbs =	
Strength Level	lbs =	2,618.4
<b>Moment....Actual</b>		
Service Level	ft-# =	
Strength Level	ft-# =	6,109.7
Moment.....Allowable	=	7,122.4
<b>Shear.....Actual</b>		
Service Level	psi =	
Strength Level	psi =	34.9
Shear.....Allowable	psi =	75.0
Anet	in2 =	
Rebar Depth 'd'	in =	6.25
<b>Masonry Data</b>		
f <sub>m</sub>	psi =	
F <sub>s</sub>	psi =	
Solid Grouting	=	
Modular Ratio 'n'	=	
Wall Weight	psf =	100.0
Short Term Factor	=	
Equiv. Solid Thick.	=	
Masonry Block Type	=	Medium Weight
Masonry Design Method	=	ASD
<b>Concrete Data</b>		
f <sub>c</sub>	psi =	2,500.0
F <sub>y</sub>	psi =	60,000.0



James G. Pierson, Inc.  
 610 SW Alder #918  
 Portland, OR 97205  
 503-226-1286  
 www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
 Dsgnr: Golberg  
 Description....  
 Site Retaining Wall sch.

Page : 6  
 Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
 License : KW-06056929  
 License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Concrete Stem Rebar Area Details

Bottom Stem	Vertical Reinforcing	Horizontal Reinforcing	
As (based on applied moment) :	0.2289 in2/ft		
(4/3) * As :	0.3052 in2/ft	Min Stem T&S Reinf Area 1.344 in2	
200bd/fy : 200(12)(6.25)/60000 :	0.25 in2/ft	Min Stem T&S Reinf Area per ft of stem Height : 0.192 in2/ft	
0.0018bh : 0.0018(12)(8) :	0.1728 in2/ft	Horizontal Reinforcing Options :	
	=====	One layer of : Two layers of :	
Required Area :	0.25 in2/ft	#4@ 12.50 in	#4@ 25.00 in
Provided Area :	0.2667 in2/ft	#5@ 19.38 in	#5@ 38.75 in
Maximum Area :	0.8467 in2/ft	#6@ 27.50 in	#6@ 55.00 in

### Footing Data

Toe Width	=	2.00 ft	f <sub>c</sub>	=	2,500 psi
Heel Width	=	3.50	F <sub>y</sub>	=	60,000 psi
Total Footing Width	=	5.50 ft	Footing Concrete Density	=	150.00 pcf
Footing Thickness	=	12.00 in	Min. As %	=	0.0018
Key Width	=	0.00 in	Rebar Cover @ Top	=	2.00 in
Key Depth	=	0.00 in	@ Bottom	=	3.00 in
Key Distance from Toe	=	2.00 ft			

### Footing Design Results

		Toe	Heel
Factored Pressure	=	1,876	11 psf
Mu' : Upward	=	39,594	1,330 ft-#
Mu' : Downward	=	5,904	4,431 ft-#
Mu: Design	=	1,395	-644 ft-#
Actual 1-Way Shear	=	17.59	15.22 psi
Allow 1-Way Shear	=	75.00	75.00 psi
Toe Reinforcing	=	# 4 @ 9.00 in	
Heel Reinforcing	=	# 4 @ 9.00 in	
Key Reinforcing	=	None Spec'd	

#### Other Acceptable Sizes & Spacings

Toe: #4@ 9.25 in, #5@ 14.34 in, #6@ 20.36 in, #7@ 27.77 in, #8@ 36.56 in, #9@ 46

Heel: #4@ 9.25 in, #5@ 14.34 in, #6@ 20.36 in, #7@ 27.77 in, #8@ 36.56 in, #9@ 46

Key: No key defined

Min footing T&S reinf Area 1.43 in2  
 Min footing T&S reinf Area per fc 0.26 in2 /ft

If one layer of horizontal bars:	If two layers of horizontal bars:
#4@ 9.26 in	#4@ 18.52 in
#5@ 14.35 in	#5@ 28.70 in
#6@ 20.37 in	#6@ 40.74 in

Footing Torsion, T<sub>u</sub> = 0.00 ft-lbs  
 Footing Allow. Torsion, phi T<sub>u</sub> = 0.00 ft-lbs

If torsion exceeds allowable, provide supplemental design for footing torsion.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
Dsgnr: Golberg  
Description....

Page : 7  
Date: 9 MAY 2022

Site Retaining Wall sch.

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Tilt

#### Horizontal Deflection at Top of Wall due to settlement of soil

(Deflection due to wall bending not considered)

Soil Spring Reaction Modulus 250.0 pci

Horizontal Defl @ Top of Wall (approximate only) 0.047 in

The above calculation is not valid if the heel soil bearing pressure exceeds that of the toe.

because the wall would then tend to rotate into the retained soil.

James G. Pierson, Inc.  
610 SW Alder #918  
Portland, OR 97205  
503-226-1286  
www.jgpierson.com

Project Name/Number : agate - retai

Title 8 ft :  
Dsgnr: Golberg  
Description....

Site Retaining Wall sch.

Page : 8  
Date: 9 MAY 2022

This Wall in File: X:\Residential Projects\Residential Projects 2019\4145 SW Agate - Butler Design\

RetainPro (c) 1987-2019, Build 11.19.11.12  
License : KW-06056929  
License To : JAMES G. PIERSON

## Cantilevered Retaining Wall

Code: IBC 2018,ACI 318-14,TMS 402-16

### Rebar Lap & Embedment Lengths Information

Stem Design Segment: Bottom

Stem Design Height: 0.00 ft above top of footing

Lap Splice length for #4 bar specified in this stem design segment = 18.72 in

Development length for #4 bar specified in this stem design segment = 14.40 in

Hooked embedment length into footing for #4 bar specified in this stem design segment = 8.40 in

As Provided = 0.2667 in2/ft

As Required = 0.2500 in2/ft